

**DRAFT  
TOXICOLOGICAL PROFILE FOR  
ETHYLBENZENE**

U.S. DEPARTMENT OF HEALTH AND HUMAN SERVICES  
Public Health Service  
Agency for Toxic Substances and Disease Registry

September 2007

Additional Resources  
<http://www.atsdr.cdc.gov/toxprofiles/tp110.html>

## DISCLAIMER

The use of company or product name(s) is for identification only and does not imply endorsement by the Agency for Toxic Substances and Disease Registry.

This information is distributed solely for the purpose of pre dissemination public comment under applicable information quality guidelines. It has not been formally disseminated by the Agency for Toxic Substances and Disease Registry. It does not represent and should not be construed to represent any agency determination or policy.

## UPDATE STATEMENT

A Toxicological Profile for Ethylbenzene was released in 1999. This present edition supersedes any previously released draft or final profile.

Toxicological profiles are revised and republished as necessary. For information regarding the update status of previously released profiles, contact ATSDR at:

Agency for Toxic Substances and Disease Registry  
Division of Toxicology and Environmental Medicine/Applied Toxicology Branch  
1600 Clifton Road NE  
Mailstop F-32  
Atlanta, Georgia 30333

This page is intentionally blank.

## FOREWORD

This toxicological profile is prepared in accordance with guidelines developed by the Agency for Toxic Substances and Disease Registry (ATSDR) and the Environmental Protection Agency (EPA). The original guidelines were published in the *Federal Register* on April 17, 1987. Each profile will be revised and republished as necessary.

The ATSDR toxicological profile succinctly characterizes the toxicologic and adverse health effects information for the hazardous substance described therein. Each peer-reviewed profile identifies and reviews the key literature that describes a hazardous substance's toxicologic properties. Other pertinent literature is also presented, but is described in less detail than the key studies. The profile is not intended to be an exhaustive document; however, more comprehensive sources of specialty information are referenced.

The focus of the profiles is on health and toxicologic information; therefore, each toxicological profile begins with a public health statement that describes, in nontechnical language, a substance's relevant toxicological properties. Following the public health statement is information concerning levels of significant human exposure and, where known, significant health effects. The adequacy of information to determine a substance's health effects is described in a health effects summary. Data needs that are of significance to protection of public health are identified by ATSDR and EPA.

Each profile includes the following:

- (A) The examination, summary, and interpretation of available toxicologic information and epidemiologic evaluations on a hazardous substance to ascertain the levels of significant human exposure for the substance and the associated acute, subacute, and chronic health effects;
- (B) A determination of whether adequate information on the health effects of each substance is available or in the process of development to determine levels of exposure that present a significant risk to human health of acute, subacute, and chronic health effects; and
- (C) Where appropriate, identification of toxicologic testing needed to identify the types or levels of exposure that may present significant risk of adverse health effects in humans.

The principal audiences for the toxicological profiles are health professionals at the Federal, State, and local levels; interested private sector organizations and groups; and members of the public. We plan to revise these documents in response to public comments and as additional data become available. Therefore, we encourage comments that will make the toxicological profile series of the greatest use.

Comments should be sent to:

Agency for Toxic Substances and Disease Registry  
Division of Toxicology and Environmental Medicine  
1600 Clifton Road, N.E.  
Mail Stop F-32  
Atlanta, Georgia 30333


The toxicological profiles are developed in response to the Superfund Amendments and Reauthorization Act (SARA) of 1986 (Public Law 99-499) which amended the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA or Superfund). This public law directed ATSDR to prepare toxicological profiles for hazardous substances most commonly found at facilities on the CERCLA National Priorities List and that pose the most significant potential threat to human health, as determined by ATSDR and the EPA. The availability of the revised priority list of 275 hazardous substances was announced in the *Federal Register* on December 7, 2005 (70 FR 72840). For prior versions of the list of substances, see *Federal Register* notices dated April 17, 1987 (52 FR 12866); October 20, 1988 (53 FR 41280); October 26, 1989 (54 FR 43619); October 17, 1990 (55 FR 42067); October 17, 1991 (56 FR 52166); October 28, 1992 (57 FR 48801); February 28, 1994 (59 FR 9486); April 29, 1996 (61 FR 18744); November 17, 1997 (62 FR 61332); October 21, 1999 (64 FR 56792); October 25, 2001 (66 FR 54014); and November 7, 2003 (68 FR 63098). Section 104(i)(3) of CERCLA, as amended, directs the Administrator of ATSDR to prepare a toxicological profile for each substance on the list.

This profile reflects ATSDR's assessment of all relevant toxicologic testing and information that has been peer-reviewed. Staff of the Centers for Disease Control and Prevention and other Federal scientists have also reviewed the profile. In addition, this profile has been peer-reviewed by a nongovernmental panel and is being made available for public review. Final responsibility for the contents and views expressed in this toxicological profile resides with ATSDR.



Howard Frumkin, M.D., Dr. P.H.  
Director

National Center for Environmental Health/  
Agency for Toxic Substances and  
Disease Registry



Julie Louise Gerberding, M.D., M.P.H.  
Administrator

Agency for Toxic Substances and  
Disease Registry

## QUICK REFERENCE FOR HEALTH CARE PROVIDERS

Toxicological Profiles are a unique compilation of toxicological information on a given hazardous substance. Each profile reflects a comprehensive and extensive evaluation, summary, and interpretation of available toxicologic and epidemiologic information on a substance. Health care providers treating patients potentially exposed to hazardous substances will find the following information helpful for fast answers to often-asked questions.

---

### *Primary Chapters/Sections of Interest*

**Chapter 1: Public Health Statement:** The Public Health Statement can be a useful tool for educating patients about possible exposure to a hazardous substance. It explains a substance's relevant toxicologic properties in a nontechnical, question-and-answer format, and it includes a review of the general health effects observed following exposure.

**Chapter 2: Relevance to Public Health:** The Relevance to Public Health Section evaluates, interprets, and assesses the significance of toxicity data to human health.

**Chapter 3: Health Effects:** Specific health effects of a given hazardous compound are reported by type of health effect (death, systemic, immunologic, reproductive), by route of exposure, and by length of exposure (acute, intermediate, and chronic). In addition, both human and animal studies are reported in this section.

**NOTE:** Not all health effects reported in this section are necessarily observed in the clinical setting. Please refer to the Public Health Statement to identify general health effects observed following exposure.

**Pediatrics:** Four new sections have been added to each Toxicological Profile to address child health issues:

- Section 1.6**     **How Can (Chemical X) Affect Children?**
- Section 1.7**     **How Can Families Reduce the Risk of Exposure to (Chemical X)?**
- Section 3.7**     **Children's Susceptibility**
- Section 6.6**     **Exposures of Children**

### **Other Sections of Interest:**

- Section 3.8**     **Biomarkers of Exposure and Effect**
  - Section 3.11**   **Methods for Reducing Toxic Effects**
- 

### **ATSDR Information Center**

**Phone:** 1-800-CDC-INFO (800-232-4636)     **Fax:** (770) 488-4178  
or 1-888-232-6348 (TTY)

**E-mail:** cdcinfo@cdc.gov     **Internet:** <http://www.atsdr.cdc.gov>

The following additional material can be ordered through the ATSDR Information Center:

*Case Studies in Environmental Medicine: Taking an Exposure History*—The importance of taking an exposure history and how to conduct one are described, and an example of a thorough exposure history is provided. Other case studies of interest include *Reproductive and Developmental Hazards*; *Skin Lesions and Environmental Exposures*; *Cholinesterase-Inhibiting Pesticide Toxicity*; and numerous chemical-specific case studies.

*Managing Hazardous Materials Incidents* is a three-volume set of recommendations for on-scene (prehospital) and hospital medical management of patients exposed during a hazardous materials incident. Volumes I and II are planning guides to assist first responders and hospital emergency department personnel in planning for incidents that involve hazardous materials. Volume III—*Medical Management Guidelines for Acute Chemical Exposures*—is a guide for health care professionals treating patients exposed to hazardous materials.

*Fact Sheets (ToxFAQs)* provide answers to frequently asked questions about toxic substances.

---

### ***Other Agencies and Organizations***

*The National Center for Environmental Health (NCEH)* focuses on preventing or controlling disease, injury, and disability related to the interactions between people and their environment outside the workplace. Contact: NCEH, Mailstop F-29, 4770 Buford Highway, NE, Atlanta, GA 30341-3724 • Phone: 770-488-7000 • FAX: 770-488-7015.

*The National Institute for Occupational Safety and Health (NIOSH)* conducts research on occupational diseases and injuries, responds to requests for assistance by investigating problems of health and safety in the workplace, recommends standards to the Occupational Safety and Health Administration (OSHA) and the Mine Safety and Health Administration (MSHA), and trains professionals in occupational safety and health. Contact: NIOSH, 200 Independence Avenue, SW, Washington, DC 20201 • Phone: 800-356-4674 or NIOSH Technical Information Branch, Robert A. Taft Laboratory, Mailstop C-19, 4676 Columbia Parkway, Cincinnati, OH 45226-1998 • Phone: 800-35-NIOSH.

*The National Institute of Environmental Health Sciences (NIEHS)* is the principal federal agency for biomedical research on the effects of chemical, physical, and biologic environmental agents on human health and well-being. Contact: NIEHS, PO Box 12233, 104 T.W. Alexander Drive, Research Triangle Park, NC 27709 • Phone: 919-541-3212.

---

### ***Referrals***

*The Association of Occupational and Environmental Clinics (AOEC)* has developed a network of clinics in the United States to provide expertise in occupational and environmental issues. Contact: AOEC, 1010 Vermont Avenue, NW, #513, Washington, DC 20005 • Phone: 202-347-4976 • FAX: 202-347-4950 • e-mail: AOEC@AOEC.ORG • Web Page: <http://www.aoec.org/>.

*The American College of Occupational and Environmental Medicine (ACOEM)* is an association of physicians and other health care providers specializing in the field of occupational and environmental medicine. Contact: ACOEM, 25 Northwest Point Boulevard, Suite 700, Elk Grove Village, IL 60007-1030 • Phone: 847-818-1800 • FAX: 847-818-9266.



## CONTRIBUTORS

### CHEMICAL MANAGER(S)/AUTHOR(S):

Jessilynn Taylor, M.S.  
Henry Abadin, M.S.P.H.  
Heraline Hicks  
Oscar Tarrago, M.D., M.P.H.  
Diana Cronin  
ATSDR, Division of Toxicology and Environmental Medicine, Atlanta, GA

Julie M. Klotzbach, Ph.D.,  
Mario Citra, Ph.D.,  
Antonio Quiñones-Rivera, Ph.D.  
Syracuse Research Corporation, North Syracuse, NY

### THE PROFILE HAS UNDERGONE THE FOLLOWING ATSDR INTERNAL REVIEWS:

1. Health Effects Review. The Health Effects Review Committee examines the health effects chapter of each profile for consistency and accuracy in interpreting health effects and classifying end points.
2. Minimal Risk Level Review. The Minimal Risk Level Workgroup considers issues relevant to substance-specific Minimal Risk Levels (MRLs), reviews the health effects database of each profile, and makes recommendations for derivation of MRLs.
3. Data Needs Review. The Applied Toxicology Branch reviews data needs sections to assure consistency across profiles and adherence to instructions in the Guidance.
4. Green Border Review. Green Border review assures the consistency with ATSDR policy.

This page is intentionally blank.

## PEER REVIEW

A peer review panel was assembled for ethylbenzene. The panel consisted of the following members:

1. John DeSesso, Ph.D., Senior Fellow, Noblis, Falls Church, VA;
2. James McDougal, Ph.D., Professor and Director of Toxicology Research, Boonshoft School of Medicine, Wright State University, Department of Pharmacology and Toxicology, Dayton, OH;
3. Andrew Salmon, Ph.D., Senior Toxicologist and Chief, Air Toxicology and Risk Assessment Unit, Office of Environmental Health Hazard Assessment, California Environmental Protection Agency, Oakland, CA

These experts collectively have knowledge of ethylbenzene's physical and chemical properties, toxicokinetics, key health end points, mechanisms of action, human and animal exposure, and quantification of risk to humans. All reviewers were selected in conformity with the conditions for peer review specified in Section 104(I)(13) of the Comprehensive Environmental Response, Compensation, and Liability Act, as amended.

Scientists from the Agency for Toxic Substances and Disease Registry (ATSDR) have reviewed the peer reviewers' comments and determined which comments will be included in the profile. A listing of the peer reviewers' comments not incorporated in the profile, with a brief explanation of the rationale for their exclusion, exists as part of the administrative record for this compound.

The citation of the peer review panel should not be understood to imply its approval of the profile's final content. The responsibility for the content of this profile lies with the ATSDR.

This page is intentionally blank.

## CONTENTS

DISCLAIMER .....	ii
UPDATE STATEMENT .....	iii
FOREWORD .....	v
QUICK REFERENCE FOR HEALTH CARE PROVIDERS.....	vii
CONTRIBUTORS .....	ix
PEER REVIEW .....	xi
CONTENTS.....	xiii
LIST OF FIGURES .....	xvii
LIST OF TABLES .....	xix
1. PUBLIC HEALTH STATEMENT.....	1
2. RELEVANCE TO PUBLIC HEALTH .....	9
2.1 BACKGROUND AND ENVIRONMENTAL EXPOSURES TO ETHYLBENZENE IN THE UNITED STATES .....	9
2.2 SUMMARY OF HEALTH EFFECTS.....	10
2.3 MINIMAL RISK LEVELS (MRLs) .....	15
3. HEALTH EFFECTS .....	31
3.1 INTRODUCTION.....	31
3.2 DISCUSSION OF HEALTH EFFECTS BY ROUTE OF EXPOSURE .....	31
3.2.1 Inhalation Exposure .....	32
3.2.1.1 Death.....	32
3.2.1.2 Systemic Effects.....	33
3.2.1.3 Immunological and Lymphoreticular Effects .....	64
3.2.1.4 Neurological Effects .....	65
3.2.1.5 Reproductive Effects.....	67
3.2.1.6 Developmental Effects.....	69
3.2.1.7 Cancer .....	72
3.2.2 Oral Exposure.....	73
3.2.2.1 Death.....	73
3.2.2.2 Systemic Effects.....	73
3.2.2.3 Immunological and Lymphoreticular Effects .....	81
3.2.2.4 Neurological Effects .....	82
3.2.2.5 Reproductive Effects.....	82
3.2.2.6 Developmental Effects.....	83
3.2.2.7 Cancer .....	83
3.2.3 Dermal Exposure.....	83
3.2.3.1 Death.....	83
3.2.3.2 Systemic Effects.....	84
3.2.3.3 Immunological and Lymphoreticular Effects .....	86
3.2.3.4 Neurological Effects .....	86
3.2.3.5 Reproductive Effects.....	86
3.2.3.6 Developmental Effects.....	86
3.2.3.7 Cancer .....	86
3.3 GENOTOXICITY .....	86
3.4 TOXICOKINETICS.....	90
3.4.1 Absorption.....	90
3.4.1.1 Inhalation Exposure .....	90

3.4.1.2	Oral Exposure .....	91
3.4.1.3	Dermal Exposure .....	92
3.4.2	Distribution .....	93
3.4.2.1	Inhalation Exposure .....	93
3.4.2.2	Oral Exposure .....	94
3.4.2.3	Dermal Exposure .....	94
3.4.3	Metabolism.....	94
3.4.4	Elimination and Excretion.....	98
3.4.4.1	Inhalation Exposure .....	98
3.4.4.2	Oral Exposure .....	100
3.4.4.3	Dermal Exposure .....	101
3.4.5	Physiologically Based Pharmacokinetic (PBPK)/Pharmacodynamic (PD) Models .....	101
3.5	MECHANISMS OF ACTION .....	114
3.5.1	Pharmacokinetic Mechanisms.....	114
3.5.2	Mechanisms of Toxicity.....	115
3.5.3	Animal-to-Human Extrapolations .....	116
3.6	TOXICITIES MEDIATED THROUGH THE NEUROENDOCRINE AXIS .....	117
3.7	CHILDREN'S SUSCEPTIBILITY .....	118
3.8	BIOMARKERS OF EXPOSURE AND EFFECT .....	120
3.8.1	Biomarkers Used to Identify or Quantify Exposure to Ethylbenzene.....	121
3.8.2	Biomarkers Used to Characterize Effects Caused by Ethylbenzene .....	122
3.9	INTERACTIONS WITH OTHER CHEMICALS .....	123
3.10	POPULATIONS THAT ARE UNUSUALLY SUSCEPTIBLE .....	123
3.11	METHODS FOR REDUCING TOXIC EFFECTS .....	124
3.11.1	Reducing Peak Absorption Following Exposure.....	125
3.11.2	Reducing Body Burden .....	125
3.11.3	Interfering with the Mechanism of Action for Toxic Effects .....	125
3.12	ADEQUACY OF THE DATABASE.....	126
3.12.1	Existing Information on Health Effects of Ethylbenzene.....	126
3.12.2	Identification of Data Needs.....	128
3.12.3	Ongoing Studies .....	135
4.	CHEMICAL AND PHYSICAL INFORMATION.....	139
4.1	CHEMICAL IDENTITY.....	139
4.2	PHYSICAL AND CHEMICAL PROPERTIES.....	139
5.	PRODUCTION, IMPORT/EXPORT, USE, AND DISPOSAL.....	143
5.1	PRODUCTION .....	143
5.2	IMPORT/EXPORT .....	143
5.3	USE .....	148
5.4	DISPOSAL.....	148
6.	POTENTIAL FOR HUMAN EXPOSURE.....	151
6.1	OVERVIEW.....	151
6.2	RELEASES TO THE ENVIRONMENT .....	154
6.2.1	Air .....	154
6.2.2	Water.....	158
6.2.3	Soil .....	158
6.3	ENVIRONMENTAL FATE .....	159
6.3.1	Transport and Partitioning.....	159
6.3.2	Transformation and Degradation .....	161

6.3.2.1	Air .....	161
6.3.2.2	Water .....	162
6.3.2.3	Sediment and Soil .....	166
6.4	LEVELS MONITORED OR ESTIMATED IN THE ENVIRONMENT .....	167
6.4.1	Air .....	167
6.4.2	Water .....	172
6.4.3	Sediment and Soil .....	175
6.4.4	Other Environmental Media .....	175
6.5	GENERAL POPULATION AND OCCUPATIONAL EXPOSURE .....	177
6.6	EXPOSURES OF CHILDREN .....	181
6.7	POPULATIONS WITH POTENTIALLY HIGH EXPOSURES .....	183
6.8	ADEQUACY OF THE DATABASE .....	184
6.8.1	Identification of Data Needs .....	184
6.8.2	Ongoing Studies .....	188
7.	ANALYTICAL METHODS .....	191
7.1	BIOLOGICAL MATERIALS .....	191
7.2	ENVIRONMENTAL SAMPLES .....	194
7.3	ADEQUACY OF THE DATABASE .....	199
7.3.1	Identification of Data Needs .....	200
7.3.2	Ongoing Studies .....	202
8.	REGULATIONS AND ADVISORIES .....	205
9.	REFERENCES .....	211
10.	GLOSSARY .....	263
APPENDICES		
A.	ATSDR MINIMAL RISK LEVELS AND WORKSHEETS .....	A-1
B.	USER'S GUIDE .....	B-1
C.	ACRONYMS, ABBREVIATIONS, AND SYMBOLS .....	C-1
D.	INDEX .....	D-1

This page is intentionally blank.



## LIST OF FIGURES

2-1. Predicted (Log-Probit Model) and Observed Incidence of Centrilobular Hepatocyte Hypertrophy in Male Rats Exposed to Oral Ethylbenzene by Gavage for 13 Weeks.....	28
3-1. Levels of Significant Exposure to Ethylbenzene - Inhalation .....	53
3-2. Levels of Significant Exposure to Ethylbenzene - Oral .....	78
3-3. Metabolic Scheme for Ethylbenzene in Humans.....	95
3-4. Conceptual Representation of a Physiologically Based Pharmacokinetic (PBPK) Model for a Hypothetical Chemical Substance.....	104
3-5. Schematic Representation of the Model of Dermal Absorption.....	112
3-6. Existing Information on Health Effects of Ethylbenzene.....	127
6-1. Frequency of NPL Sites with Ethylbenzene Contamination .....	152
6-2. Major Degradation Pathways for Ethylbenzene in the Atmosphere.....	163
6-3. Major Degradation Pathways for Ethylbenzene in Water, Sediment, and Soil .....	164

This page is intentionally blank.

## LIST OF TABLES

3-1. Levels of Significant Exposure to Ethylbenzene - Inhalation .....	34
3-2. Levels of Significant Exposure to Ethylbenzene - Oral .....	74
3-3. Levels of Significant Exposure to Ethylbenzene - Dermal.....	85
3-4. Genotoxicity of Ethylbenzene <i>In Vivo</i> .....	87
3-5. Genotoxicity of Ethylbenzene <i>In Vitro</i> .....	89
3-6. Parameter Values for Tardif et al. (1997) Ethylbenzene PBPK Models .....	105
3-7. Parameter Values for Dennison et al. (2003) Ethylbenzene PBPK Model.....	109
3-8. Parameters Used in the Shatkin and Brown PBPK Model of Dermal Absorption of Ethylbenzene .....	113
3-9. Ongoing Studies on Ethylbenzene.....	136
4-1. Chemical Identity of Ethylbenzene .....	140
4-2. Physical and Chemical Properties of Ethylbenzene .....	141
5-1. Ethylbenzene Production in the United States from 1983 to 2005.....	144
5-2. Facilities that Produce, Process, or Use Ethylbenzene .....	145
5-3. Manufacturers and Annual Production Capacity of Ethylbenzene.....	147
6-1. Releases to the Environment from Facilities that Produce, Process, or Use Ethylbenzene.....	155
6-2. Ethylbenzene Concentrations in Ambient Air Samples Collected in the United States .....	171
6-3. Distribution of Blood Ethylbenzene Concentrations in Children (ng/mL).....	182
6-4. Ongoing Research Regarding the Environmental Fate and Exposure to Ethylbenzene .....	189
7-1. Analytical Methods for Determining Ethylbenzene in Biological Samples .....	192
7-2. Analytical Methods for Determining Ethylbenzene in Environmental Samples.....	195
7-3. Analytical Methods for Determining Biomarkers of Ethylbenzene in Biological Materials .....	201
7-4. Analytical Methods for Determining Environmental Degradation Products of Ethylbenzene .....	203
8-1. Regulations and Guidelines Applicable to Ethylbenzene.....	207

This page is intentionally blank.

## 1. PUBLIC HEALTH STATEMENT

This public health statement tells you about ethylbenzene and the effects of exposure to it.

The Environmental Protection Agency (EPA) identifies the most serious hazardous waste sites in the nation. These sites are then placed on the National Priorities List (NPL) and are targeted for long-term federal clean-up activities. Ethylbenzene has been found in at least 829 of the 1,689 current or former NPL sites. Although the total number of NPL sites evaluated for this substance is not known, the possibility exists that the number of sites at which ethylbenzene is found may increase in the future as more sites are evaluated. This information is important because these sites may be sources of exposure and exposure to this substance may harm you.

When a substance is released either from a large area, such as an industrial plant, or from a container, such as a drum or bottle, it enters the environment. Such a release does not always lead to exposure. You can be exposed to a substance only when you come in contact with it. You may be exposed by breathing, eating, or drinking the substance, or by skin contact.

If you are exposed to ethylbenzene, many factors will determine whether you will be harmed. These factors include the dose (how much), the duration (how long), and how you come in contact with it. You must also consider any other chemicals you are exposed to and your age, sex, diet, family traits, lifestyle, and state of health.

### What is ethylbenzene?

<b><i>Colorless liquid that smells like gasoline</i></b>	You can smell ethylbenzene in the air at 2 parts of ethylbenzene per million parts of air (2 ppm). It evaporates at room temperature and burns easily.
<b><i>Used in industry and in consumer products</i></b>	Ethylbenzene is found naturally in oil. Large amounts of ethylbenzene are produced in the United States. Most of it is used to make styrene. Ethylbenzene is also used in fuels.  Consumer products containing ethylbenzene include: <ul style="list-style-type: none"> <li>• gasoline</li> <li>• paints and inks</li> <li>• pesticides</li> <li>• carpet glues</li> <li>• varnishes and paints</li> <li>• tobacco products</li> </ul>

## 1. PUBLIC HEALTH STATEMENT

For more information on the physical and chemical properties of ethylbenzene, and its production, disposal, and use, see Chapters 4 and 5.

### What happens to ethylbenzene when it enters the environment?

<b><i>Most commonly found in air</i></b>	Ethylbenzene moves easily into the air from water and soil. Ethylbenzene in soil can also contaminate groundwater.
<b><i>Rapidly broken down in air</i></b>	<p><i>Air:</i> Ethylbenzene in air is broken down in less than 3 days with the aid of sunlight.</p> <p><i>Water:</i> In surface water such as rivers and harbors, ethylbenzene breaks down by reacting with other compounds naturally present in water.</p> <p><i>Soil:</i> In the soil, ethylbenzene is broken down by soil bacteria.</p>

For more information on ethylbenzene in the environment, see Chapter 6.

### How might I be exposed to ethylbenzene?

<b><i>Air</i></b>	<p>If you live in a city or near many factories or heavily traveled highways, you may be exposed to ethylbenzene in the air. Releases of ethylbenzene into the air occur from burning oil, gas, and coal and from industries using ethylbenzene.</p> <p>The median levels of ethylbenzene in air are:</p> <ul style="list-style-type: none"> <li>• 0.62 ppb in city and suburban locations</li> <li>• 0.01 ppb in rural locations</li> <li>• 1 ppb in indoor air</li> </ul>
<b><i>Water</i></b>	<p>Ethylbenzene is infrequently detected in private and public groundwater wells used for drinking water. Higher levels of ethylbenzene may be found in private residential wells near landfills, waste sites, or leaking underground fuel storage tanks.</p> <p>People with ethylbenzene-contaminated tap water could be exposed by drinking the water or eating foods prepared with it. Exposure could also result from breathing in ethylbenzene while showering, bathing, or cooking with contaminated water.</p>
<b><i>Soil</i></b>	Background levels in soils have not been reported. Ethylbenzene may get into the soil by gasoline or other fuel spills and poor disposal of industrial and household wastes.

## 1. PUBLIC HEALTH STATEMENT

<b>Workplace air</b>	Gas and oil workers may be exposed to ethylbenzene either through skin contact or by breathing ethylbenzene vapors. Varnish workers, spray painters, and people involved in gluing operations may also be exposed to high levels of ethylbenzene. Exposure may also occur in factories that use ethylbenzene to produce other chemicals.
<b>Consumer products</b>	You might be exposed to ethylbenzene by using any of the following products: <ul style="list-style-type: none"> <li>• gasoline</li> <li>• carpet glues</li> <li>• varnishes and paints</li> <li>• tobacco products</li> </ul>

For more information on human exposure to ethylbenzene, see Chapter 6.

### How can ethylbenzene enter and leave my body?

<b>Rapidly enters your body</b>	When you breathe air containing ethylbenzene, it enters your body rapidly and almost completely through your lungs. Ethylbenzene in food or water may also rapidly and almost completely enter your body through the digestive tract. It may enter through your skin when you come into contact with liquids containing ethylbenzene.
<b>Typically leaves your body within 2 days</b>	Once in your body, ethylbenzene is broken down into other chemicals. Most of these other chemicals leave your body in the urine within 2 days.  Small amounts can also leave through the lungs and in feces.

For more information on how ethylbenzene enters and leaves the body, see Chapter 3.

### How can ethylbenzene affect my health?

Scientists use many tests to protect the public from harmful effects of toxic chemicals and to find ways for treating persons who have been harmed

The effect of ethylbenzene on human health depends on how much ethylbenzene is present, how you are exposed to it, and the length of exposure.

## 1. PUBLIC HEALTH STATEMENT

<b>Short-term exposure in air</b>	<p><i>Humans:</i> Exposure to high levels of ethylbenzene in the air for short periods can cause eye and throat irritation. Exposure to higher levels can result in vertigo and dizziness.</p> <p><i>Animals:</i> Exposure to very high levels (about 2 million times the usual level in urban air) can cause death.</p>
<b>Long-term exposure in air</b>	<p><i>Hearing:</i> Exposure to relatively low concentrations of ethylbenzene for several days to weeks resulted in potentially irreversible damage to the inner ear and hearing of animals.</p> <p><i>Kidney:</i> Exposures to relatively low concentrations of ethylbenzene for several months to years caused in kidney damage in animals.</p> <p><i>Reproduction:</i> There is no clear evidence that ethylbenzene affects fertility.</p> <p><i>Cancer:</i> An increase in kidney tumors in rats and lung and liver tumors in mice were found after they were exposed to ethylbenzene in air for 2 years. The International Agency for Research on Cancer (an expert group that is part of the World Health Organization) has determined on that long-term exposure to ethylbenzene may cause cancer in humans.</p>
<b>Long-term exposure by ingestion</b>	<p><i>Hearing:</i> Rats exposed to large amounts of ethylbenzene by mouth had severe damage to the inner ear.</p>
<b>Short-term eye and skin contact</b>	<p><i>Irritation:</i> Liquid ethylbenzene caused eye damage and skin irritation in rabbits.</p>

Further information on the health effects of ethylbenzene in humans and animals can be found in Chapters 2 and 3.

### How can ethylbenzene affect children?

This section discusses potential health effects in humans from exposures during the period from conception to maturity at 18 years of age.

<b>Children are likely to have similar effects as adults</b>	No information is available about the effect of exposure to ethylbenzene on children or immature animals. It is likely that children would show the same health effects as adults. We do not know whether children will have effects at the same exposure levels as adults.
<b>Birth defects</b>	We do not know whether ethylbenzene causes birth defects in people. Minor birth defects and low birth weights have occurred in newborn animals whose mothers were exposed air contaminated with ethylbenzene.
<b>Exposure from breast milk</b>	We do not know whether ethylbenzene can accumulate in breast milk.



## 1. PUBLIC HEALTH STATEMENT

**How can families reduce the risk of exposure to ethylbenzene?**

<b><i>Limit children's exposure to consumer products containing ethylbenzene</i></b>	<p>Use adequate ventilation to minimize exposure to ethylbenzene vapors from consumer products such as</p> <ul style="list-style-type: none"> <li>• gasoline</li> <li>• pesticides</li> <li>• varnishes and paints</li> <li>• newly installed carpeting</li> </ul> <p>Sometimes older children sniff household chemicals in an attempt to get high. Your children may be exposed to ethylbenzene by inhaling products containing it, such as paints, varnishes, or gasoline. Talk with your children about the dangers of sniffing chemicals.</p>
<b><i>Store household chemicals out of reach of young children</i></b>	<p>Always store household chemicals in their original labeled containers out of reach of young children to prevent accidental poisonings. Never store household chemicals in containers children would find attractive to eat or drink from, such as old soda bottles.</p> <p>Gasoline should be stored in a gasoline can with a locked cap.</p>
<b><i>Follow directions on label</i></b>	<p>Always follow directions on household products, such as use with good ventilation.</p>
<b><i>Limit exposure to tobacco smoke</i></b>	<p>Ethylbenzene is a component of tobacco smoke. Avoid smoking in enclosed spaces like inside the home or car in order to limit exposure to children and other family members.</p>

**Is there a medical test to determine whether I have been exposed to ethylbenzene?**

<b><i>Can be measured in blood and breath</i></b>	<p>Ethylbenzene can be measured in blood and in the breath of people exposed to ethylbenzene.</p> <p>This should be done within a few hours after exposure occurs because these metabolites leave the body very quickly.</p>
<b><i>Metabolites can be measured in urine</i></b>	<p>The presence of ethylbenzene breakdown products (metabolites) in urine might indicate that you were exposed to ethylbenzene; however, these breakdown products can also form when you are exposed to other substances, such as styrene.</p> <p>The detection of these metabolites in your urine cannot be used to predict the kind of health effects that might develop from that exposure.</p> <p>You should have this test done within a few hours after exposure occurs because these metabolites leave the body very quickly.</p>

For more information on the different substances formed by ethylbenzene breakdown and on tests to detect these substances in the body, see Chapters 3 and 7.

## 1. PUBLIC HEALTH STATEMENT

**What recommendations has the federal government made to protect human health?**

The federal government develops regulations and recommendations to protect public health. Regulations can be enforced by law. The EPA, the Occupational Safety and Health Administration (OSHA), and the Food and Drug Administration (FDA) are some federal agencies that develop regulations for toxic substances. Recommendations provide valuable guidelines to protect public health, but cannot be enforced by law. The Agency for Toxic Substances and Disease Registry (ATSDR) and the National Institute for Occupational Safety and Health (NIOSH) are two federal organizations that develop recommendations for toxic substances.

Regulations and recommendations can be expressed as “not-to-exceed” levels, that is, levels of a toxic substance in air, water, soil, or food that do not exceed a critical value that is usually based on levels that affect animals; they are then adjusted to levels that will help protect humans. Sometimes these not-to-exceed levels differ among federal organizations because they used different exposure times (an 8-hour workday or a 24-hour day), different animal studies, or other factors.

Recommendations and regulations are also updated periodically as more information becomes available. For the most current information, check with the federal agency or organization that provides it.

Some regulations and recommendations for ethylbenzene include the following:

<b><i>Levels in drinking water set by EPA</i></b>	The EPA has determined that exposure to ethylbenzene in drinking water at concentrations of 30 ppm for one day or 3 ppm for 10 days is not expected to cause any harmful effects in a child.  The EPA has determined that lifetime exposure to 0.7 ppm ethylbenzene is not expected to cause any harmful effects.
<b><i>Levels in surface water set by EPA</i></b>	If you eat fish and drink water from a body of water, the water should contain no more than 0.53 ppm ethylbenzene.
<b><i>Levels in workplace air set by OSHA</i></b>	OSHA set a legal limit of 100 ppm ethylbenzene in air averaged over an 8-hour work day.

For more information on regulations and advisories, see Chapter 8.

## 1. PUBLIC HEALTH STATEMENT

**Where can I get more information?**

If you have any more questions or concerns, please contact your community or state health or environmental quality department, or contact ATSDR at the address and phone number below.

ATSDR can also tell you the location of occupational and environmental health clinics. These clinics specialize in recognizing, evaluating, and treating illnesses that result from exposure to hazardous substances.

Toxicological profiles are also available on-line at [www.atsdr.cdc.gov](http://www.atsdr.cdc.gov) and on CD-ROM. You may request a copy of the ATSDR ToxProfiles™ CD-ROM by calling the toll-free information and technical assistance number at 1-800-CDCINFO (1-800-232-4636), by e-mail at [cdcinfo@cdc.gov](mailto:cdcinfo@cdc.gov), or by writing to:

Agency for Toxic Substances and Disease Registry  
Division of Toxicology and Environmental Medicine  
1600 Clifton Road NE  
Mailstop F-32  
Atlanta, GA 30333  
Fax: 1-770-488-4178

Organizations for-profit may request copies of final Toxicological Profiles from the following:

National Technical Information Service (NTIS)  
5285 Port Royal Road  
Springfield, VA 22161  
Phone: 1-800-553-6847 or 1-703-605-6000  
Web site: <http://www.ntis.gov/>

1. PUBLIC HEALTH STATEMENT

This page is intentionally blank.

## 2. RELEVANCE TO PUBLIC HEALTH

### 2.1 BACKGROUND AND ENVIRONMENTAL EXPOSURES TO ETHYLBENZENE IN THE UNITED STATES

Ethylbenzene is widely distributed in the environment. It is primarily used for the production of styrene, which is the monomeric unit for polystyrene materials. Ethylbenzene is also used as a solvent and in the manufacture of several organic compounds other than styrene; however, these uses are very minor in comparison to the amounts used for styrene production. The production volume of ethylbenzene is typically among the highest of all chemicals manufactured in the United States. In 2005, nearly 12 billion pounds of ethylbenzene were produced domestically, with historical levels ranging anywhere from approximately 7 to 13 billion pounds annually. Routine human activities, such as driving automobiles, boats, or aircraft, or using gasoline powered tools and equipment, release ethylbenzene to the environment. Environmental and background levels of ethylbenzene are generally small and therefore, have minimal impact on public health. Trace levels of ethylbenzene are found in internal combustion engine exhaust, food, soil, water, and tobacco smoke, but usually at levels well below those that have been shown to exhibit toxic effects in laboratory animals or human exposure studies.

Ethylbenzene is not considered highly persistent in the environment. It partitions primarily to air and removal via photochemically generated hydroxyl radicals is an important degradation mechanism. The half-life for this reaction in the atmosphere is approximately 1–2 days. Biodegradation under aerobic conditions and indirect photolysis are important degradation mechanisms for ethylbenzene in soil and water. Based on a vapor pressure of 9.53 mm Hg and Henry's law constant of  $7.9 \times 10^{-3}$  atm·m<sup>3</sup>/mol, volatilization from water and soil surfaces is expected to be an important environmental fate process for ethylbenzene. If released to soil, ethylbenzene is expected to possess moderate mobility based on a soil adsorption coefficient ( $K_{oc}$ ) value of 240.

Ethylbenzene is ubiquitous in ambient air, primarily as a result of automobile emissions. The median level of ethylbenzene in city and suburban air was reported as 2.7 µg/m<sup>3</sup> (0.62 ppb). In contrast, the median level of ethylbenzene measured in rural locations was 0.056 µg/m<sup>3</sup> (0.013 ppb). Ethylbenzene levels in indoor air tend to be higher than corresponding levels monitored in outdoor air, as a result of contributions from environmental tobacco smoke (ETS) and various consumer products, in addition to the permeation indoors of ethylbenzene from outside air. A study analyzed the components of ETS for the 50 top-selling U.S. cigarette brand styles in 1991 and for the University of Kentucky Research cigarette, K1R4F. The ethylbenzene concentrations measured were 8.68 µg/m<sup>3</sup> for full-flavor cigarettes,

## 2. RELEVANCE TO PUBLIC HEALTH

8.24  $\mu\text{g}/\text{m}^3$  for full-flavor, low-tar cigarettes, and 8.72  $\mu\text{g}/\text{m}^3$  for ultra-low-tar cigarettes. The mean ethylbenzene concentration for all cigarettes was 8.50  $\mu\text{g}/\text{m}^3$ . A study reported a maximum outdoor air concentration of 7.4  $\mu\text{g}/\text{m}^3$  (1.7 ppb) for ethylbenzene at four residential locations, while indoor air concentrations at these same homes ranged from 5 to 110  $\mu\text{g}/\text{m}^3$  (1–25.3 ppb). Ethylbenzene is detected infrequently in surface water. Data from the EPA STOrage and REtrieval Database (STORET), indicated that ethylbenzene was detected in <3% of the surface water samples analyzed in the United States from January 2005 to March 2007, with a maximum concentration of 2 ppb.

Ethylbenzene was identified in 82 different food items at a maximum concentration of 0.129 ppm in data obtained from the FDA Total Diet Study Market Basket Surveys collected between September 1991 and October 2003. Trace concentrations of ethylbenzene have been reported in split peas (0.013 mg/kg [ppm]), lentils (0.005 mg/kg [ppm]), and beans (mean concentration 0.005 mg/kg [ppm]; maximum concentration 0.011 mg/kg [ppm]).

The general population is primarily exposed to ethylbenzene from the inhalation of ambient air. This is due to the direct release of ethylbenzene into the air by the burning of fossil fuels or industrial processes, and partitioning into the air from other media (e.g., soil, surface water). This partitioning of ethylbenzene into the air or water would play a role in exposure to populations living near hazardous waste sites. In addition to inhalation exposure, ingestion of ethylbenzene may also occur because trace amounts have been found in water supplies and various food items.

## 2.2 SUMMARY OF HEALTH EFFECTS

In humans, eye irritation was observed after exposure to 10,000 ppm ethylbenzene for a few seconds. Volunteers reported irritation and chest constriction after acute-duration exposures to 2,000 ppm ethylbenzene. These symptoms worsened as the concentration was increased to 5,000 ppm. Human exposures in the range of 2,000–5,000 ppm ethylbenzene were associated with dizziness and vertigo. Complete recovery occurs if exposure is not prolonged. Momentary ocular irritation, a burning sensation, and profuse lacrimation were observed in humans exposed to 1,000 ppm ethylbenzene. Workers exposed occupationally to solvent mixtures that included ethylbenzene showed an increased incidence of hearing loss compared to unexposed individuals. Respiratory effects were not observed in two patients exposed to 55.3 ppm ethylbenzene for 15 minutes. An increase in the mean number of lymphocytes and a decrease in hemoglobin levels were observed during a 1-year period in workers exposed chronically to solvents including ethylbenzene. However, no adverse hematological effects were observed in workers

## 2. RELEVANCE TO PUBLIC HEALTH

exposed to ethylbenzene for 20 years. Although no information on ethylbenzene concentrations was reported, an estimated concentration of 6.4 mg/m<sup>3</sup> was derived from a mean post-shift in urinary mandelic acid concentration in workers, based on the relationship between ethylbenzene concentrations in air and urinary mandelic acid concentration in a chamber-exposed group. No liver lesions or differences in liver function tests between exposed and nonexposed workers were observed and no cases of malignancy in workers were reported. However, given the low exposure concentration, this study had limited the power to detect any effect. No other studies in humans exposed to ethylbenzene were located. Given that little data in humans are available, it is assumed that adverse effects observed in animals are relevant to humans.

Acute-duration and intermediate-duration studies in animals suggest that the auditory system is a sensitive target of ethylbenzene toxicity. Significant losses of outer hair cells (OHCs) in the organ of Corti have been observed in rats after acute-duration exposure  $\geq 400$  ppm and intermediate-duration inhalation exposure to  $\geq 200$  ppm ethylbenzene. These OHC losses have been observed up to 11 weeks after termination of the exposure, suggesting that these effects may be irreversible. Significant deterioration of auditory thresholds is also observed in animals affected with OHC losses. Auditory deficits have also been observed in animals after an intermediate-duration oral exposure to ethylbenzene. An almost complete loss of the three rows of outer hair cells in the organ of Corti was observed in rats 10 days after the last dose (900 mg/kg/day) in an acute-duration study. Effects on the central nervous system, such as moderate motor activation, narcotic effects, changes in posture and arousal, and salivation and prostration have been observed in animals after acute- and intermediate-duration exposure to  $\geq 400$  ppm ethylbenzene.

Results of 4- and 13-week studies indicate that intermediate-duration oral exposure to ethylbenzene produces effects to the liver. Effects indicative of liver toxicity observed included increased activity of serum liver enzymes (alanine aminotransferase [ALT] and gamma-glutamyltransferase [GGT]) in males ( $\geq 250$  mg/kg/day) and females (750 mg/mg/day), increased absolute and relative liver weights ( $\geq 250$  mg/kg/day in males and females), and a dose-related increase in the incidence of centrilobular hepatocyte hypertrophy ( $\geq 250$  mg/kg/day in males and females). Increased bilirubin ( $\leq 250$  mg/kg/day in males and 750 mg/kg/day in females), total protein (750 mg/kg/day in females), albumin (750 mg/kg/day in males and females), globulins (750 mg/kg/day in females), and cholesterol ( $\leq 250$  mg/kg/day in males and females), and decreased prothrombin time (750 mg/kg/day in males and  $\geq 250$  mg/kg/day in females) were considered by study investigators as adaptive effects in the liver. In males in the 75 mg/k/day group, relative liver weight was significantly increased by 4% compared to controls; however, no

## 2. RELEVANCE TO PUBLIC HEALTH

histopathological changes, or increases in absolute liver or serum liver enzyme activities were observed at this dosage. Given that ethylbenzene is a microsomal enzyme inducer, and the absence of histopathology and other evidence of liver injury at the 75 mg/kg/day dosage, the small increase in relative liver weight in male rats was at this dosage not considered evidence for an adverse effect on the liver. Results of the 4-week gavage study in rats were similar to those of the 13-week study, identifying no-observed-adverse-effect level (NOAEL) and lowest-observed-adverse-effect level (LOAEL) values of 250 and 750 mg/kg/day, respectively, for liver effects. Observed effects consistent with hepatotoxicity included increased absolute and relative liver weights ( $\geq 250$  mg/kg/day in males and 750 mg/kg/day in females), increased incidence of hepatocyte centrilobular ( $\geq 250$  mg/kg/day in males and 750 mg/kg/day in females), and increase serum liver enzyme activity (ALT) (750 mg/kg/day in males and females). Histopathological changes characterized by cloudy swelling of parenchymal cells of the liver and an increase in liver weight were observed in female rats administered 408 mg/kg/day by gavage for 6 months. No other hepatic changes were reported. No liver effects were observed in female rats administered 136 mg/kg/day. However, this study was poorly reported and did not provide adequate descriptions of study methods or results.

Guinea pigs exposed to sublethal concentrations of ethylbenzene ( $\leq 10,000$  ppm for <100 minutes) showed “moderate” pulmonary edema and congestion. These findings had disappeared in animals after a 4–8-day recovery period, suggesting that these pathological effects in the lung are reversible. A 50% respiratory depression was observed in mice exposed to  $\geq 1,432$  ppm for 5–30 minutes. Respiratory depression has not been reported in humans exposed to ethylbenzene. Nasal and eye irritation was evident in animals exposed to 1,000 ppm for  $\geq 3$  minutes. One study did not observe weight or histopathological effects in the lungs of rats or mice exposed to 782 ppm or rabbits exposed to 1,610 ppm ethylbenzene for 4 weeks. Absolute and relative lung weight was increased in rats, but not mice, exposed to  $\geq 250$  ppm for 13 weeks; no treatment-related histopathological effects were observed. One study did not report pulmonary injury in rats, guinea pigs, rabbits, or monkeys exposed to 600–2,200 ppm ethylbenzene for approximately 6 months; however, only two animals were used in some of the dose groups in rabbits and monkeys. No treatment-related histopathological effects were noted in respiratory tissue in rats or female mice exposed to up to 750 ppm ethylbenzene for 2 years. Although an increase in alveolar epithelial hyperplasia was noted in male mice in the 750-ppm group the incidence fell within historical controls for the conducting laboratory. The available data on adverse respiratory effects associated with ethylbenzene exposure in animals and the limited data available in humans suggest that respiratory effects in humans could result following inhalation exposure to high concentrations of



## 2. RELEVANCE TO PUBLIC HEALTH

ethylbenzene. Respiratory effects from low-level exposure, such as that found in the outdoor air, appear to be less likely.

Developmental effects have been reported in the offspring of pregnant animals exposed to ethylbenzene during gestation. The best reported studies available suggest that developmental effects are generally observed at concentrations of approximately  $\geq 1,000$  ppm. Significant increases in the incidence of fetal skeletal variations were observed in the offspring of pregnant rats exposed to 2,000 ppm and reductions in fetal body weight were observed in the offspring of pregnant rats exposed to  $\geq 1,000$  ppm ethylbenzene during gestation. Maternal toxicity, manifested as reduced body weight gain, was also observed in rats exposed to  $\geq 1,000$  ppm. No developmental effects were observed at concentrations of  $\leq 500$  ppm. In contrast, an increased incidence of fetuses with extra ribs was observed in the offspring of rats exposed to 100 ppm during gestation, but not when the animals were exposed to 100 ppm during pre-mating and gestation. No other significant increases in major malformations or minor anomalies were observed. Neurodevelopmental assessments conducted on F2 rat offspring indicated no effects in a functional observational battery assessment, fore- or hind-limb grip strength, swimming ability, motor activity, startle response, or learning and memory assessments at 500 ppm.

The number of implantations or live fetuses per litter and the percentage of resorptions or non-live implants per litter were unaffected in pregnant rats exposed to 2,000 ppm ethylbenzene during gestation. In a two-generation study, estrous cycle length was significantly reduced in F0, but not F1, females exposed to 500 ppm or in rats or mice exposed to 975 ppm ethylbenzene for 90 days. Reproductive parameters were not affected in F0 or F1 males or females at 500 ppm ethylbenzene. Exposure of rats and rabbits to 100 or 1,000 ppm ethylbenzene for 3 weeks during prior to mating or gestation or both resulted in no conclusive evidence of reproductive effects in either species. Assessments of reproductive organs conducted following intermediate- and chronic-duration exposure to ethylbenzene have not observed histopathological changes in the testes of rats, mice, or rabbits exposed to concentrations as high as 2,400 ppm ethylbenzene for 4 days or in rats or mice exposed to 782 ppm ethylbenzene or rabbits exposed to 1,610 ppm for 4 weeks. No effect was observed on spermatid counts, sperm motility, weight of the caudal epididymis, or testicular morphology in rats or mice exposed to 975 ppm ethylbenzene for 90 days. No adverse histopathological effects were seen in the testes of rats or guinea pigs exposed to concentrations up to 1,250 or 600 ppm, respectively, for 6–7 months.

Other systemic effects have been observed in animals after acute-, intermediate-, and chronic-duration exposures to ethylbenzene. Eye irritation and lacrimation have been observed after acute-duration

## 2. RELEVANCE TO PUBLIC HEALTH

exposures in rats, mice, and guinea pigs exposed to  $\geq 1,000$  ppm ethylbenzene. Lacrimation was observed in rats exposed to 382 ppm for 4 weeks. In contrast, no ocular effects were seen in rats or mice after a 13-week exposure to 975 ppm ethylbenzene. Mild irritation, reddening, exfoliation, and blistering have been reported in rabbits when ethylbenzene was applied directly on the skin. Slight irritation of the eye and corneal injuries were observed in rabbits when ethylbenzene was instilled onto the eyes.

One study examined the possible association between occupational exposure to ethylbenzene and increased cancer risk; no cases of malignancy were observed in workers exposed to ethylbenzene for 20 years. Animal studies have found increased incidences of neoplasms in rats and mice following inhalation or oral exposure, which are considered relevant to humans. The inhalation studies found clear evidence of carcinogenic activity in male rats based on increased incidences of renal tubule neoplasm's and testicular adenomas, some evidence of carcinogenic activity in female rats based on increased incidences of renal tubule adenomas, some evidence of carcinogenic activity in male mice based on increased incidences of alveolar/bronchiolar neoplasms, and some evidence of carcinogenic activity in female mice based on increased incidences of hepatocellular neoplasms. In a reevaluation of the histopathology of rat kidneys from the NTP study, a study confirmed the NTP findings and suggested that the increased incidence of kidney tumors in rats in the high-dose group was related to a chemical-induced exacerbation of chronic progressive nephropathy (CPN) with a minor contributing factor in male rats being  $\alpha_2\mu$ -globulin nephropathy. The author suggests that since CPN is an age-related disease of rodents without a counterpart in humans, the kidney results of the NTP study are not relevant to humans for risk assessment purposes. However, in an analysis of the association between CPN and renal tubule cell neoplasms in male F344 rats, a study concluded that the association between CPN and renal tubule cell neoplasms is marginal. Results of this analysis suggest that the number of renal tubule cell neoplasms secondary to CPN would be few. An increase in the total number of malignant tumors was observed in rats orally exposed to ethylbenzene; however, data on specific tumor types were not provided. On the basis of the NTP study, IARC has classified ethylbenzene as a Group 2B carcinogen (possibly carcinogenic to humans). In the most recent carcinogenicity assessment by the EPA conducted in 1991, ethylbenzene was classified as Group D (not classifiable as to human carcinogenicity) due to the lack of animal bioassays and human studies; however, the EPA assessment predated the NTP study. Ethylbenzene is not included in the NTP's Report on Carcinogens; however, this may reflect that NTP has not recently considered the carcinogenicity of ethylbenzene, rather than a judgment that ethylbenzene is not carcinogenic.

## 2. RELEVANCE TO PUBLIC HEALTH

Acute- and intermediate-duration studies provide strong evidence that ototoxicity is a sensitive effect following inhalation exposure to ethylbenzene. A more detailed discussion of this effect follows. The reader is referred to Section 3.2, Discussion of Health Effects by Route of Exposure, for additional information on other effects.

A study of workers exposed occupationally to solvent mixtures that include ethylbenzene (mean exposure level 1.8 ppm) showed a 58% incidence of hearing loss compared to 36% in the reference (unexposed) group. The role of ethylbenzene in the observed losses cannot be ascertained from this study given that ethylbenzene was only one of several solvents, most of which were present at mean concentrations 1.5–3.5 times higher than ethylbenzene. Consistent with the outcome of occupational studies showing hearing loss, significant and persistent adverse auditory effects have been shown in animals after acute- and intermediate-duration inhalation exposures to ethylbenzene and after acute-duration oral exposures. OHCs in the organ of Corti (located in the cochlea) are a sensitive target of toxicity of ethylbenzene. Significant losses of OHCs in the organ of Corti were observed in male rats after acute-duration inhalation exposure to  $\geq 400$  ppm and intermediate-duration inhalation exposure to  $\geq 200$  ppm ethylbenzene. These losses in OHC were observed 8–11 weeks after the last exposures. Inhalation of  $\geq 400$  ppm ethylbenzene for 5 days or 4 weeks also resulted in a significant deterioration of auditory thresholds. The magnitude of the shifts in auditory thresholds observed after the first 4 weeks of exposure did not change during a 13-week exposure period or after an 8-week post-exposure recovery period. Inner hair cells were affected by ethylbenzene only at  $\geq 600$  ppm in the intermediate-duration study. Guinea pigs exposed to ethylbenzene at 2,500 ppm for 5 days did not show auditory deficits or losses in outer hair cells, whereas significant deficits and hair cell loss were observed in rats exposed to ethylbenzene at 550 ppm. An almost complete loss of OHC was reported in male rats 10 days after an acute-duration oral exposure to ethylbenzene. The mechanisms of the species differences between rats and guinea pigs are not understood. However, given the observations of hearing loss in workers exposed to 1.8 ppm ethylbenzene, the rat appears to be an appropriate animal model.

### 2.3 MINIMAL RISK LEVELS (MRLs)

Estimates of exposure levels posing minimal risk to humans (MRLs) have been made for ethylbenzene. An MRL is defined as an estimate of daily human exposure to a substance that is likely to be without an appreciable risk of adverse effects (noncarcinogenic) over a specified duration of exposure. MRLs are derived when reliable and sufficient data exist to identify the target organ(s) of effect or the most sensitive health effect(s) for a specific duration within a given route of exposure. MRLs are based on

## 2. RELEVANCE TO PUBLIC HEALTH

noncancerous health effects only and do not consider carcinogenic effects. MRLs can be derived for acute, intermediate, and chronic duration exposures for inhalation and oral routes. Appropriate methodology does not exist to develop MRLs for dermal exposure.

Although methods have been established to derive these levels (Barnes and Dourson 1988; EPA 1990a), uncertainties are associated with these techniques. Furthermore, ATSDR acknowledges additional uncertainties inherent in the application of the procedures to derive less than lifetime MRLs. As an example, acute inhalation MRLs may not be protective for health effects that are delayed in development or are acquired following repeated acute insults, such as hypersensitivity reactions, asthma, or chronic bronchitis. As these kinds of health effects data become available and methods to assess levels of significant human exposure improve, these MRLs will be revised.

***Inhalation MRLs***

- An MRL of 10 ppm has been derived for acute-duration inhalation exposure (14 days or less) to ethylbenzene based on a NOAEL for significant deterioration in CAP auditory threshold and significant OHC loss at 400 ppm (LOAEL).

The database for acute-duration inhalation exposure to ethylbenzene is composed mostly of studies in laboratory animals. Some of the available reports and studies in humans are of limited use for dose-response assessment because insufficient information was provided to clearly characterize the exposure to ethylbenzene. Several studies with laboratory animals identify ototoxicity as the most sensitive end point for acute-duration inhalation exposure to ethylbenzene. Damage to the OHCs of the organ of Corti and, in some cases, significant reductions in auditory thresholds were observed in rats exposed to  $\geq 400$  ppm ethylbenzene by inhalation for 5 days (Cappaert et al. 1999, 2000, 2001, 2002). Losses of OHCs appeared to be concentration related as losses were 52–66% in animals exposed to 800 ppm ethylbenzene (Cappaert et al. 1999), 40–75% at 550 ppm, and approximately 25% at 400 ppm (Cappaert et al. 2000, 2001). OHC losses in rats exposed to 300 ppm were small (12%) and not statistically significant (Cappaert et al. 2000). Significant auditory deterioration, manifested as shifts in auditory thresholds, was also observed in rats exposed to  $\geq 400$  ppm ethylbenzene for 5 days (Cappaert et al. 1999, 2000, 2001, 2002). Auditory thresholds in rats exposed to ethylbenzene at  $\geq 400$  ppm were significantly affected in the mid-frequency region; however, an increasingly broader range of frequencies were affected with increasing concentrations of ethylbenzene (Cappaert et al. 1999, 2000). Cappaert et al. (2002) demonstrated a significant species difference in the susceptibility of rats and guinea pigs to the ototoxic effects of ethylbenzene with guinea pigs showing no auditory deficits or losses in OHCs at 2,500 ppm

## 2. RELEVANCE TO PUBLIC HEALTH

ethylbenzene after 5 days (Cappaert et al. 2002). Auditory assessments indicate that effects were evident shortly after exposure and persisted for up to 11 weeks (termination of the observation period) (Cappaert et al. 1999, 2000, 2001, 2002). The data suggest that these auditory effects might be irreversible.

The observed damage to the auditory capacity of rats exposed to ethylbenzene during acute-duration studies reported in Cappaert et al. study (2000) was chosen as a critical effect to derive the acute-duration inhalation MRL. Ototoxicity was observed at relatively low exposure levels (400 ppm) and was a serious adverse effect that the impaired auditory threshold; no other adverse effects were observed at lower levels. An acute-duration MRL based on ototoxicity would be considered as protective of other effects observed in acute-exposure studies.

In the study by Cappaert et al. (2000), Wag/Rij rats (eight rats/group; sex not provided) were exposed to 0, 300, 400, or 550 ppm ethylbenzene (99% pure) 8 hours/day for 5 days. Animal weight was recorded weekly. Measurement of Distortion Product Otoacoustic Emissions (DPOAE), Compound Action Potential (CAP), and hair cell counts were conducted 3–6 weeks after the last ethylbenzene exposure. Exposed animals did not show clinical signs of intoxication and there were no significant differences in terminal body weight between exposed and control rats. DPOAE amplitude growth curves showed a significant reduction in rats exposed to 550 ppm, but not to 300 or 400 ppm ethylbenzene. Effects were significant at 5.6, 8, and 11.3 kHz, but not at other frequencies. The DPOAE thresholds were significantly shifted (increased stimulus was needed to elicit the threshold response) at 5.6, 8, 11.3, and 16 kHz in rats in the 550-ppm group. DPOAE threshold shifts were not observed in other exposure groups. Animals exposed to 550 ppm showed a significant shift in the CAP amplitude growth curves at 8, 12, and 16 kHz. In the 400-ppm group, the CAP growth curves were affected only at 12 kHz and there was no effect in animals in the 300-ppm group. CAP thresholds were significantly shifted at 8, 12, and 16 kHz in the 550-ppm group and at 12 and 16 kHz in the 400-ppm group. There was no deterioration of CAP thresholds in the 300-ppm group. Significant OHC losses of approximately 33 and 75% were observed in the 550-ppm group in the auditory regions corresponding to 11 and 21 kHz, respectively. In the 400-ppm group, significant losses (25%) were observed in the 11 kHz region. OHC losses in the 21 kHz region in the 300-ppm group were approximately 12%, but were not statistically significantly different from controls. This study identifies a NOAEL of 300 ppm and a LOAEL of 400 ppm for significant deterioration in CAP auditory thresholds and significant OHC losses.

A LOAEL/NOAEL approach was used to derive a point of departure to estimate an acute-duration inhalation MRL for ethylbenzene using the NOAEL of 300 ppm and the LOAEL of 400 ppm.

## 2. RELEVANCE TO PUBLIC HEALTH

Application of a benchmark dose analysis was precluded because the results in Cappaert et al. (2000) were presented graphically and the details necessary to conduct a benchmark dose assessment, such as standard errors or standard deviations, were not clearly discernible. The NOAEL of 300 ppm was not adjusted for intermittent exposure given that the pharmacokinetics of ethylbenzene indicate that ethylbenzene will rapidly be absorbed, attain equilibrium with blood, be metabolized, and be eliminated from the body. Steady-state blood ethylbenzene concentrations achieved within 2 hours of initiating inhalation exposure to ethylbenzene concentration ranging from 75 to 500 ppm (Charest-Tardif et al. 2006). The blood elimination kinetics of inhaled ethylbenzene show that ethylbenzene is rapidly eliminated from the blood, with elimination half-times ranging from 3.3 to 63 minutes (e.g., nonlinearity of clearance with exposure concentration, similar elimination half-times (Charest-Tardif et al. 2006; Tardif et al. 1997). To calculate the human equivalent NOAEL ( $\text{NOAEL}_{\text{HEC}}$ ), the NOAEL was multiplied by the ratio of the animal-to-human blood/gas partition coefficients for ethylbenzene. The blood/air partition coefficients for ethylbenzene were estimated to be 42.7 for the rat and 28.0 for the human (Tardif et al. 1997). Since the ethylbenzene blood/gas partitioning coefficient in animals is greater than the partitioning coefficient in humans, a default value of 1 is used for the animal-to-human blood/gas ratio (EPA 1994o). Thus, the  $\text{NOAEL}_{\text{HEC}}$  is 300 ppm. The  $\text{NOAEL}_{\text{HEC}}$  was divided by an uncertainty factor of 30 (3 for extrapolation from animals to humans with dosimetric adjustment and 10 for human variability), resulting in an acute-duration inhalation MRL of 10 ppm.

The developmental effects of inhaled ethylbenzene have been examined in high quality, guideline-compliant studies, which included complete examination of fetuses (Faber et al. 2006, 2007; NIOSH 1981; Saillenfait et al. 2003, 2006, 2007). Results of studies in rats indicate that ethylbenzene produces reduced fetal weight, skeletal anomalies, and delayed development of urogenital tract; skeletal anomalies and delayed urogenital development were observed in the presence of maternal toxicity (Faber et al. 2006; NIOSH 1981). Urogenital malformations (not specified) in mice and decreased fetal weight in rabbits also have been observed (Ungváry and Tátrai 1985); however, the usefulness of this study is hampered by the incomplete descriptions of the results and because an analysis of the results on a per litter basis was not provided. Malformations of the uropoietic apparatus at the ethylbenzene concentrations reported by Ungváry and Tátrai (1985) were not observed in longer-duration studies (Faber et al. 2006, 2007; Saillenfait et al. 2003, 2006, 2007).

Neurotoxic and respiratory effects were observed after acute-duration exposure to ethylbenzene at concentrations equal to or higher than those that elicited auditory effects in animals. Effects observed after acute-duration exposure to ethylbenzene include moderate activation of motor behavior in rats

## 2. RELEVANCE TO PUBLIC HEALTH

exposed to 400 ppm (Molnar et al. 1986) and reduced activity and prostration and shallow breathing in rats and mice at 1,200 ppm (Ethylbenzene Producers Association 1986a). Rats or mice exposed to  $\geq 2,000$  ppm showed posture changes, reduced grip strength, reduced motor coordination (Tegeris and Balster 1994), narcotic effects (Molnar et al. 1986), and neurotransmission disturbances in the forebrain and hypothalamus (Andersson et al. 1981). Mice exposed to 4,060 ppm for 20 minutes showed a 50% reduction in respiratory rate (Nielsen and Alarie 1982). A 50% respiratory depression observed in mice at 1,432 ppm was attributed to sensory irritation (De Ceaurriz et al. 1981). Ethylbenzene concentrations of 1,000 ppm caused momentary ocular irritation, a burning sensation, and profuse lacrimation in humans (Thienes and Haley 1972; Yant et al. 1930). Male volunteers exposed to 2,000 ppm ethylbenzene reported throat irritation and chest constriction (Yant et al. 1930). No histopathological findings were made in the lungs of surviving rats, mice, or rabbits exposed to 1,200, 400, or 2,400 ppm ethylbenzene, respectively, for 4 days (Ethylbenzene Producers Association 1986a).

Increased liver weight was reported after acute-duration exposure in rats exposed to  $\geq 400$  ppm ethylbenzene (Ethylbenzene Producers Association 1986a; Toftgard and Nilsen 1982), but not in mice at 1,200 ppm or rabbits at 2,400 ppm (Ethylbenzene Producers Association 1986a). At these same levels and durations of exposures, induction of microsomal enzymes and related ultrastructural changes (e.g., proliferation of the smooth endoplasmic reticulum) were observed. These effects occurred in the absence of histopathological changes to the liver. Therefore, the effects on the liver appear to be related to induction of microsomal enzymes in smooth endoplasmic reticulum.

Kidney weight was increased in rats exposed to  $\geq 1,200$  ppm (Ethylbenzene Producers Association 1986a; Toftgard and Nilsen 1982), but not in mice at 1,200 ppm or rabbits at 2,400 ppm (Ethylbenzene Producers Association 1986a). However, increased kidney weights occurred in the absence of histological changes (Ethylbenzene Producers Association 1986a).

- [An MRL of 0.7 ppm has been derived for intermediate-duration inhalation exposure \(15–364 days\) to ethylbenzene based on a loss of cochlear OHC at 200 ppm.](#)

Ototoxicity (loss of cochlear OHC) observed in the study by Gagnaire et al. (2007) was selected as the critical effect to derive the intermediate-duration inhalation MRL. Ototoxicity was observed at relatively low exposure levels (200 ppm) and was a serious adverse effect that the impaired auditory threshold; no other adverse effects were observed at lower levels. An intermediate-duration MRL based on ototoxicity would be considered as protective of other effects observed in intermediate-exposure studies.

## 2. RELEVANCE TO PUBLIC HEALTH

Male Sprague-Dawley rats (14 rats/exposure group) were exposed to 0, 200, 400, 600, and 800 ppm ethylbenzene (99% pure), 6 hours/day, 6 days/week, for 13 weeks (Gagnaire et al. 2007). Ototoxicity was assessed based on effects on neurophysiological measurements and cochlear total hair cell counts. Following the 8th week of recovery, eight rats/group were killed. In the 800-ppm group, one rat lost its head plug and could not undergo neurophysiological testing, one rat died for unknown reasons, and another rat was sacrificed due to a large neck tumor. There were no significant differences in body weight gain between the surviving treated animals and controls. Audiometric thresholds at 2, 4, 8, and 16 kHz were significantly higher than in animals exposed to 400, 600, and 800 ppm ethylbenzene in controls. The effect was evident at week 4, did not change throughout the exposure period, and was not reversed after 8 weeks of recovery. No shift in audiometric thresholds was observed in rats in the 200-ppm group; however, the morphological assessment of the organ of Corti showed significant losses (up to 30% of the outer hair cells in the mid frequency region) in the third row of the OHC in four of eight rats exposed to 200 ppm. A concentration-related loss in third row OHC (OHC3) was evident with almost complete loss observed in the 600- and 800-ppm groups. The data suggest that the extent of the damage at each concentration was greatest in the OHC3 followed, in decreasing order, by damage in OHC2, OHC1, and IHC. There was no significant hair cell loss in the control animals. The LOAEL for OHC3 loss was 200 ppm, the lowest concentration tested.

A LOAEL/NOAEL approach was used to derive a point of departure to estimate an intermediate-duration inhalation MRL for ethylbenzene. Application of a benchmark dose analysis was precluded because the results in the Gagnaire et al. (2007) study were presented graphically and the details necessary to conduct a benchmark dose assessment, such as standard errors or standard deviations, were not clearly discernible or, for those results where the necessary data were available, the benchmark models tested did not fit the data adequately.

The LOAEL of 200 ppm was not adjusted for intermittent exposure given that the pharmacokinetics of ethylbenzene indicate that ethylbenzene will rapidly be absorbed, attain equilibrium with blood, be metabolized, and be eliminated from the body. Steady-state blood ethylbenzene concentrations achieved within 2 hours of initiating inhalation exposure to ethylbenzene concentration ranging from 75 to 500 ppm (Charest-Tardif et al. 2006). The blood elimination kinetics of inhaled ethylbenzene show that ethylbenzene is rapidly eliminated from the blood, with elimination half-times ranging from 3.3 to 63 minutes (e.g., nonlinearity of clearance with exposure concentration, similar elimination half-times (Charest-Tardif et al. 2006; Tardif et al. 1997). To calculate the human equivalent LOAEL ( $LOAEL_{HEC}$ ), the LOAEL is multiplied by the ratio of the animal-to-human blood/gas partition coefficients for



## 2. RELEVANCE TO PUBLIC HEALTH

ethylbenzene. Since the ethylbenzene blood/gas partitioning coefficient in animals is greater than the partitioning coefficient in humans, a default value of 1 is used for the animal-to-human blood/gas ratio (EPA 1994o). Thus, the LOEL<sub>HEC</sub> is 200 ppm. The LOEL<sub>HEC</sub> was divided by an uncertainty factor of 300 (10 for use of a LOEL, 3 for extrapolation from animals to humans with dosimetric adjustment, and 10 for human variability) resulting in an intermediate-duration inhalation MRL of 0.7 ppm.

The database of toxicity studies of intermediate-duration inhalation exposures includes several studies in animals, but no studies in humans. The available animal studies indicate that rats are sensitive to the ototoxic effects of ethylbenzene (Gagnaire et al. 2007). This is in agreement with the results of acute-duration studies (Cappaert et al. 1999, 2000, 2001, 2002). Rats exposed to  $\geq 400$  ppm ethylbenzene via inhalation for 13 weeks showed significant increases in auditory thresholds after 4 weeks. These threshold shifts persisted unchanged for the duration of the exposure period and during an 8-week post-exposure recovery period (Gagnaire et al. 2007). Cell counts conducted in the organ of Corti after the 8-week recovery period showed significant losses of outer hair cells in rats exposed to  $\geq 200$  ppm. Concentration-related losses of inner hair cells (IHC) (14 and 32%) were observed in animals in the 600- and 800-ppm groups, respectively, with occasional IHC losses in the 400-ppm group. Exposed rats did not show clinical signs of toxicity or differences in body weight gain relative to unexposed animals (Gagnaire et al. 2007).

Systemic effects have been observed at concentrations equal to or higher than those that elicited ototoxic effects in rats. Increased liver, kidney, lung, and spleen weights have been observed in animals exposed to ethylbenzene concentrations in the 250- to 1,000-ppm range (Cragg et al. 1989; Elovaara et al. 1985; NIOSH 1981; NTP 1992; Wolf et al. 1956). For instance, significant increases in absolute and relative liver weights were observed in rats and mice exposed to 782 ppm for 4 weeks, but not in animals in the 382-ppm groups (Cragg et al. 1989). Liver weight was not affected in rabbits at concentrations as high as 1,610 ppm. No other organs, including lung or kidney, showed weight changes in rats or mice at 782 ppm or in rabbits at 1,610 ppm (Cragg et al. 1989). Gross and microscopic examination of over 30 organs (including organs of the respiratory, endocrine, digestive, renal, and nervous systems) did not show treatment-related effects in rats or mice exposed to 782 ppm or rabbits at 1,610 ppm (Cragg et al. 1989). Absolute and relative lung weights were significantly increased in female rats exposed to  $\geq 250$  ppm for 13 weeks; male rats showed an increased relative lung weight at 1,000 ppm (NTP 1992); however, there was no evidence of histopathological injury. Increased absolute and/or relative liver and kidney weights without evidence of histopathological injury were observed in male and female rats or mice exposed to  $\geq 250$  ppm ethylbenzene for 13 weeks (NTP 1992). Some of the organ weight increases

## 2. RELEVANCE TO PUBLIC HEALTH

reported at the lower concentrations were <10% (NTP 1992) or deemed to be slight (Wolf et al. 1956). Neurological effects (sporadic salivation) were reported in rats at  $\geq 382$  ppm (Cragg et al. 1989). Cragg et al. (1989) observed small, but statistically significant, increases in platelet counts in male rats and leukocyte counts in female rats exposed to 782 ppm ethylbenzene for 4 weeks. Although no details were provided, Wolf et al. (1956) did not report hematological changes in animals exposed to up to 2,200 ppm.

Increased incidence of skeletal variations or all variations combined were observed in the offspring of pregnant rats exposed to  $\geq 1,000$  ppm ethylbenzene; however, on a per litter basis, significant increases were observed only at 2,000 ppm (Saillenfait et al. 2003). Fetal malformations in the offspring of rats exposed to  $\leq 500$  ppm ethylbenzene occurred at a low frequency and did not appear to be attributable to ethylbenzene exposure (Saillenfait et al. 2003, 2006, 2007). Significant reductions in fetal body weight were observed in the offspring of pregnant rats exposed to  $\geq 1,000$  ppm ethylbenzene during gestation (Saillenfait et al. 2003, 2006, 2007), but not in rats exposed to  $\leq 500$  ppm (Saillenfait et al. 2003, 2006, 2007). Maternal toxicity was observed only in rats exposed to  $\geq 1,000$  ppm as evidenced by the significant reduction in weight gain (corrected for gravid uterine weight) (Saillenfait et al. 2003, 2006, 2007). NIOSH (1981) observed an increase in the incidence of skeletal anomalies in the offspring of rats exposed to approximately 1,000 ppm during pre-mating and gestation. Increased maternal liver, kidney, and spleen weights were observed in that dose group. Developmental effects were not consistently evident at approximately 100 ppm. Developmental landmarks and neurodevelopment were not statistically or biologically significantly affected in the offspring of rats exposed to up to 500 ppm ethylbenzene in a two-generation reproductive toxicity test (Faber et al. 2006, 2007). Reproductive parameters were not significantly affected in animals exposed to ethylbenzene concentrations as high as 1,000 ppm (Saillenfait et al. 2003, 2006, 2007). Faber et al. (2006) reported a reduction in estrus cycle length in F0, but not F1, females exposed to 500 ppm ethylbenzene. There was no impairment in fertility or increased time to mating in the F0 females (Faber et al. 2006).

- An MRL of 0.3 ppm has been derived for chronic-duration inhalation exposure (365 days or more) to ethylbenzene based on a LOAEL of 75 ppm for nephropathy in rats.

In the NTP (1999) study, groups of F344/N rats (50 animals/sex/dose group) were exposed to 0, 75, 250, or 750 ppm ethylbenzene by inhalation 5 days/week, 6 hours/day, for 104 weeks. Animals were observed twice daily and clinical findings were recorded monthly. Body weights were recorded at the initiation of the study, weekly for the first 13 weeks, at week 16, monthly through the end of exposure, and prior to terminal necropsy. Animals that survived to study termination were killed by asphyxiation with CO<sub>2</sub>. A complete necropsy and microscopic examination of major tissues and organs were performed on all rats

## 2. RELEVANCE TO PUBLIC HEALTH

that survived to study termination or died early. Survival of male rats in the 750-ppm group was significantly less than that of the chamber controls. No clinical findings were attributed to ethylbenzene exposure. The severity of nephropathy observed in exposed rats was significantly increased in females at  $\geq 75$  ppm and in males at 750 ppm. In male rats exposed to 750 ppm, the incidences of renal tubule proliferative lesions were significantly increased relative to control animals. The incidences of renal tubule adenoma and adenoma or carcinoma (combined) in the 750-ppm group were significantly greater than the incidence in control animals. The incidence of renal tubule hyperplasia in 750 ppm males was significantly greater than that in the control group. An increase was observed in the incidence of cystic degeneration of the liver in male rats at 750 ppm.

In a 2-year study, female mice exposed to  $\geq 250$  ppm ethylbenzene showed an increased incidence of hyperplasia (characterized as focal, poorly delineated, monomorphic increases of cells lacking compressive features or altered arrangement) of the pituitary gland pars distalis relative to the incidence in control animals (NTP 1999). Male and female mice in the 750-ppm group showed an increased incidence of follicular cell hyperplasia in the thyroid gland. Eosinophilic foci of the liver were observed in females in the 750-ppm group at a higher incidence than in control animals. Syncytial alterations of hepatocytes were observed in male mice in all ethylbenzene exposure groups, but not in controls, with a significant increase in incidence observed at  $\geq 250$  ppm. Other nonneoplastic changes in male mice exposed to 750 ppm included mild-to-minimal hepatocellular hypertrophy and hepatocyte necrosis (NTP 1999). The only available chronic-duration inhalation studies in animals suggest that a concentration-related increase in the severity of nephropathy in female rats is the most sensitive end point of ethylbenzene exposure. Thus, the study by NTP (1999) was selected to estimate a chronic-duration inhalation MRL.

A LOAEL/NOAEL approach was used to derive a point of departure to estimate a chronic-duration inhalation MRL for ethylbenzene. Application of a benchmark dose analysis was precluded because standard errors or standard deviations were not provided for the nephropathy severity ratings in the NTP (1999) study. The LOAEL of 75 ppm was not adjusted for intermittent exposure given that the pharmacokinetics of ethylbenzene indicate that ethylbenzene will rapidly be absorbed, attain equilibrium with blood, be metabolized, and be eliminated from the body. Steady-state blood ethylbenzene concentrations achieved within 2 hours of initiating inhalation exposure to ethylbenzene concentration ranging from 75 to 500 ppm (Charest-Tardif et al. 2006). The blood elimination kinetics of inhaled ethylbenzene show that ethylbenzene is rapidly eliminated from the blood, with elimination half-times ranging from 3.3 to 63 minutes (e.g., nonlinearity of clearance with exposure concentration, similar

## 2. RELEVANCE TO PUBLIC HEALTH

elimination half-times (Charest-Tardif et al. 2006; Tardif et al. 1997). To calculate the human equivalent LOAEL (LOAEL<sub>HEC</sub>), the LOAEL is multiplied by the ratio of the animal-to-human blood/gas partition coefficients for ethylbenzene. Since the ethylbenzene blood/gas partitioning coefficient in animals is greater than the partitioning coefficient in humans, a default value of 1 is used for the animal-to-human blood/gas ratio (EPA 1994o). Thus, the LOAEL<sub>HEC</sub> is 75 ppm. The LOAEL<sub>HEC</sub> was divided by an uncertainty factor of 300 (10 for use of a LOAEL, 3 for extrapolation from animals to humans with dosimetric adjustment, and 10 for human variability) resulting in an intermediate-duration inhalation MRL of 0.3 ppm.

The database of chronic-duration inhalation studies with ethylbenzene includes a chronic-duration study in rats and mice (NTP 1999) and studies in humans. Hematological effects (increased average number of lymphocytes and decreased hemoglobin) were observed in workers exposed to solvents containing ethylbenzene (Angerer and Wulf 1985). Concentration-related increases in the severity of nephropathy were observed in female rats exposed to  $\geq 75$  ppm for 2 years (NTP 1999). In male rats, the severity of nephropathy was higher than in control animals only at 750 ppm (NTP 1999). Significant increases in the incidence of renal tubule hyperplasia were also observed in male and female rats in the 750-ppm groups.

***Oral MRLs***

**Acute-duration Exposure.** No studies describing acute-duration oral exposure of humans to ethylbenzene were found in the literature. Two animal studies have examined the acute oral toxicity of ethylbenzene. An almost complete loss of the three rows of OHCs in the organ of Corti were reported in male rats administered 900 mg/kg/day (the only dose tested) by gavage for 2 weeks (Gagnaire and Langlais 2005). These losses were observed 10 days after the last dose. Although losses of OHCs have also been observed in acute-duration inhalation studies (Cappaert et al. 1999, 2000, 2001, 2002), Gagnaire and Langlais (2005) did not have a control group to establish the magnitude of the effects relative to unexposed animals. This study was used to rank the ototoxicity of 21 solvents administered by gavage. Nevertheless, the OHC losses observed in the ethylbenzene-treated animals were among the highest observed among the 21 organic solvents tested (Gagnaire and Langlais 2005). The 900 mg/kg/day dose was considered a serious LOAEL for ototoxicity. In the second study, doses of 500 or 1,000 mg/kg ethylbenzene decreased luteinizing hormone, progesterone, and 17  $\beta$ -estradiol levels, increased stromal tissue with dense collagen bundles and reduced lumen in the uterus, and delayed the estrus cycle in female rats during the diestrus stage (Ungvary 1986). The poor reporting of the methods and results of the Ungvary (1986) study precludes using as the basis on an MRL.

## 2. RELEVANCE TO PUBLIC HEALTH

Because the only dose tested in the Gagnaire and Langlais (2005) study is a serious LOAEL, an acute-duration oral MRL cannot be derived for ethylbenzene.

- An MRL of 0.5 mg/kg/day has been derived for intermediate-duration oral exposure to ethylbenzene based on the BMDL<sub>10</sub> of 48.2 mg/kg/day for hepatotoxicity (centrilobular hepatocyte hypertrophy) in male rats.

Hepatotoxicity, specifically the incidence of centrilobular hepatocyte hypertrophy, was selected as the critical effect to derive the intermediate-duration oral MRL. Based on evidence of hepatotoxicity (increased serum liver enzyme activity, absolute and relative liver weights, dose-related increased incidence of centrilobular hepatocyte hypertrophy, and the lack of evidence for adverse effects in other tissues or organ systems at lower oral intermediate-duration dosages, liver effects were selected as the basis for deriving the intermediate oral MRL. The critical study identified NOAEL and LOAEL values for hepatotoxicity of 75 and 250 mg/kg/day, respectively (Mellert et al. 2007). No other adverse effects were observed at lower doses.

In the principal study, groups of 10 male and 10 female Wister rats were administered ethylbenzene (no vehicle) by oral gavage at doses of 0, 75, 250, or 750 mg/kg/day for 13 weeks. The total daily dose of ethylbenzene was administered as split morning/evening half doses. Animals were examined daily for mortality and clinical signs. Food and water consumption and body weights were recorded weekly. A detailed clinical examination (ophthalmology and a functional observational battery [FOB]) and assessment of motor activity were conducted during the last week of treatment. After 13 weeks, urinalysis was conducted and blood samples were obtained and analyzed for hematology and clinical chemistry; organ weights were recorded and gross histopathologic examinations of the liver, kidney, and pancreas were conducted on animals in all groups. A comprehensive histopathological examination of tissues was performed in the control and 750 mg/kg/day groups.

No mortalities were observed during the course of the study (Mellert et al. 2007). Clinical signs (post-dosing salivation) in treated animals were observed in all animals administered  $\geq 250$  mg/kg/day and in one animal administered 75 mg/kg/day. Terminal body weight in males was significantly decreased by 14% compared to controls in the 750 mg/kg/day group. Mean corpuscular volume was increased in males and females and platelet count was reduced in females treated with 750 mg/kg/day. Prothrombin time was significantly decreased (<8% compared to controls) in females administered  $\geq 250$  mg/kg/kg, but no changes in prothrombin times were observed in males in any treatment group. Effects indicative of liver

## 2. RELEVANCE TO PUBLIC HEALTH

toxicity included increased activity of serum liver enzymes ALT and GGT in males ( $\geq 250$  mg/kg/day) and females (750 mg/kg/day), increased absolute and relative liver weights ( $\geq 250$  mg/kg/day in males and females), and a dose-related increase in the incidence of centrilobular hepatocyte hypertrophy ( $\geq 250$  mg/kg/day in males and females). Increased bilirubin ( $\leq 250$  mg/kg/day in males and 750 mg/kg/day in females), total protein (750 mg/kg/day in females), albumin (750 mg/kg/day in males and females), globulins (750 mg/kg/day in females), and cholesterol ( $\leq 250$  mg/kg/day in males and females), and decreased prothrombin time (750 mg/kg/day in males and  $\geq 250$  mg/kg/day in females) were considered by study investigators as adaptive effects in the liver. In males in the 75 mg/kg/day group, relative liver weight was significantly increased by (4% compared to controls); however, no histopathological changes or increases in absolute liver or serum liver enzyme activities were observed at this dosage. Given that ethylbenzene is a microsomal enzyme inducer and the absence of histopathology and other evidence of liver injury at the 75 mg/kg/day dosage, the small increase in relative liver weight in male rats at this dosage was not considered indicative of an adverse effect on the liver.

Renal effects in males included increased serum creatinine (750 mg/kg/day), increased incidences of transitional epithelial cells and granular and epithelial cell casts in the urine ( $\geq 250$  mg/kg/day), increased absolute and relative kidney weights ( $\geq 250$  mg/kg/day), and a dose-related increase in severity of hyaline droplet nephropathy ( $\geq 250$  mg/kg/day) (Mellert et al. 2007). Adverse renal effects in males were most likely related to accumulation of  $\alpha_2\mu$ -globulin accumulation, and, therefore, considered not relevant to humans. Absolute kidney weight was significantly increased by 7 and 13% in females administered 250 and 750 mg/kg/day, respectively, compared to controls. However, since no histopathological findings or alterations in urinalysis parameters were observed, increased kidney weight in females was not considered adverse. Absolute and relative thymus weights were decreased in females treated with  $\geq 250$  mg/kg/day, but no histopathological findings were observed. Histopathological examination of all other tissues did not reveal any abnormalities. Results of the FOB did not reveal consistent treatment-related effects. NOAEL and LOAEL values of 250 and 750 mg/kg/day, respectively, were identified based on hepatotoxicity in male and female rats.

Based on evidence of hepatotoxicity (increased serum liver enzyme activity, absolute and relative liver weights, and incidence of centrilobular hepatocyte hypertrophy), the liver was identified as the most sensitive target for oral ethylbenzene, with NOAEL and LOAEL values of 75 and 250 mg/kg/day, respectively. Since serum liver enzyme activities were increased in the mid- and high-dose groups in males, but only in the high-dose group in females, males appeared more sensitive than females to hepatic effects of oral ethylbenzene. To determine the point of departure for derivation of the intermediate-

## 2. RELEVANCE TO PUBLIC HEALTH


duration MRL, data sets for serum liver enzymes (ALT and GGT), relative liver weight, and centrilobular hepatocyte hypertrophy in male rats were evaluated for suitability for benchmark dose (BMD) modeling. Using all available continuous variable models in the EPA Benchmark Dose Software (BMDS) version 1.3.2 (EPA 2000), no models provided adequate fit to the data for serum liver enzymes and relative liver weights; therefore, these data sets were considered unsuitable for BMD analysis. Data for the incidence of centrilobular hepatocyte hypertrophy were analyzed using all available dichotomous models in the EPA Benchmark Dose Software (version 1.3.2). Predicted doses associated with a 10% extra risk were calculated. As assessed by the chi-square goodness-of-fit statistic, all available dichotomous models provided adequate fit ( $X^2 p > 0.1$ ). Comparing across models, a better fit is generally indicated by a lower Akaike's Information Criteria (AIC). As assessed by AIC, the log-probit model (Figure 2-1) provided the best fit to the data. The  $BMD_{10}$  and  $BMDL_{10}$  predicted by the log-probit model for the data on centrilobular hepatocyte hypertrophy in male rats were 78.9 and 48.2 mg/kg/day, respectively. The  $BMDL_{10}$  of 48.2 mg/kg/day for male rats was selected as the point of departure for deriving the intermediate-duration oral MRL.

The  $BMDL_{10}$  of 48.2 mg/kg/day was divided by a total uncertainty factor of 100 (10 for extrapolation from animals to humans and 10 for human variability), resulting in an intermediate-duration oral MRL of 0.5 mg/kg/day.

The intermediate-duration oral database for ethylbenzene is limited to the critical study by Mellert et al. (2007) evaluating the effects of oral exposure of rats to ethylbenzene for 4 and 13 weeks, and a poorly reported 6-month exposure study in rats (Wolf et al. 1956). Results of the 4-week exposure study in rats are similar to those observed in the 13-week study, showing that the liver is the primary target organ for oral ethylbenzene. Effects consistent with hepatotoxicity include increased absolute and relative liver weights ( $\geq 250$  mg/kg/day in males and 750 mg/kg/day in females), increased incidence of hepatocyte centrilobular ( $\geq 250$  mg/kg/day in males and 750 mg/kg/day in females), and increased serum liver enzyme activity (ALT) (750 mg/kg/day in males and females). The increase in relative kidney weight and hyaline droplet nephropathy in males administered  $\geq 250$  mg/kg/day was most likely secondary to increases accumulation of accumulation of  $\alpha_2\mu$ -globulin accumulation, and, therefore, considered not relevant to humans. The 4-week study identified NOAEL and LOAEL values of 250 and 750 mg/kg/day, respectively, for liver in male rats (Mellert et al. 2007). Histopathological changes characterized by cloudy swelling of parenchymal cells of the liver and an increase in liver weight were observed in female rats administered 408 mg/kg/day by gavage for 6 months (Wolf et al. 1956). No other hepatic changes

## 2. RELEVANCE TO PUBLIC HEALTH

**Figure 2-1. Predicted (Log-Probit Model) and Observed Incidence of Centrilobular Hepatocyte Hypertrophy in Male Rats Exposed to Oral Ethylbenzene by Gavage for 13 Weeks\***



15:00 07/26 2007

\*BMDs and BMDLs indicated are associated with a 10% extra risk change from the control, and are in units of mg/kg/day.



## 2. RELEVANCE TO PUBLIC HEALTH

were reported. No liver effects were observed in female rats administered 136 mg/kg/day. However, this study was poorly reported and did not provide adequate descriptions of study methods or results.

Although no additional data are available regarding the effects of intermediate oral exposure to ethylbenzene, results of an acute-duration oral study indicate that ethylbenzene is ototoxic (Gagnaire and Langlais 2005). In male rats administered 900 mg/kg/day (the only dose tested) by gavage for 2 weeks, an almost complete loss of the three rows of OHCs in the organ of Corti was observed in male rats (Gagnaire and Langlais 2005). The 4- and 13-week oral studies by Mellert et al. (2007) did not examine the cochlea or measure auditory function. Therefore, it is not possible to determine whether ototoxicity occurred in the 4- and 13-week studies.

**Chronic-duration Exposure.** No studies describing the non-carcinogenic effects of chronic-duration oral exposure to ethylbenzene in humans or animals were located.

2. RELEVANCE TO PUBLIC HEALTH

This page is intentionally blank.

### 3. HEALTH EFFECTS

#### 3.1 INTRODUCTION

The primary purpose of this chapter is to provide public health officials, physicians, toxicologists, and other interested individuals and groups with an overall perspective on the toxicology of ethylbenzene. It contains descriptions and evaluations of toxicological studies and epidemiological investigations and provides conclusions, where possible, on the relevance of toxicity and toxicokinetic data to public health.

A glossary and list of acronyms, abbreviations, and symbols can be found at the end of this profile.

#### 3.2 DISCUSSION OF HEALTH EFFECTS BY ROUTE OF EXPOSURE

To help public health professionals and others address the needs of persons living or working near hazardous waste sites, the information in this section is organized first by route of exposure (inhalation, oral, and dermal) and then by health effect (death, systemic, immunological, neurological, reproductive, developmental, genotoxic, and carcinogenic effects). These data are discussed in terms of three exposure periods: acute (14 days or less), intermediate (15–364 days), and chronic (365 days or more).

Levels of significant exposure for each route and duration are presented in tables and illustrated in figures. The points in the figures showing no-observed-adverse-effect levels (NOAELs) or lowest-observed-adverse-effect levels (LOAELs) reflect the actual doses (levels of exposure) used in the studies. LOAELs have been classified into "less serious" or "serious" effects. "Serious" effects are those that evoke failure in a biological system and can lead to morbidity or mortality (e.g., acute respiratory distress or death). "Less serious" effects are those that are not expected to cause significant dysfunction or death, or those whose significance to the organism is not entirely clear. ATSDR acknowledges that a considerable amount of judgment may be required in establishing whether an end point should be classified as a NOAEL, "less serious" LOAEL, or "serious" LOAEL, and that in some cases, there will be insufficient data to decide whether the effect is indicative of significant dysfunction. However, the Agency has established guidelines and policies that are used to classify these end points. ATSDR believes that there is sufficient merit in this approach to warrant an attempt at distinguishing between "less serious" and "serious" effects. The distinction between "less serious" effects and "serious" effects is considered to be important because it helps the users of the profiles to identify levels of exposure at which

### 3. HEALTH EFFECTS

major health effects start to appear. LOAELs or NOAELs should also help in determining whether or not the effects vary with dose and/or duration, and place into perspective the possible significance of these effects to human health.

The significance of the exposure levels shown in the Levels of Significant Exposure (LSE) tables and figures may differ depending on the user's perspective. Public health officials and others concerned with appropriate actions to take at hazardous waste sites may want information on levels of exposure associated with more subtle effects in humans or animals (LOAELs) or exposure levels below which no adverse effects (NOAELs) have been observed. Estimates of levels posing minimal risk to humans (Minimal Risk Levels or MRLs) may be of interest to health professionals and citizens alike.

A User's Guide has been provided at the end of this profile (see Appendix B). This guide should aid in the interpretation of the tables and figures for Levels of Significant Exposure and the MRLs.

#### **3.2.1 Inhalation Exposure**

##### **3.2.1.1 Death**

No studies were located regarding lethality in humans following inhalation exposure to ethylbenzene. Matsumoto et al. (1992) reported the case of a 44-year-old man who died 9 days after exposure to gasoline vapors for at least 10 hours in an enclosed car. The patient's clothing was saturated with gasoline, but there was no apparent ingestion of gasoline. The patient suffered chemical burns over 50% of the total body surface area, and the cause of death was reported as multiple organ failure. Ethylbenzene was detected in the patient's blood (estimated initial blood concentration of 2.6 µg/mL). However, since gasoline contains approximately 1.4% (by weight) ethylbenzene (Agency for Toxic Substances and Disease Registry 1995), it is unlikely that death was due to ethylbenzene exposure.

Studies on the lethality of inhaled ethylbenzene have been conducted using several animal models, with exposure times ranging from a few hours to 2 years. The LC<sub>50</sub> values obtained from acute inhalation exposure studies were 13,367 ppm following a 2-hour exposure (Ivanov 1962) and 4,000 ppm following a 4-hour exposure (Smyth et al. 1962); 100% mortality was observed following exposure to 16,698 ppm for 2 hours (Ivanov 1962) and exposure to 8,000 ppm for 4 hours (Smyth et al. 1962). Inhalation exposure of Fischer 344 rats and B6C3F<sub>1</sub> mice to ethylbenzene for 6 hours/day for 4 days produced lethality at concentrations of 1,200 and 2,400 ppm, respectively, although exposure to concentrations up to

### 3. HEALTH EFFECTS

2,400 ppm was not lethal to rabbits (Ethylbenzene Producers Association 1986a). In intermediate-duration exposure studies, inhalation exposure of rats and mice to 782 ppm or rabbits to 1,610 ppm ethylbenzene for 4 weeks did not produce lethality (Cragg et al. 1989). No mortality was observed in rats or mice exposed to 782 ppm or rabbits exposed to 1,610 ppm ethylbenzene for 4 weeks (Cragg et al. 1989) or in rats or mice exposed to 975 ppm ethylbenzene for 90 days (NTP 1992). Survival of male rats, but not female rats or male or female mice, exposed to 750 ppm ethylbenzene for 2 years was significantly decreased (NTP 1999); survival in male rats exposed to 75 or 250 ppm ethylbenzene was not affected.

The LC<sub>50</sub> values and all reliable LOAEL values for death in rats and mice following acute- or chronic-duration exposure are recorded in Table 3-1 and plotted in Figure 3-1.

#### 3.2.1.2 Systemic Effects

Little data are available on the systemic effects of inhaled ethylbenzene in humans. Most of the information available is from case reports in which quantitative data on exposure concentrations and durations were not reported. In addition, most of the available studies have confounding factors (e.g., simultaneous exposures to other toxic substances) and insufficient reporting of important study details. In general, the systemic effects observed in humans were respiratory tract and ocular irritation, and possible ototoxicity (hearing loss) and hematological alterations (increased lymphocyte counts and decreased hemoglobin concentration) (Angerer and Wulf 1985; Cometto-Muñiz and Cain 1995; Thienes and Haley 1972; Yant et al. 1930).

Several studies were located on the systemic effects of ethylbenzene in animals following inhalation exposure. Acute- and intermediate-duration exposure to inhaled ethylbenzene is associated with respiratory irritation, changes to the liver (increased organ weights and induction of microsomal enzymes), and effects on the hematological system (decreased platelets and increased leukocyte counts). Chronic exposure is associated with adverse effects to the liver (necrosis and hypertrophy), kidney (nephropathy and hyperplasia), and endocrine system (thyroid and pituitary hyperplasia).

No studies were located describing cardiovascular, gastrointestinal, musculoskeletal, renal, endocrine, dermal, body weight, or metabolic effects in humans, or dermal effects in animals after inhalation exposure to ethylbenzene.

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

Key to Figure	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
<b>ACUTE EXPOSURE</b>								
<b>Death</b>								
1	Rat (Fischer- 344)	4 d 6 hr/d				2400 M (100% mortality by day 3)	Ethylbenzene Producers Association 1986a	
2	Rat (NS)	4 hr				4000 M (LC50)	Smyth et al. 1962	
3	Mouse (B6C3F1)	4 d 6 hr/d				1200 M (4/5 animals died by day 3)	Ethylbenzene Producers Association 1986a	
<b>Systemic</b>								
4	Rat (Wistar)	2 wk 5 d/wk 6 hr/d	Hepatic		50 M (induction of UDP-glucuronyl transferase and D-glucuronyllactone dehydrogenase)		Elovaara et al. 1985	
			Renal		600 M (increase in relative kidney weights)			

\*\*\*DRAFT FOR PUBLIC COMMENT\*\*\*

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
5	Rat (Fischer- 344)	4 d 6 hr/d	Resp	2000 M			<a href="#">Ethylbenzene Producers Association 1986a</a>	No liver or renal histopathological changes were observed.
			Hepatic		400 M (increased liver weight)			
			Renal	400 M	1200 M (increased relative kidney weight)			
			Ocular Bd Wt	400 M 1200 M	1200 M (lacrimation)			
6	Rat (Sprague- Dawley)	3 d 6 hr/d	Resp	2000 M			<a href="#">Toftgard and Nilsen 1982</a>	
			Hepatic		2000 M (increased relative liver weight, and induction of nadph-cytochrome reductase and 7-ethoxycoumarin o-deethylase)			
			Renal		2000 M (increased relative kidney weight)			
7	Mouse (Swiss)	5 min	Resp		1432 M (RD50)		<a href="#">De Ceaurriz et al. 1981</a>	

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure	Species (Strain)	Exposure/Duration/Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
8	Mouse (B6C3F1)	4 d 6 hr/d	Ocular		400 M (lacrimation)		Ethylbenzene Producers Association 1986a	
			Bd Wt	400 M				
9	Mouse (Swiss-Webster)	30 min	Resp		4060 M (RD50)		Nielsen and Alarie 1982	
10	Mouse (CFW)	20 min	Ocular		2000 M (lacrimation and palpebral closure)		Tegeris and Balster 1994	
11	Rabbit (New Zealand)	4 d 6 hr/d	Resp	2400 M			Ethylbenzene Producers Association 1986a	
			Hepatic	2400 M				
			Renal	2400 M				
			Ocular		400 M (lacrimation)			
			Bd Wt	2400 M				
<b>Neurological</b>								
12	Rat (Wag/Rij/Cpb/l <sup>5</sup> d)	8 hr/d				800 M (loss of outer hair cells and hearing loss)	Cappaert et al. 1999	
13	Rat (Wag/Rij)	8 hr 5 d		300 <sup>b</sup>		400 (loss of outer hair cells and shifts in hearing thresholds)	Cappaert et al. 2000	



Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
14	Rat (albino Wag/Rij)	8 hr/d 5 d		300	400	(loss of outer hair cells)	<a href="#">Cappaert et al. 2001</a>	
15	Rat (Wag/Rij)	8 hr/d 5 d			550 F	(loss of outer hair cells and shifts in hearing thresholds)	<a href="#">Cappaert et al. 2002</a>	
16	Rat (Fischer- 344)	4 d 6 hr/d		1200 M		2400 M (salivation, prostration)	<a href="#">Ethylbenzene Producers Association 1986a</a>	
17	Rat (CFY)	4 hr		200 M	400 M	(moderate activation in motor behavior)	<a href="#">Molnar et al. 1986</a>	
18	Mouse (B6C3F1)	4 d 6 hr/d		400 M		1200 M (prostration and reduced activity)	<a href="#">Ethylbenzene Producers Association 1986a</a>	
19	Mouse (CFW)	20 min			2000 M	(postural changes, decreased arousal and rearing, disturbed gait, decreased mobility, righting reflex, decreased grip strength, increased landing foot splay, impaired psychomotor coordination)	<a href="#">Tegeris and Balster 1994</a>	

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
20	Rabbit (New Zealand)	4 d 6 hr/d		2400 M			Ethylbenzene Producers Association 1986a	
<b>Reproductive</b>								
21	Rat (Fischer- 344)	4 d 6 hr/d		2400 M			Ethylbenzene Producers Association 1986a	
22	Mouse (B6C3F1)	4 d 6 hr/d		1200 M			Ethylbenzene Producers Association 1986a	
23	Rabbit (New Zealand)	4 d 6 hr/d		2400 M			Ethylbenzene Producers Association 1986a	

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
<b>INTERMEDIATE EXPOSURE</b>								
<b>Systemic</b>								
24	Rat (Fischer- 344)	4 wk 5 d/wk 6 hr/d	Resp	782			<a href="#">Cragg et al. 1989</a>	
			Cardio	782				
			Gastro	782				
			Hemato	382	782	(increased platelet counts in males; increased mean total leukocyte counts in males and females)		
			Musc/skel	782				
			Hepatic	382	782	(increased absolute and relative liver weight)		
			Renal	782				
			Endocr	782				
			Ocular	99	382	(sporadic incidence of lacrimation)		
			Bd Wt	782				

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
25	Rat (Wistar)	5-16 wk 5 d/wk 6 hr/d	Hepatic		50 M (induction of UDP-glucuronyl transferase and D-glucuronyllactone dehydrogenase)		<a href="#">Elovaara et al. 1985</a>	
			Renal		300 M (increase in microsomal enzyme activity and glutathione)			
			Bd Wt	600 M				
26	Rat (Wistar)	3 wk 5 d/wk 7 hr/d Gd 1-19	Resp	985 F			<a href="#">NIOSH 1981</a>	
			Hepatic	97 F	959 F (increased liver weight)			
			Renal	97 F	959 F (increased kidney weight)			
			Bd Wt	985 F				

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
27	Rat (F344/N)	90 d 5 d/wk 6 hr/d	Resp	99 F	246 F (increased absolute and relative lung weight)		NTP 1992	
			Cardio	975				
			Gastro	975				
			Hemato	975				
			Musc/skel	975				
			Hepatic	99 M	246 M (increased absolute and relative liver weight)			
			Renal	246 M	498 M (<10% increase in absolute and relative kidney weight)			
			Endocr	975				
			Ocular	975				
Bd Wt	975							
28	Rat SD	6 hr/d Gd 6-20	Hepatic		250 F (increased absolute and relative liver weight, moderate to marked hepatocellular hypertrophy)		Saillenfait et al. 2006, 2007	
			Bd Wt	250 F	1000 F			

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
29	Mouse (B6C3F1)	4 wk 5 d/wk 6 hr/d	Resp	782			<a href="#">Cragg et al. 1989</a>	
			Cardio	782				
			Gastro	782				
			Hemato	782				
			Musc/skel	782				
			Hepatic	382	782	(increased absolute and relative liver weight)		
			Renal	782				
			Endocr	782				
			Ocular	782				
			Bd Wt	782				

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
30	Mouse (B6C3F1)	90 d 5 d/wk 6 hr/d	Resp	975			NTP 1992	
			Cardio	975				
			Gastro	975				
			Hemato	975				
			Musc/skel	975				
			Hepatic	498 M	740 M (increased absolute and relative liver weight)			
			Renal	740 F	975 F (increased relative kidney weight)			
			Endocr	975				
			Ocular	975				
Bd Wt	975							

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
31	Rabbit (New Zealand)	4 wk 5 d/wk 6 hr/d	Resp	1610			<a href="#">Cragg et al. 1989</a>	
			Cardio	1610				
			Gastro	1610				
			Hemato	1610				
			Musc/skel	1610				
			Hepatic	1610				
			Renal	1610				
			Endocr	1610				
			Ocular	1610				
			Bd Wt	1610				
32	Rabbit (New Zealand)	Gd 1-24 7 d/wk 7 hr/d	Resp	962 F			<a href="#">NIOSH 1981</a>	
			Hepatic	99 F	962 F (increased absolute and relative liver weights in pregnant rabbits)			
			Renal	962 F				
			Bd Wt	962 F				
			Other	962 F				
<b>Immuno/ Lymphoret</b>								
33	Rat (Fischer- 344)	4 wk 5 d/wk 6 hr/d		782			<a href="#">Cragg et al. 1989</a>	



Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
34	Rat (Wistar)	3 wk 5 d/wk 7 hr/d Gd 1-19		97 F	959 F (increased spleen weight)		NIOSH 1981	
35	Rat (F344/N)	90 d 5 d/wk 6 hr/d		975			NTP 1992	NOAEL based on evaluation of thymus weight, gross pathology, histopathology, and hematology.
36	Mouse (B6C3F1)	4 wk 5 d/wk 6 hr/d		782			Cragg et al. 1989	NOAEL based on evaluation of thymus and spleen weight, gross pathology, histopathology, and hematology.
37	Mouse (B6C3F1)	13 wk 5 d/wk 6 hr/d		975			NTP 1992	NOAEL based on evaluation of thymus weight, gross pathology, histopathology, and hematology.
38	Rabbit (New Zealand)	4 wk 5 d/wk 6 hr/d		1610			Cragg et al. 1989	

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure	Species <sup>a</sup> (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
<b>Neurological</b>								
39	Rat (Fischer-344)	4 wk 5 d/wk 6 hr/d		99	382	(sporadic incidence of salivation)	Cragg et al. 1989	
40	Rat (SD)	6 hr/d 6 d/wk 13 wk			200 <sup>c</sup> M	600 M (complete loss of third row outer hair cells and hearing loss)	Gagnaire et al. 2007	
41	Rat (F344/N)	90 d 5 d/wk 6 hr/d		975			NTP 1992	
42	Mouse (B6C3F1)	4 wk 5 d/wk 6 hr/d		782			Cragg et al. 1989	NOAEL based on clinical observations, organ weights, and histopathology.
43	Mouse (B6C3F1)	90 d 5 d/wk 6 hr/d		975			NTP 1992	NOAEL based on clinical observations, organ weights, and histopathology.
44	Rabbit (New Zealand)	4 wk 5 d/wk 6 hr/d		1610			Cragg et al. 1989	NOAEL based on clinical observations, organ weights, and histopathology.

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
<b>Reproductive</b>								
45	Rat (Fischer- 344)	4 wk 5 d/wk 6 hr/d		782			Cragg et al. 1989	NOAEL based on histopathological examination of reproductive organs.
46	Rat (CrI-CD)	6 hr/d 70 d		500			Faber et al. 2006	NOAEL based on reproductive parameters (mating/fertility indices, gestation length, implantations, births/litter and litter size).
47	Rat (Wistar)	3 wk 5 d/wk 7 hr/d Gd 1-19		985 F			NIOSH 1981	NOAEL assessed by pregnancy rate, implantations, number of litters, resorptions, and live fetuses.
48	Rat (F344/N)	90 d 5 d/wk 6 hr/d		975			NTP 1992	NOAEL based on vaginal cytology and sperm motility, organ weights, and estrous cycle.

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
49	Mouse (B6C3F1)	4 wk 5 d/wk 6 hr/d		782			Cragg et al. 1989	NOAEL based on histopathological examination of reproductive organs.
50	Mouse (B6C3F1)	13 wk 5 d/wk 6 hr/d		975			NTP 1992	NOAEL based on vaginal cytology and sperm motility, organ weights, and estrous cycle.
51	Rabbit (New Zealand)	4 wk 5 d/wk 6 hr/d		1610			Cragg et al. 1989	NOAEL based on histopathological assessment of reproductive organs.
52	Rabbit (New Zealand)	Gd 1-24 7 d/wk 7 hr/d		962 F			NIOSH 1981	NOAEL assessed by pregnancy rate, implantations, number of litters, resorptions, and live fetuses.
<b>Developmental</b>								
53	Rat (CrI-CD)	6 hr/d 70 d		500 F			Faber et al. 2006	NOAEL based on fetal survival and gross and histopathological examination of fetuses.

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
54	Rat (Cri-CD)	6 hr/d 70 d		500 F			<a href="#">Faber et al. 2007</a>	NOEAL based on fetal survival, body weights, physical landmarks, and neurobehavioral tests.
55	Rat (Wistar)	3 wk 5 d/wk 7 hr/d Gd 1-19		97 F	959 F (skeletal anomalies, supernumerary ribs)		<a href="#">NIOSH 1981</a>	
56	Rat (Sprague- Dawley)	6 hr/d Gd 6-20		500 F	1000 F (decreased fetal body weight)		<a href="#">Saillenfait et al. 2003</a>	
57	Rat (Sprague- Dawley)	6 hr/d Gd 6-20		250 F	1000 F (slight decrease in fetal body weight)		<a href="#">Saillenfait et al. 2006, 2007</a>	
58	Rabbit (New Zealand)	Gd 1-24 7 d/wk 7 hr/d		962 F			<a href="#">NIOSH 1981</a>	NOAEL assessed by pregnancy rate, implantations, number of litters, resorptions, and live fetuses.

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
<b>CHRONIC EXPOSURE</b>								
<b>Death</b>								
59	Rat (F344)	6 hr/d 5 d/wk 2 yr				750 M (decreased survival)	NTP 1999	Survival of male rats was not affected at 75 or 250 ppm. In addition, survival of female rats and male and female mice was not affected at 750 ppm.
<b>Systemic</b>								
60	Rat (F344)	6 hr/d 5 d/wk 2 yr	Resp	750			NTP 1999	
			Cardio	750				
			Hemato	750				
			Musc/skel	750				
			Hepatic	750				
			Renal		75 <sup>d</sup> F	(increased severity of nephropathy)		
			Endocr	750				
			Dermal	750				
			Bd Wt	750				

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments
					Less Serious (ppm)	Serious (ppm)		
61	Mouse (F344)	6 hr/d 5 d/wk 2 yr	Resp	750			NTP 1999	
			Cardio	750				
			Gastro	750				
			Musc/skel	750				
			Hepatic	250 M	750 M (hypertrophy and necrosis)			
			Renal	750				
			Endocr	75 F	250 F (hyperplasia in pituitary gland pars distalis)			
					750 (thyroid follicular cell hyperplasia)			
					Dermal	750		
		Bd Wt	750					
<b>Cancer</b>								
62	Rat (F344)	6 hr/d 5 d/wk 2 yr				750 M (CEL: renal tubule adenoma or carcinoma)	NTP 1999	

Table 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

(continued)

Key to Figure	Species (Strain)	Exposure/Duration/Frequency (Route)	System	NOAEL (ppm)	LOAEL		Reference Chemical Form	Comments	
					Less Serious (ppm)	Serious (ppm)			
63	Mouse (F344)	6 hr/d 5 d/wk 2 yr				750	(CEL: alveolar/bronchiolar adenoma or carcinoma and hepatocellular adenoma or carcinoma)	NTP 1999	

a The number corresponds to entries in Figure 3-1.

b Used to derive an acute-duration inhalation minimal risk level (MRL) of 10 ppm for ethylbenzene. The NOAEL of 300 ppm was converted to a human equivalent concentration, which was divided by an uncertainty factor of 30 (3 for extrapolation from animals to humans using dosimetric adjustment and 10 for human variability) (see Appendix A).

c Used to derive an intermediate-duration inhalation minimal risk level (MRL) of 0.7 ppm for ethylbenzene. The LOAEL of 200 ppm was converted to a human equivalent concentration, which was divided by an uncertainty factor of 300 (10 for use of a LOAEL, 3 for extrapolation from animals to humans using dosimetric adjustment, and 10 for human variability) (see Appendix A).


d Used to derive a chronic-duration inhalation minimal risk level (MRL) of 0.3 ppm for ethylbenzene. The LOAEL of 75 ppm was converted to a human equivalent concentration, which was divided by an uncertainty factor of 300 (10 for use of a LOAEL, 3 for extrapolation from animals to humans using dosimetric adjustment, and 10 for human variability) (see Appendix A).

Bd Wt = body weight; Cardio = cardiovascular; CEL = cancer effect level; d = day(s); Endocr = endocrine; F = Female; Gastro = gastrointestinal; Gd = gestational day; Gn pig = guinea pig; Hemato = hematological; hr = hour(s); HVA = homovanillic acid; Immuno/Lymphoret = immunological/lymphoreticular; LC50 = lethal concentration, 50% kill; LOAEL = lowest-observed-adverse-effect level; M = male; min = minute(s); mo = month(s); Musc/skel = musculoskeletal; NADPH = Nicotinamide adenosine dinucleotide phosphate; NOAEL = no-observed-adverse-effect level; NS = not specified; ppm = parts per million; RD50 = 50% decrease in respiration rate; Resp = respiratory; x = time(s); (W) = drinking water; wk = week(s); yr = year(s)



Figure 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation

Acute (≤14 days)



\*\*\*DRAFT FOR PUBLIC COMMENT\*\*\*

Figure 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation (Continued)

Intermediate (15-364 days)

\*\*\*DRAFT FOR PUBLIC COMMENT\*\*\*




Figure 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation (Continued)  
Intermediate (15-364 days)




Figure 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation (Continued)  
Intermediate (15-364 days)

\*\*\*DRAFT FOR PUBLIC COMMENT\*\*\*





Figure 3-1 Levels of Significant Exposure to Ethylbenzene - Inhalation (Continued)

Chronic (≥365 days)



\*\*\*DRAFT FOR PUBLIC COMMENT\*\*\*

c-Cat	-Humans	f-Ferret	n-Mink	◆ Cancer Effect Level-Animals	▼ Cancer Effect Level-Humans	■ LD50/LC50
d-Dog	k-Monkey	j-Pigeon	o-Other	● LOAEL, More Serious-Animals	▲ LOAEL, More Serious-Humans	⋮ Minimal Risk Level
r-Rat	m-Mouse	e-Gerbil		◐ LOAEL, Less Serious-Animals	△ LOAEL, Less Serious-Humans	⋮ for effects
p-Pig	h-Rabbit	s-Hamster		○ NOAEL - Animals	△ NOAEL - Humans	⋮ other than
q-Cow	a-Sheep	g-Guinea Pig				⋮ Cancer

### 3. HEALTH EFFECTS

The systemic effects observed after inhalation exposure are discussed below. The highest NOAEL values and all reliable LOAEL values for systemic effects in each species and duration category are recorded in Table 3-1 and plotted in Figure 3-1.

**Respiratory Effects.** Male volunteers reported throat and nasal irritation and feelings of “chest constriction” during a 6-minute inhalation exposure to 2,000 ppm ethylbenzene (Yant et al. 1930). More severe throat and nasal irritation were reported immediately upon exposure to 5,000 ppm ethylbenzene. No data on pulmonary function were reported (Yant et al. 1930). No bronchospastic response was observed in two subjects challenged with 55 ppm ethylbenzene for 15 minutes in an inhalation chamber, based on comparison of pre- and post-exposure pulmonary function tests (Moscato et al. 1987).

Results of acute studies in animals indicate that inhalation of ethylbenzene produces adverse respiratory effects ranging from irritation to pulmonary congestion. Nasal irritation (based on nose rubbing) was observed in guinea pigs exposed to 1,000 ppm for 3 and 8 minutes and to 2,000, 5,000, and 10,000 ppm for 480, 30, and 10 minutes, respectively (Yant et al. 1930). Gross histopathology revealed congestion and edema in the lungs of animals that died after exposure to 10,000 ppm ethylbenzene, with less severe effects observed in surviving animals. Pulmonary congestion also was observed in rats and mice that died during exposure a 4-day exposure to 2,400 and  $\geq 1,200$  ppm ethylbenzene, respectively (Ethylbenzene Producers Association 1986a). A 50% reduction in breathing rate was observed in mice exposed to 1,432 ppm for 5 minutes (De Ceaurriz et al. 1981) and 4,060 ppm for 30 minutes (Nielsen and Alarie 1982). No adverse respiratory effects were observed in rats exposed to 2,000 ppm for 3 days (Toftgard and Nilsen 1982) or in rats, mice, and rabbits exposed to 1,200, 400, or 2,400 ppm, respectively, for 4 days (Ethylbenzene Producers Association 1986a).

Adverse respiratory effects attributed to intermediate- or chronic-duration inhalation exposures to ethylbenzene have been observed in animals. Relative lung weight was increased in male rats exposed to 975 ppm for 90 days, although increased absolute and relative lung weights were observed only in female rats exposed to 246 ppm ethylbenzene, but not to higher concentrations (NTP 1992). Pulmonary lesions (inflammatory cell infiltrate) were observed in male rats exposed to  $\geq 246$  ppm for 90 days (NTP 1992). However, the NTP Pathology Working Group considered these effects to be more typical of an infectious agent than a response to the test compound; therefore, pulmonary findings were not attributed to ethylbenzene exposure. No histopathological changes were observed in rats exposed to 2,200 ppm, guinea pigs or rabbits exposed 1,250 ppm, or monkeys exposed to 600 ppm ethylbenzene for 6 months (Wolf et al. 1956); however, the utility of this study is limited by a general lack of study details (e.g., no

### 3. HEALTH EFFECTS

exposure or control data were provided) and the small size of exposure groups (1–2 rabbits or monkeys per group). No histopathological findings clearly attributable to ethylbenzene were observed in respiratory tissue of rats or mice exposed to up to 750 ppm ethylbenzene for 2 years (NTP 1999). Although the incidences of edema, congestion, and hemorrhage observed in male rats in the 750 ppm group were increased relative to control rats, observations were considered to be agonal changes in moribund animals and not directly related to chemical toxicity (NTP 1999).

**Cardiovascular Effects.** Intermediate and chronic exposure of animals to inhaled ethylbenzene does not appear to produce adverse cardiovascular effects, based on results of histopathological examinations. No adverse histopathological effects were reported in cardiac tissue of rats or mice exposed to 782 ppm or rabbits exposed to 1,610 ppm ethylbenzene for 4 weeks (Cragg et al. 1989). Similarly, no cardiovascular effects were observed in rats or mice exposed to 975 ppm ethylbenzene for 90 days (NTP 1992) or in rats exposed to 2,200 ppm, guinea pigs or rabbits exposed to 1,250 ppm, or monkeys exposed to 600 ppm ethylbenzene for 6 months (Wolf et al. 1956). No adverse histopathological findings were observed in cardiovascular tissues of rats or mice exposed to 750 ppm ethylbenzene for 2 years (NTP 1999).

**Gastrointestinal Effects.** No adverse effects on the gastrointestinal system have been observed following intermediate or chronic inhalation exposure of animals. No changes in gross appearance or adverse histopathological effects were observed in the intestines of rats and mice exposed to 782 ppm or rabbits exposed to 1,610 ppm ethylbenzene for 4 weeks (Cragg et al. 1989). No adverse histopathological changes in gastrointestinal tissue were observed in rats or mice exposed to  $\leq 975$  ppm ethylbenzene for 90 days (NTP 1992) or in rats or mice exposed to  $\leq 750$  ppm ethylbenzene for 2 years (NTP 1999).

**Hematological Effects.** Two studies involving long-term monitoring of workers occupationally exposed to ethylbenzene were located (Angerer and Wulf 1985; Bardodej and Cirek 1988). Angerer and Wulf (1985) reported increased lymphocyte count and decreased hemoglobin concentration in male varnish workers exposed to a mixture of solvents, including ethylbenzene, compared to an unexposed control group. Workers were employed for an average of 8.2 years and exposed to an average ethylbenzene concentration of 1.64 ppm. Average lymphocyte levels increased (41.5–68.8%) and average hemoglobin values decreased (5.2–7.1%) in exposed workers, compared to unexposed controls. However, due to concomitant exposure to other chemicals (xylenes, lead, toluene), the relationship of adverse hematological effects to inhaled ethylbenzene cannot be established. No adverse hematological effects were seen in male workers employed at an ethylbenzene manufacturing facility over a 20-year period, compared to unexposed control workers (Bardodej and Cirek 1988). Although no information on

### 3. HEALTH EFFECTS

ethylbenzene concentrations was reported, an estimated concentration of 6.4 mg/m<sup>3</sup> was derived from a mean post-shift in urinary mandelic acid concentration in workers, based on the relationship between ethylbenzene concentrations in air and urinary mandelic acid concentration in a chamber-exposed group (Bardodej and Bardodejova 1988). However, given the low exposure concentration, this study had limited power to detect any effect.

Studies using animal models yield conflicting results regarding hematological effects of inhaled ethylbenzene. Platelet count was significantly decreased in male rats and mean total leukocyte count was significantly increased in female rats exposed to 782 ppm ethylbenzene for 4 weeks; hematological effects were not observed in male or female rats exposed to ≤382 ppm, mice exposed to ≤782 ppm, or rabbits exposed to ≤1,610 ppm (Cragg et al. 1989). No adverse hematological effects were observed in rats or mice exposed to 975 ppm ethylbenzene for 90 days (NTP 1992), or in rats exposed to ≤2,200 ppm, guinea pigs or rabbits exposed ≤1,250 ppm, or monkeys exposed to ≤600 ppm ethylbenzene for 6 months (Wolf et al. 1956).

**Musculoskeletal Effects.** No musculoskeletal effects have been observed in laboratory animals exposed to inhaled ethylbenzene for intermediate or chronic durations. No bone tissue abnormalities were observed upon histopathological examination of tissue from rats and mice exposed to 782 ppm and rabbits exposed to 1,610 ppm for 4 weeks (Cragg et al. 1989). Similarly, no adverse effect on bone tissue was observed in rats or mice exposed to 975 ppm ethylbenzene for 90 days (NTP 1992) or 750 ppm for 2 years (NTP 1999).

**Hepatic Effects.** No adverse effects on liver function, as measured by serum liver enzyme activities, were observed in male workers employed at an ethylbenzene manufacturing facility over a 20-year period (Bardodej and Cirek 1988). Although no information on ethylbenzene concentrations was reported, an estimated concentration of 6.4 mg/m<sup>3</sup> was derived as described above under hematological effects (Section 3.2.1.3 ). Given the low exposure concentration, this study had limited the power to detect any effect.

Results of studies in laboratory animals have found various effects on the liver, including induction of cytochrome P-450, changes in liver weight (at least in part related to induction of cytochrome P-450), changes in hepatocyte ultrastructure consistent with induction of smooth endoplasmic reticulum, and histopathological changes, including hepatocyte necrosis. Increased liver weights, induction of hepatic drug metabolizing enzymes, and changes in hepatocyte ultrastructure (consistent with induction of



## 3. HEALTH EFFECTS

smooth endoplasmic reticulum) have been observed in rats following acute inhalation exposure to ethylbenzene. Concentration-related increases in absolute and relative liver weights were reported in male rats exposed to  $\geq 400$  ppm ethylbenzene for 3–4 days, although no histopathological changes were observed (Ethylbenzene Producers Association 1986a). Increased relative liver weight, increased hepatic concentration of cytochrome P-450, and induction of hepatic microsomal enzymes (NADPH-cytochrome reductase, 7-ethoxycoumarin O-deethylase) were reported in rats exposed to 2,000 ppm ethylbenzene concentrations for 3 days (Toftgard and Nilsen 1982). Similarly, hepatic drug metabolizing enzymes (UDP glucuronyl-transferase, D-glucuronolactone dehydrogenase) were increased in male rats exposed to 50 ppm ethylbenzene for 2 weeks, and ethoxycoumarin o-deethylase was increased at 300 ppm (Elovaara et al. 1985). Electron microscopy showed changes in hepatocyte ultrastructure consistent with induction of cytochrome P-450 (e.g., smooth endoplasmic reticulum proliferation, slight degranulation of rough endoplasmic reticulum) in rats exposed to 600 ppm ethylbenzene for 2 weeks (Elovaara et al. 1985). Hepatic changes following acute exposure to ethylbenzene are consistent with induction of hepatic microsomal enzymes.

Similar hepatic effects (liver weights, induction of hepatic drug metabolizing enzymes, and changes in hepatocyte ultrastructure) also have been reported in laboratory animals exposed to inhaled ethylbenzene for intermediate exposure durations. Significant increases in relative liver weight were observed in female rats exposed to  $\geq 250$  ppm ethylbenzene for 15 days (Saillenfait et al. 2006), rats and mice exposed to 782 ppm ethylbenzene for 4 weeks (Cragg et al. 1989), pregnant and nonpregnant rats and pregnant rabbits exposed to 1,000 ppm ethylbenzene for 3 weeks prior to mating and throughout gestation (NIOSH 1981), and rats and mice exposed to 246 and 740 ppm ethylbenzene, respectively, for 90 days (NTP 1992). Increased liver weight was also observed in rats exposed to 400 ppm, and guinea pigs and monkeys exposed to 600 ppm ethylbenzene for 6 months (Wolf et al. 1956). Hepatic microsomal enzymes (total cytochrome P-450 protein, 7-ethoxycoumarin O-deethylase, aminopyrine N-demethylase) were induced in rats exposed to 50 ppm ethylbenzene for 16 weeks and changes in hepatocyte ultrastructure (e.g., smooth endoplasmic reticulum proliferation, slight degranulation of rough endoplasmic reticulum) in rats exposed to ethylbenzene from 2 to 15 weeks (Elovaara et al. 1985).

Other histopathological findings in animals exposed to inhaled ethylbenzene were moderate to marked hypertrophy of periportal hepatocytes with clear cytoplasm in female rats exposed to  $\geq 250$  ppm ethylbenzene for 15 days (the investigators noted that minimal hypertrophy was observed in controls) (Saillenfait et al. 2006) and a cloudy swelling of hepatocytes of rats exposed to 2,200 ppm for 6 months

### 3. HEALTH EFFECTS

(Wolf et al. 1956). No histopathological changes in the liver were observed in rats or mice exposed to 246 and 740 ppm, respectively, for 90 days (NTP 1992).

Chronic exposure of mice, but not rats, to inhaled ethylbenzene for 2 years produced hepatic toxicity, as indicated by histopathological changes (syncytial alterations of hepatocytes, hepatocellular hypertrophy, and hepatocyte necrosis) (NTP 1999). Syncytial alterations (enlarged hepatocytes with multiple nuclei), which were concentration-related in incidence and severity, were observed at in male mice exposed to  $\geq 75$  ppm ethylbenzene, and hepatocyte hypertrophy and necrosis were observed in male mice exposed to 750 ppm. In female mice exposed to 750 ppm ethylbenzene for 2 years, the incidence and severity of eosinophilic foci, which was considered to be a preneoplastic lesion, was increased.

**Renal Effects.** Renal effects of acute and intermediate exposure to inhaled ethylbenzene are primarily limited to minimally adverse effects, including increased kidney weight in rats and mice and induction of microsomal enzymes in rats. However, chronic exposure of male and female rats results in more serious renal effects, including nephropathy, renal tubule hyperplasia, and renal tubular adenomas and carcinomas (see Section 3.2.1.7, Cancer). In addition, effects associated with accumulation of  $\alpha_{2\mu}$ -globulin and hyaline droplets have been observed in male rats exposed to inhaled ethylbenzene. Accumulation of  $\alpha_{2\mu}$ -globulin in the renal tubule epithelial cells of male rats is associated with tubular epithelial necrosis, regenerative proliferation, and renal tumors. This accumulation is not observed in female rats, mice, or humans (which lack that protein), or in male rats, which are genetically lacking  $\alpha_{2\mu}$ -globulin. Adverse effects in male rats associated with renal accumulation of  $\alpha_{2\mu}$ -globulin are therefore not considered relevant to humans (EPA 1991g). However, since renal toxicity of chronic exposure to inhaled ethylbenzene has been observed in female rats, renal effects associated with ethylbenzene are relevant to humans.

Acute exposure to inhaled ethylbenzene had been reported to produce increases in kidney weight, induce renal microsomal enzymes, and enhance renal hyaline droplets in rats of both sexes. In male rats only, this accumulation includes  $\alpha_{2\mu}$ -globulin, but evidently other proteins are involved in females, and probably also in the males. Relative kidney weight was significantly increased (11–20%) in male rats exposed to 2,000 ppm for 2 days (Toftgard and Nilsen 1982) and 1,200 ppm ethylbenzene for 4 days (Ethylbenzene Producers Association 1986a), and in male and female rats exposed to 750 ppm ethylbenzene (6–7%), but not at 75 ppm, for 1 week (Stott et al. 2003). Although no change in renal histopathology accompanied increased kidney weight in rats exposed to 1,200 ppm ethylbenzene for 4 days (Ethylbenzene Producers Association 1986a), increased accumulation of  $\alpha_{2\mu}$ -globulin and hyaline

### 3. HEALTH EFFECTS

droplets were observed after 1 week in the kidneys of male rats exposed to 750 ppm ethylbenzene compared to controls (Stott et al. 2003). Renal congestion was reported in rats and mice that died during exposure to 2,400 or 1,200 ppm ethylbenzene, respectively (Ethylbenzene Producers Association 1986a). Induction of renal cytochrome P-450 microsomal enzymes (7-ethoxycoumarin, O-deethylase, UDP glucuronyl-transferase, NADPH-cytochrome c reductase) was reported in rats following a 3-day exposure to 2,000 ppm ethylbenzene (Toftgard and Nilsen 1982).

Renal effects of intermediate-duration exposure to inhaled ethylbenzene are similar to those observed following acute exposure (increased kidney weight, induction of renal microsomal enzymes, and changes associated with accumulation of  $\alpha_{2\mu}$ -globulin). Several studies have shown that exposure of rats or mice to inhaled ethylbenzene for durations of 4 weeks –7 months increases relative kidney weight (Elovaara et al. 1985; NIOSH 1981; NTP 1999; Stott et al. 2003; Wolf et al. 1956). Concentration-related increases in renal microsomal enzymes (7-ethoxycoumarin O-deethylase, UDP glucuronyl-transferase) and renal glutathione concentration were reported in rats following a 5–16-week exposure to ethylbenzene at concentrations ranging from 50 to 600 ppm (Elovaara et al. 1985). Histopathological changes in the kidney include  $\alpha_{2\mu}$ -globulin-associated changes (nuclear-size and staining variations and vacuolation or decreased amount of cytoplasm) in male rats exposed to 750 ppm for 4 weeks (Stott et al. 2003) and swelling of the tubular epithelium in rats exposed to 600 ppm ethylbenzene for up to 7 months (Wolf et al. 1956).

Chronic exposure of male and female rats, but not mice, to inhaled ethylbenzene for 2 years resulted in nephropathy and renal tubule hyperplasia (NTP 1999). Although age-related nephropathy was observed in control rats, the severity was increased compared to controls in female rats exposed to  $\geq 75$  ppm and male rats exposed to 750 ppm. The incidence of renal tubular hyperplasia (considered as a preneoplastic effect) was increased in male and female rats exposed to 750 ppm. NTP (1999) concluded that ethylbenzene may have exacerbated the development of age-related nephropathy in rats and that renal tubular lesions were related to exposure. Additional information pertaining to renal carcinogenesis is provided in Section 3.2.1.7.

**Endocrine Effects.** Adverse endocrine effects, based on histopathological examinations of endocrine tissues, have not been observed in laboratory animals exposed to inhaled ethylbenzene for 4 weeks to 6 months (Cragg et al. 1989; NTP 1992; Wolf et al. 1956), although chronic exposure is reported to produce hyperplasia of the thyroid and pituitary (NTP 1999). Mice exposed to 750 ppm ethylbenzene for 2 years showed an increased incidence of follicular cell hyperplasia in the thyroid gland. In female mice

### 3. HEALTH EFFECTS

exposed to  $\geq 250$  ppm ethylbenzene, the incidences of hyperplasia of the pituitary gland pars distalis were significantly greater than those in the control group. No effects on other endocrine tissues were observed in mice and no effects on any endocrine tissue were observed in rats exposed to 750 ppm ethylbenzene for 2 years (NTP 1999).

**Ocular Effects.** Ocular effects observed in humans and animals after inhalation exposure to ethylbenzene are presumed to be due to direct contact of the eyes with ethylbenzene vapor. These effects are discussed in Section 3.2.3.2.

**Body Weight Effects.** Studies in animals examined body weight effects in acute-, intermediate-, and chronic-duration inhalation exposure to ethylbenzene. Mean body weight was not affected in rats or mice exposed to 400 ppm or in rabbits exposed to 2,400 ppm ethylbenzene for 4 days (Ethylbenzene Producers Association 1986a). Rats exposed to 1,200 ppm showed a mean body weight that was lower than in control animals. No effect on body weight was observed in rabbits after 7 days of exposure to 750 ppm (Romanelli et al. 1986).

No changes in body weight were observed in pregnant rats or rabbits exposed to 985 and 962 ppm ethylbenzene, respectively, for 3 weeks prior to mating and throughout gestation (NIOSH 1981). A decrease in body weight gain of 26–48% at weeks 2, 5, and 9, but not at week 16 was observed in male rats exposed to 600 ppm ethylbenzene for 16 weeks (Elovaara et al. 1985). No adverse effect on body weight was observed in rats or mice exposed to 782 ppm or rabbits exposed to 1,610 ppm ethylbenzene for 4 weeks (Cragg et al. 1989). No effect on body weight was observed in rats and mice exposed to 975 ppm ethylbenzene for 90 days (NTP 1992). Similarly, no biologically significant effect on body weight was observed in rats and mice exposed to concentrations of ethylbenzene of up to 750 ppm for 2 years (NTP 1999).

#### 3.2.1.3 Immunological and Lymphoreticular Effects

Angerer and Wulf (1985) reported increased lymphocyte counts in male varnish workers exposed to a mixture of solvents, including ethylbenzene, compared to an unexposed control group. Workers were employed for an average of 8.2 years and exposed to an average ethylbenzene concentration of 1.64 ppm. Average lymphocyte levels increased (41.5–68.8%) in exposed workers, compared to unexposed controls.

### 3. HEALTH EFFECTS

However, due to concomitant exposure to other chemicals (xylenes, lead, toluene), the relationship of adverse hematological effects to inhaled ethylbenzene cannot be established.

Mean total leukocyte count was significantly increased in female rats exposed to 782 ppm ethylbenzene, but not  $\leq 382$  ppm, for 4 weeks (Cragg et al. 1989). Absolute and relative spleen weights were increased in pregnant rats exposed to 1,000 ppm ethylbenzene during pre-mating and gestation or gestation alone, although histopathological changes were not observed (NIOSH 1981). Spleen weight was not affected in rabbits exposed to 1,000 ppm during gestation (NIOSH 1981). No histopathological changes were observed in bone marrow (sternum), lymph nodes, thymic region, or spleen of rats or mice exposed to 782 ppm or rabbits exposed to 1,610 ppm ethylbenzene for 4 weeks (Cragg et al. 1989). No treatment-related effect on the histopathology of several lymphoreticular tissues, including bronchial lymph nodes, regional lymph nodes, mandibular and mesenteric lymph nodes, mediastinal lymph nodes, spleen, or thymus were observed in rats and mice exposed to 975 ppm ethylbenzene for 90 days (NTP 1992) or 750 ppm for 2 years (NTP 1999).

The highest NOAELs for immunological and lymphoreticular effects in each species for intermediate- or chronic-duration exposure are reported in Table 3-1 and plotted in Figure 3-1.

#### 3.2.1.4 Neurological Effects

Symptoms of dizziness accompanied by vertigo have been observed in humans acutely exposed to air concentrations of ethylbenzene ranging from 2,000 to 5,000 ppm for 6 minutes (Yant et al. 1930).

Workers exposed occupationally for a mean of 13 years to solvent mixtures that include ethylbenzene (mean ethylbenzene exposure level 1.8 ppm) showed a 58% incidence of hearing loss compared to 36% in the reference group (Sliwinska-Kowalska et al. 2001). Hearing losses (expressed as increased hearing thresholds) were observed at all frequencies and appeared to range from 3 to 8 dB. The role of ethylbenzene in the observed losses cannot be ascertained from this study given that ethylbenzene was only one of several solvents, most of which were present at mean concentrations 1.5–3.5 times higher than ethylbenzene.

Neurological effects have been observed in several animals following acute-duration exposure to inhaled ethylbenzene, although there is considerable variability in species sensitivity. In general, central nervous

## 3. HEALTH EFFECTS

system depression is associated with acute exposure to higher concentrations, whereas stimulation of the motor nervous system is associated with lower concentrations. The most serious adverse neurological effect associated with acute- and intermediate-duration inhalation exposure to ethylbenzene is ototoxicity, characterized by deterioration in auditory thresholds and alterations of cochlear morphology.

Clinical signs of general central nervous system depression or increased motor activity have been observed in animals acutely exposed to inhaled ethylbenzene. Moderate activation in motor behavior was observed in rats following a 4-hour inhalation exposure to levels of ethylbenzene ranging from 400 to 1,500 ppm, whereas narcotic effects were observed at higher ethylbenzene concentrations (2,180–5,000 ppm) (Molnar et al. 1986). This study is limited by a lack of methodological detail and appropriate statistical analysis. Central nervous system depression (unconsciousness) and ataxia were observed in guinea pigs exposed to 2,000 ppm ethylbenzene for acute-duration periods (Yant et al. 1930). Salivation, prostration, and/or reduced activity were observed in rats and mice exposed to 2,400 or 1,200 ppm ethylbenzene, respectively, for 4 days (Ethylbenzene Producers Association 1986a). However, rabbits exposed to 2,400 ppm ethylbenzene for the same period showed no adverse behavioral effects. Exposure of mice to ethylbenzene for 20 minutes to  $\geq 2,000$  ppm produced changes in posture; decreased arousal and rearing; increased ease of handling; disturbances of gait, mobility, and righting reflex; decreased forelimb grip strength; increased landing foot splay; and impaired psychomotor coordination (Tegeris and Balster 1994). These acute effects were short-lived and more pronounced during exposure than after exposure, with recovery beginning within minutes of removal from the exposure chamber. Sensorimotor reactivity also decreased. Acute exposure of rats and mice to 245 and 342 ppm, respectively (Frantik et al. 1994), resulted in a 30% depression of evoked electrical activity in the brain immediately after exposure.

General signs of neurotoxicity have not been observed in animals exposed to inhaled ethylbenzene for intermediate or chronic durations, although ethylbenzene concentrations evaluated in intermediate- and chronic-duration studies were lower than those evaluated in acute studies. No behavioral changes, clinical signs of neurotoxicity or histopathological alterations of neurological tissues were observed in rats or mice exposed to concentrations of up to 782 ppm or rabbits exposed to concentrations up to 1,610 ppm ethylbenzene for 4 weeks. Sporadic salivation was noted in rats at doses of  $\geq 382$  ppm (Cragg et al. 1989). In a 90-day study (NTP 1992), rats and mice showed no adverse histopathological effects on brain tissue at doses up to 975 ppm. No adverse effects were noted in the brain tissues of rats and mice exposed to concentrations of ethylbenzene of up to 750 ppm for 2 years (NTP 1999).

### 3. HEALTH EFFECTS

Ototoxic effects of inhaled ethylbenzene have been observed following acute- or intermediate-duration exposure of rats. Effects are characterized by deterioration in auditory thresholds and alterations of cochlear morphology. Male rats exposed to ethylbenzene at 800 ppm, 8 hours/day for 5 days showed significant deterioration in auditory thresholds (threshold shifts were 10–20 and 17–28 dB using two methods) 1 and 4 weeks after the exposure had ceased (Cappaert et al. 1999). The magnitude of the increase in thresholds did not change between assessments conducted on post-exposure weeks 1 and 4; threshold shifts were evident at all tested frequencies (1–24 kHz). Eight to 11 weeks after exposure, a significant loss (52–66%) of outer hair cells (OHCs) in the organ of Corti in the auditory region corresponding to 11–21 kHz was observed. No loss of inner hair cells (IHCs) was found in the exposed animals (Cappaert et al. 1999). Similarly, auditory threshold shifts (approximately 15–30 dB) and OHC losses (25–75%) were observed 3–6 weeks after exposure in male rats exposed to 400 or 550 ppm ethylbenzene, 8 hours/day for 5 days. Auditory thresholds and OHC counts were not affected in rats exposed to 300 ppm ethylbenzene (Cappaert et al. 2000, 2001). Cappaert et al. (2002) demonstrated a significant species difference in the susceptibility of rats and guinea pigs to the ototoxic effects of ethylbenzene. Guinea pigs exposed to ethylbenzene at 2,500 ppm, 6 hours/day for 5 days did not show auditory deficits or losses in OHCs. There was no loss of IHCs in either species (Cappaert et al. 2002).

Electrophysiological measures showed significant shifts in auditory thresholds in rats exposed to ethylbenzene at  $\geq 400$  ppm ethylbenzene, 6 hours/day, 6 days/week for 4 weeks (Frantik et al. 1994). Auditory deficits persisted unchanged throughout the 13-week exposure period and the 8-week post-exposure recovery period in rats exposed to  $\geq 400$  ppm ethylbenzene (Gagnaire et al. 2007). Histological assessments conducted after the 8-week recovery period showed significant losses in OHCs in rats exposed to  $\geq 200$  ppm ethylbenzene, 6 hours/day, 6 days/week for 13 weeks (Gagnaire et al. 2007). IHC losses (14–32%) were observed in rats exposed to 600 and 800 ppm ethylbenzene, but only occasionally in rats exposed to 400 ppm (Gagnaire et al. 2007).

The highest NOAEL values and all reliable LOAEL values for neurological effects in each species and duration category are recorded in Table 3-1 and plotted in Figure 3-1.

#### **3.2.1.5 Reproductive Effects**

No studies were located regarding reproductive effects in humans following inhalation exposure to ethylbenzene.

## 3. HEALTH EFFECTS

Adverse reproductive outcome was observed in rabbits exposed to inhaled ethylbenzene during gestation (Ungváry and Tátrai 1985); however, adverse reproductive effects have not been observed in other studies in rabbits, rats, or mice (Faber et al. 2006; NIOSH 1981; Saillenfait et al. 2003, 2006, 2007; Ungváry and Tátrai 1985). Treatment-related effects on reproductive organs, as assessed by histopathological examination, have not been observed (Cragg et al. 1989; Ethylbenzene Producers Association 1986a; Faber et al. 2006; NTP 1992; Wolf et al. 1956).

Pregnant rats exposed to ethylbenzene during gestation exhibited increased postimplantation loss at  $\geq 138$  ppm and rabbits exhibited increased abortions at 230 ppm (Ungváry and Tátrai 1985), however, due to inadequate reporting, it is unclear if effects occurred in the presence or absence of maternal toxicity. No reproductive effects were noted in mice or rabbits exposed during gestation to 115 ppm (Ungváry and Tátrai 1985) or rats exposed to 250–2,000 ppm (Saillenfait et al. 2003, 2006, 2007). No adverse effects on reproduction were observed in female rats and rabbits exposed to approximately 100 or 1,000 ppm ethylbenzene for 3 weeks prior to mating and throughout gestation (NIOSH 1981). Reproductive function and outcome was assessed in a 2-generation reproductive toxicity study in rats exposed to 25, 100, or 500 ppm ethylbenzene starting with a pre-mating exposure of  $\geq 70$  days and continuing through gestation day 20, lactation day 5–21 (oral exposure of mothers on lactation days 1–4), and postnatal day 21 (Faber et al. 2006). Estrous cycle length was significantly reduced in F0 rats in the 500-ppm group (4.0 days vs. 4.4 days in controls), but was not altered in the F1 females. Reproductive parameters (mating or fertility indices, gestation length, number of implantation sites, number of births/litter, and litter size) were not affected in F0 or F1 females (or males, as appropriate) exposed to 25–500 ppm ethylbenzene.

No treatment-related histopathological changes were noted in the testes of rats, mice, or rabbits exposed to concentrations as high as 2,400 ppm ethylbenzene for 4 days (Ethylbenzene Producers Association 1986a). No testicular histopathological abnormalities were reported in rats and mice exposed to 782 ppm and rabbits exposed to ethylbenzene concentrations as high as 1,610 ppm for 4 weeks (Cragg et al. 1989). NTP (1992) reported no effect on sperm or testicular morphology or on the length of the estrous cycle in rats or mice exposed to 975 ppm ethylbenzene for 90 days. Mice showed a decrease in epididymal weight in the 1,000-ppm group; however, this observation was not considered biologically significant since there was no significant difference in spermatid counts, sperm motility, or weight of the caudal epididymis among treated and control animals. Inhalation exposure of male monkeys and rabbits to 600 ppm ethylbenzene for 6 months produced degeneration of germinal epithelium in the testes of one



### 3. HEALTH EFFECTS

monkey and one rabbit (Wolf et al. 1956). No adverse histopathological effects were seen in the testes of rats or guinea pigs exposed to concentrations up to 1,250 or 600 ppm, respectively, for 6–7 months (Wolf et al. 1956). In a 2-generation reproduction study, no effects were observed on sperm number, motility, and morphology in F0 and F1 rats exposed to 25–500 ppm ethylbenzene (Faber et al. 2006).

The highest NOAEL values and all reliable LOAEL values for reproductive effects in each species for acute-, intermediate-, and chronic-duration are recorded in Table 3-1 and plotted in Figure 3-1.

#### 3.2.1.6 Developmental Effects

No studies were located regarding developmental effects in humans following inhalation exposure to ethylbenzene.

The developmental effects of inhaled ethylbenzene have been studied in rats (NIOSH 1981; Ungváry and Tátrai 1985), mice (Ungváry and Tátrai 1985), and rabbits (NIOSH 1981; Ungváry and Tátrai 1985) exposed during gestation or pre-mating and gestation, rats exposed from pre-gestation through lactation (Faber et al. 2006), and in a 2-generation reproduction study in rats (Faber et al. 2007). Results of studies in rats indicate that ethylbenzene produces reduced fetal weight, skeletal anomalies, and anomalies and delayed development of urogenital tract; skeletal and urogenital anomalies were observed in the presence of maternal toxicity (Faber et al. 2006; NIOSH 1981; Ungváry and Tátrai 1985). Studies conducted by Faber et al. (2006, 2007) and NIOSH (1981) are of high quality and guideline-compliant. However, usefulness of the Ungváry and Tátrai (1985) study is hampered by incomplete descriptions of the results and because an analysis of the results on a per litter basis was not provided.

In rats, continuous inhalation exposure to ethylbenzene on gestational days 7–15 to concentrations ranging from 138 to 552 ppm resulted in fetal resorption and a concentration-related retardation of skeletal development in surviving fetuses (Ungváry and Tátrai 1985). Retarded skeletal development was observed in 28, 30, and 35% of fetuses exposed to 138, 276, and 552 ppm ethylbenzene, respectively. Increased incidence of extra ribs and anomalies of the urinary tract (specific effects not reported) were observed in 7% of fetuses at 552 ppm, but were not observed in controls. Maternal toxicity was reported to be moderate and dose-dependent, but data were not presented. In this same study, the incidence of anomalies of the uropoietic apparatus (not specified) was observed in the offspring of mice exposed to 115 ppm ethylbenzene on gestation days 6–15, although no adverse developmental effects were observed

## 3. HEALTH EFFECTS

after exposure of rats to 138 ppm for 6 hours/day on gestation days 7–15 (Ungváry and Tátrai 1985). Anomalies of the uropoietic apparatus were not observed in other developmental studies (Faber et al. 2006, 2007; Saillenfait et al. 2003, 2006, 2007). Since Ungváry and Tátrai (1985) did not include sufficient details regarding the adverse fetal effects, dictating caution in the interpretation of study findings.

In a NIOSH study conducted by Andrews et al. (NIOSH 1981), increases in the incidences of fetuses with extra ribs were observed in the offspring of rats exposed to 100 or 1,000 ppm ethylbenzene through gestation day 19 or 1,000 ppm during pre-mating and gestation. The incidence of supernumerary ribs was increased only in the offspring of rats exposed to 1,000 ppm during gestation. Reduced pup crown-rump length and an increased incidence of supernumerary ribs were observed in the offspring of rats exposed to 1,000 ppm during gestation, but not in the offspring of rats exposed to 1,000 ppm during pre-mating and gestation. No other significant increases in major malformations or minor anomalies were observed. There was some evidence of maternal toxicity (increased relative liver, kidney, and spleen weights) in rats exposed to 1,000 ppm ethylbenzene during pre-mating and gestation or gestation only (NIOSH 1981).

Statistically significant reductions in fetal body weight were observed in the offspring of pregnant rats exposed to  $\geq 1,000$  ppm ethylbenzene during gestation (Saillenfait et al. 2003, 2006, 2007), but not in rats exposed to 500 ppm (Saillenfait et al. 2003) or 250 ppm (Saillenfait et al. 2006, 2007). A significant increase in the number of fetuses with fetal malformations (mostly skeletal variations) was observed in the offspring of rats exposed to  $\geq 1,000$  ppm ethylbenzene (Saillenfait et al. 2003, 2006, 2007). On a per litter basis, a significant increase in the incidence of fetal malformations was observed only at 2,000 ppm (Saillenfait et al. 2003). Maternal toxicity was observed in rats exposed to  $\geq 1,000$  ppm, as indicated by significant reductions in maternal weight gain compared to control animals (Saillenfait et al. 2003, 2006, 2007).

Survival from birth to postnatal days (PND) 4 and 21 was not affected in F1 or F2 offspring of pregnant rats exposed to ethylbenzene at 25, 100, or 500 ppm during pre-mating, mating, gestation, and lactation (Faber et al. 2006). A statistically significant delay in balanopreputial separation was observed in F1 males in the 500 ppm group, although the mean age at separation in that group (44.7 days) was similar to that observed in historical controls (44.8 days). No exposure-related macroscopic findings or changes in organ weight in F1 pups necropsied on PND 21 were observed.

### 3. HEALTH EFFECTS

Results of a 2-generation reproduction study in rats show that the mean age at acquisition of vaginal patency was significantly reduced in F1 females at 25, 100, and 500 ppm; however, the values in the treated groups (33.3–33.9 days) were similar to the historical control value (33.4 days) in the conducting laboratory (Faber et al. 2006). F2 generation pups (which were not exposed to ethylbenzene by inhalation) did not show differences from controls in the age at preputial separation or vaginal patency (Faber et al. 2007). Developmental landmarks (pinna detachment, hair growth, incisor eruption, and eye opening) were not affected in F1 male or female pups exposed to 25–500 ppm ethylbenzene (Faber et al. 2006); however, in the F2 generation, statistically significant delays in hair growth were observed in males and females in all exposure groups and eye opening was significantly delayed in males the 25 and 100 ppm groups, but not in the 500 ppm group (Faber et al. 2007). Neurodevelopmental tests conducted on subsets of the F2 offspring (Faber et al. 2007) did not show statistically significant differences from controls in a functional observational battery assessment or in fore- or hind-limb grip strength. Although the data suggest an increase in motor activity in F2 males and females in the 25–500 ppm groups on PNDs 13 and 17, there were no statistical differences in motor activity on PNDs 13, 17, and 21 between exposed and control animals (Faber et al. 2007). A statistically significant increase in motor activity was observed on PND 61 in F2 females in the 25 ppm group only. Startle response was not affected in F2 rats of either sex on PND 20 or females on PND 60; F2 males showed statistically lower startle responses, but this was attributed to highly variable and abnormal responses in some control animals. Swimming ability, learning, and memory assessments conducted in a Biel water maze did not reveal any significant effects in F2 animals in any of the exposure groups (Faber et al. 2007). No morphometric or histologic effects in brains of F2 animals were observed from any exposure group on PND 21 or 72 (Faber et al. 2007).

Reduced fetal weight was observed in female rats exposed to 115 ppm during gestation (Ungváry and Tátrai 1985). In the offspring of rabbits exposed to ethylbenzene, no treatment-related effects were observed in fetal size, placental weight, or intrauterine growth retardation and there were no significant incidences of major malformations, minor anomalies, or common variants observed in the absence of maternal toxicity (NIOSH 1981).

The highest NOAEL values and all reliable LOAEL values for developmental effects in each species and duration category are recorded in Table 3-1 and plotted in Figure 3-1.

## 3. HEALTH EFFECTS

**3.2.1.7 Cancer**

No association has been found between the occurrence of cancer in humans and occupational exposure to ethylbenzene. No cases of malignancy were observed in workers exposed to ethylbenzene monitored for 20 years (Bardodej and Cirek 1988). No information on ethylbenzene concentrations was reported, although an estimated concentration of 6.4 mg/m<sup>3</sup> was derived as described above under hematological effects (Section 3.2.1.3). However, no clear conclusions can be drawn from this study due to the lack of measured ethylbenzene concentrations. Furthermore, the low exposure concentration limited the power of this study to detect any effect. No other studies were found regarding cancer effects in humans exposed to ethylbenzene by inhalation.

Information concerning the carcinogenicity of ethylbenzene in animals comes from an NTP-sponsored bioassay in male and female rats and mice exposed to 0, 75, 250, or 750 ppm ethylbenzene for up to 2 years (NTP 1999). NTP (1999) concluded that ethylbenzene showed clear evidence of carcinogenic activity in male rats based on increased incidences of renal tubule neoplasms and testicular adenomas, some evidence of carcinogenic activity in female rats based on increased incidences of renal tubule adenomas, some evidence of carcinogenic activity in male mice based on increased incidences of alveolar/bronchiolar neoplasms, and some evidence of carcinogenic activity in female mice based on increased incidences of hepatocellular neoplasms (NTP 1999).

Pathological findings in male and female rats exposed to 750 ppm ethylbenzene showed significant increases in the incidence of renal tubule adenoma and adenoma or carcinoma (combined) compared to control animals. An extended histopathological evaluation of the kidneys showed significant increases in the incidence of nephropathy and of renal tubular hyperplasia (a preneoplastic lesion) in male rats exposed to 750 ppm; in female rats, nephropathy was observed at concentrations  $\geq 75$  ppm and renal tubular hyperplasia was only observed at a concentration of 750 ppm. In a reevaluation of the histopathology of rat kidneys from the NTP study, Hard (2002) confirmed the NTP (1999) findings and suggested that the increase incidence of kidney tumors in rats in the high-dose group was related to a chemical-induced exacerbation of chronic progressive nephropathy (CPN), with a minor contributing factor in male rats being  $\alpha_2\mu$ -globulin nephropathy. However, in an analysis of the association between CPN and renal tubule cell neoplasms in male F344 rats, Seely et al. (2002) concluded that the association between CPN and renal tubule cell neoplasms is marginal. Results of this analysis suggest that the number of renal tubule cell neoplasm's secondary to CPN would be few (Seely et al. 2002). The incidence of interstitial cell adenoma in the testes of males exposed to 750 ppm was significantly greater

### 3. HEALTH EFFECTS

than in the control group and slightly exceeded the historical control range for inhalation studies. The incidence of bilateral testicular adenoma was also significantly increased in males exposed to 750 ppm.

In male mice, the incidences of alveolar/bronchiolar adenoma and alveolar/bronchiolar adenoma or carcinoma (combined) were significantly greater in males exposed to 750 ppm than in the controls. No significant increase in the incidence of neoplastic lung lesions was observed in female rats. The incidences of hepatocellular adenoma and hepatocellular adenoma or carcinoma (combined) were significantly greater in female mice exposed to 750 ppm than in the control group. Hepatocellular adenomas or carcinomas were not observed in male mice.

#### **3.2.2 Oral Exposure**

##### **3.2.2.1 Death**

No studies were located regarding death in humans following oral exposure to ethylbenzene.

Lethality has been observed in laboratory animals following ingestion of ethylbenzene. The oral LD<sub>50</sub> for gavage administration of ethylbenzene was reported to be 4,769 mg/kg ethylbenzene in rats (Smyth et al. 1962). In another oral study with rats exposed to ethylbenzene, the LD<sub>50</sub> was reported to be approximately 3,500 mg/kg ethylbenzene (Wolf et al. 1956). The usefulness of these data is limited since the study methodology was not provided.

An oral LD<sub>50</sub> value for rats is recorded in Table 3-2 and plotted in Figure 3-2.

##### **3.2.2.2 Systemic Effects**

No studies were located describing respiratory, cardiovascular, gastrointestinal, hematological, musculoskeletal, hepatic, renal, endocrine, dermal, ocular, body weight, or metabolic effects in humans or gastrointestinal, musculoskeletal, endocrine, dermal, ocular, body weight, or metabolic effects in animals after oral exposure to ethylbenzene.

The highest NOAEL values and all reliable LOAEL values are recorded in Table 3-2 and plotted in Figure 3-2.

Table 3-2 Levels of Significant Exposure to Ethylbenzene - Oral

Key to Figure	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (mg/kg/day)	LOAEL		Reference Chemical Form	Comments
					Less Serious (mg/kg/day)	Serious (mg/kg/day)		
<b>ACUTE EXPOSURE</b>								
<b>Death</b>								
1	Rat (Carworth-Wistar)	once (G)				4769 M (LD50)	Smyth et al. 1962	
<b>Neurological</b>								
2	Rat (SD)	1 x/d 5 d/wk 2 wk (G)				900 M (complete loss of outer hair cells in cochlea)	Gagnaire and Langlais 2005	
<b>INTERMEDIATE EXPOSURE</b>								
<b>Systemic</b>								
3	Rat (Wistar)	4 wk 7 d/wk 2 x/d (GO)	Resp	750			Mellert et al. 2007	
			Cardio	750				
			Hemato	750				
			Hepatic	75 M	250 M (increased absolute and relative liver weights, increased incidence of centrilobular hepatocyte hypertrophy)			
			Renal	75 M	250 M (hyaline droplet nephropathy)			

\*\*\*DRAFT FOR PUBLIC COMMENT\*\*\*

Table 3-2 Levels of Significant Exposure to Ethylbenzene - Oral

(continued)

Key to Figure <sup>a</sup>	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (mg/kg/day)	LOAEL		Reference Chemical Form	Comments
					Less Serious (mg/kg/day)	Serious (mg/kg/day)		
4	Rat (Wistar)	13 wk 7 d/wk 2 x/d (GO)	Resp	750			<a href="#">Mellert et al. 2007</a>	
			Cardio	750				
			Hemato	250	750	(increased mean corpuscular volume in males and females, decreased platelet counts in females)		
			Hepatic	<sup>b</sup> 75	250	(increased serum liver enzymes in males, increased absolute and relative liver weights in males and females, increased incidence of centrilobular hepatocyte hypertrophy in males and females)		
			Renal	75 M	250 M	(hyaline droplet nephropathy)		

Table 3-2 Levels of Significant Exposure to Ethylbenzene - Oral

(continued)

Key to Figure	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (mg/kg/day)	LOAEL		Reference Chemical Form	Comments
					Less Serious (mg/kg/day)	Serious (mg/kg/day)		
5	Rat	6 mo 5 d/wk 1 x/d (GO)	Hemato	680 F			<a href="#">Wolf et al. 1956</a>	Quality of study is poor, with inadequate descriptions of study methods and results.
			Hepatic	136 F	408 F (increased liver weight; cloudy swelling of parenchymal liver cells)			
			Renal	136 F	408 F (increased kidney weight; cloudy swelling of kidney tubular epithelium)			
<b>Neurological</b>								
6	Rat (Wistar)	4 wk 7 d/wk 2 x/d (GO)		750			<a href="#">Mellert et al. 2007</a>	
7	Rat (Wistar)	13 wk 7 d/wk 2 x/d (GO)		750			<a href="#">Mellert et al. 2007</a>	NOAEL based on absence of histopathological findings of neurological tissues and negative findings for assessment of motor activity and FOB.
<b>Reproductive</b>								
8	Rat (Wistar)	4 wk 7 d/wk 2 x/d (GO)		750			<a href="#">Mellert et al. 2007</a>	



Table 3-2 Levels of Significant Exposure to Ethylbenzene - Oral

(continued)


Key to Figure	Species (Strain)	Exposure/ Duration/ Frequency (Route)	System	NOAEL (mg/kg/day)	LOAEL		Reference Chemical Form	Comments
					Less Serious (mg/kg/day)	Serious (mg/kg/day)		
9	Rat (Wistar)	13 wk 7 d/wk 2 x/d (GO)		750			Mellert et al. 2007	NOAEL based on absence of histopathological findings of reproductive tissues.

a The number corresponds to entries in Figure 3-2.

b Study results used to derive an intermediate-duration oral minimal risk level (MRL) of 0.5 mg/kg/day for ethylbenzene, as described in detail in Appendix A. Benchmark dose (BMD) analysis was performed on incidences of centrilobular hepatocyte hypertrophy to select a point of departure (BMDL10 = 48.2), which was divided by an uncertainty factor of 100 (10 for extrapolation from animals to humans and 10 for human variability)

d = day(s); F = Female; (G) = gavage; (GO) = gavage in oil; Hemato = hematological; LD50 = lethal dose, 50% kill; LOAEL = lowest-observed-adverse-effect level; M = male; mo = month(s); NOAEL = no-observed-adverse-effect level; x = time(s); wk = week(s)

Figure 3-2 Levels of Significant Exposure to Ethylbenzene - Oral  
Acute (≤14 days)



\*\*\*DRAFT FOR PUBLIC COMMENT\*\*\*



## 3. HEALTH EFFECTS

**Respiratory Effects.** No clinical signs of respiratory effects or histopathological findings in respiratory tissues were observed in male and female rats exposed to 750 mg/kg/day by gavage for 4 or 13 weeks (Mellert et al. 2007). No respiratory effects were observed in female rats orally exposed to 680 mg/kg ethylbenzene by gavage for 6 months (Wolf et al. 1956). The utility of this study is limited because of poor protocol description.

**Cardiovascular Effects.** No histopathological findings were made in cardiac tissue from male and female rats exposed to 750 mg/kg/day by gavage for 4 or 13 weeks (Mellert et al 2007) or from female rats exposed to 13.6–680 mg/kg via gavage for 6 months (Wolf et al. 1956)

**Hematological Effects.** Decreased platelet count was observed in females administered 750 mg/kg/day and increased mean corpuscular volume was observed in males and females exposed to  $\geq 250$  mg/kg/day ethylbenzene by gavage for 13 weeks (Mellert et al 2007). No effects on hematological parameters were observed in rats treated for 4 weeks (Mellert et al. 2007). No adverse effects on bone marrow counts or histopathology were reported in female rats orally exposed to 13.6–680 mg/kg ethylbenzene by gavage for 6 months (Wolf et al. 1956). The usefulness of this study is limited by the poorly described and limited results that were provided.

**Hepatic Effects.** Effects indicative of liver toxicity were observed in male and female rats exposed to oral ethylbenzene for 4 and 13 weeks (Mellert et al. 2007). After 4 weeks of exposure, observed effects consistent with hepatotoxicity included increased absolute and relative liver weights ( $\geq 250$  mg/kg/day in males and 750 mg/kg/day in females), increased incidence of hepatocyte centrilobular hypertrophy ( $\geq 250$  mg/kg/day in males and 750 mg/kg/day in females), and increase serum liver enzyme activity (ALT) (750 mg/kg/day in males and females) (Mellert et al. 2007). After 13 weeks of exposure, increased activity of serum liver enzymes (ALT and GGT) in males ( $\geq 250$  mg/kg/day) and females (750 mg/mg/day), increased absolute and relative liver weights ( $\geq 250$  mg/kg/day in males and females), and a dose-related increase in the incidence of centrilobular hepatocyte hypertrophy ( $\geq 250$  mg/kg/day in males and females) were observed. Increased bilirubin ( $\leq 250$  mg/kg/day in males and 750 mg/kg/day in females), total protein (750 mg/kg/day in females), albumin (750 mg/kg/day in males and females), globulins (750 mg/kg/day in females), and cholesterol ( $\leq 250$  mg/kg/day in males and females), and decreased prothrombin time (750 mg/kg/day in males and  $\geq 250$  mg/kg/day in females) were considered by study investigators as adaptive effects in the liver. In males in the 75 mg/k/day group, relative liver weight was significantly increased by (4% compared to controls); however, no histopathological changes,

### 3. HEALTH EFFECTS

or increases in absolute liver or serum liver enzyme activities were observed at this dosage. Given that ethylbenzene is a microsomal enzyme inducer, and the absence of histopathology and other evidence of liver injury at the 75 mg/kg/day dosage, the small increase in relative liver weight in male rats was at this dosage not considered evidence for an adverse effect on the liver (Mellert et al. 2007). Histopathological changes characterized by cloudy swelling of parenchymal cells of the liver and an increase in liver weight were observed in female rats administered 408 mg/kg/day for 6 months (Wolf et al. 1956). No other hepatic changes were reported. No liver effects were observed in female rats administered 136 mg/kg/day. No conclusions could be drawn from these results because of serious weaknesses in the methodology and reporting of the data, including incidence data and statistical analyses.

**Renal Effects.** Renal effects in males administered ethylbenzene by gavage for 13 weeks included increased serum creatinine (750 mg/kg/day), increased incidences of transitional epithelial cells and granular and epithelial cell casts in the urine ( $\geq 250$  mg/kg/day), increased absolute and relative kidney weights ( $\geq 250$  mg/kg/day), and a dose-related increase in severity of hyaline droplet nephropathy ( $\geq 250$  mg/kg/day) (Mellert et al. 2007). Adverse renal effects in males were most likely related to accumulation of  $\alpha_2\mu$ -globulin accumulation, and, therefore, considered not relevant to humans. Similar renal findings were observed in male rats exposed for 4 weeks (administered ethylbenzene by gavage for 13 weeks). Absolute kidney weight was significantly increased by 7 and 13% in females administered 250 and 750 mg/kg-day, respectively, compared to controls. However, since no histopathological findings or alterations in urinalysis parameters were observed, increased kidney weight in females was not considered evidence for renal toxicity in female rats. The only animal study that investigated renal effects following ethylbenzene exposure involved female rats administered 13.6–680 mg/kg/body weight ethylbenzene by gavage for 6 months (Wolf et al. 1956). Histopathological changes characterized as cloudy swelling of the tubular epithelium in the kidney and an increase in kidney weight were observed at the 408 mg/kg/day dose level. No other renal changes were reported. As in hepatic effects, no conclusions could be drawn from these results because of serious weaknesses in the methodology and reporting of the data (e.g., no data on the number of animals with renal effects). Furthermore, no statistical analysis was performed.

#### 3.2.2.3 Immunological and Lymphoreticular Effects

No studies were located regarding immunological effects in humans following oral exposure to ethylbenzene.

### 3. HEALTH EFFECTS

Absolute and relative thymus weights were significantly decreased in females treated with  $\geq 250$  mg/kg/day for 13 weeks, but no histopathological findings were observed (Mellert et al. 2007). Therefore, effects were not considered adverse.

#### 3.2.2.4 Neurological Effects

No studies were located regarding neurological effects in humans following oral exposure to ethylbenzene.

Significant ototoxic effects were observed in male rats administered 900 mg/kg/day (the only dose tested) by gavage for 2 weeks (Gagnaire and Langlais 2005). The authors reported an almost complete loss of the three rows of OHCs in the organ of Corti 10 days after the last exposure to ethylbenzene. This study did not have a control group to clearly establish the magnitude of the effects relative to unexposed animals; nevertheless, this study showed that the losses observed in ethylbenzene-exposed animals were among the highest observed among 21 organic solvents tested (Gagnaire and Langlais 2005). No ethylbenzene-related behavioral changes were observed in female rats administered 13.6–680 mg/kg/day ethylbenzene by gavage for 6 months (Wolf et al. 1956). No other parameters were investigated. The utility of this study is limited because the monitored behavioral changes were not reported, and the study protocol was poorly described.

In male and female rats exposed to 75–750 mg/kg/day ethylbenzene by gavage for 13 weeks, no neurological effects were observed, based on negative results of motor activity tests and a functional observational battery (FOB) (Mellert et al. 2007). However, assessments of ototoxicity were not conducted; therefore, it is not possible to determine whether ototoxicity occurred in the 13-week study.

#### 3.2.2.5 Reproductive Effects

No studies were located regarding reproductive effects in humans following oral exposure to ethylbenzene.

The only available reproduction study reported that acute oral exposure to 500 or 1,000 mg/kg ethylbenzene decreases peripheral hormone levels and may block or delay the estrus cycle in female rats

### 3. HEALTH EFFECTS

during the diestrus stage (Ungváry 1986). Decreased levels of hormones, including luteinizing hormone, progesterone, and 17  $\beta$ -estradiol, were accompanied by uterine changes, which consisted of increased stromal tissue with dense collagen bundles and reduced lumen. No dose response was noted. The study is limited by the absence of statistical analysis of the data.

No histopathological findings of reproductive tissues were observed in male and female rats exposed to 750 mg/kg/day by gavage for 4 or 13 weeks (Mellert et al. 2007).

#### **3.2.2.6 Developmental Effects**

No studies were located regarding developmental effects in humans or animals following oral exposure to ethylbenzene.

#### **3.2.2.7 Cancer**

No studies were located regarding carcinogenic effects in humans following oral exposure to ethylbenzene.

The carcinogenicity of ethylbenzene by the oral route has been evaluated in a chronic-duration study in Sprague-Dawley rats (Maltoni et al. 1985). A statistically significant increase in total malignant tumors was reported in females and in combined male and female groups exposed to 500 mg kg/day via gavage for 104 weeks and observed until after week 141. No data on specific tumor type were presented, only one dose was tested, and no information on survival was provided.

### **3.2.3 Dermal Exposure**

#### **3.2.3.1 Death**

No studies were located regarding lethal effects in humans following only dermal exposure to ethylbenzene. Matsumoto et al. (1992) reported the case of a 44-year-old man who died 9 days after being massively exposed to gasoline (which contained ethylbenzene) dermally and by inhalation for  $\geq 10$  hours.

### 3. HEALTH EFFECTS

The dermal LD<sub>50</sub> in rabbits exposed to liquid ethylbenzene (applied to clipped skin subsequently covered with an impervious plastic film) was calculated to be 15,433 mg/kg/body weight (Smyth et al. 1962). No additional studies were located regarding death in animals following dermal exposure to ethylbenzene.

#### 3.2.3.2 Systemic Effects

No studies were located regarding respiratory, cardiovascular, gastrointestinal, hematological, musculoskeletal, hepatic, renal, endocrine, body weight, or metabolic effects in humans or animals after dermal exposure to ethylbenzene.

The systemic effects observed after dermal exposure to ethylbenzene are discussed below. The highest NOAEL values and all reliable LOAEL values for each species and duration category are recorded in Table 3-3.

**Dermal Effects.** No studies were located regarding dermal effects in humans following dermal exposure to ethylbenzene.

Liquid ethylbenzene applied directly to the skin of an unspecified number of rabbits caused irritation characterized by reddening, exfoliation, and blistering (Wolf et al. 1956). Mild dermal irritation (grade 2 on a scale of 10) was also noted in New Zealand White rabbits 24 hours after application of ethylbenzene to clipped skin (Smyth et al. 1962).

**Ocular Effects.** Ocular effects observed in humans and animals after inhalation exposure are assumed to be due to exposure of the mucous membranes of the eye to ethylbenzene vapor. Volunteers reported eye irritation and burning, and profuse lacrimation, which gradually decreased with continued exposure to 1,000 ppm for 1–6 minutes (Yant et al. 1930). Upon entering the chamber with an ethylbenzene concentration of 2,000 or 5,000 ppm, the volunteers also experienced severe eye irritation. Cometto-Muñiz and Cain (1995) reported eye irritation in humans after exposure to ethylbenzene vapor. Eye irritation was observed at 10,000 ppm.

Liquid ethylbenzene applied directly to the eyes of rabbits for an unspecified duration caused slight irritation of conjunctival membranes (Wolf et al. 1956) and slight corneal injury (Smyth et al. 1962; Wolf et al. 1956).



Table 3-3 Levels of Significant Exposure to Ethylbenzene - Dermal

Species (Strain)	Exposure/Duration/Frequency (Route)	System	NOAEL	LOAEL		Reference Chemical Form	Comments
				Less Serious	Serious		
<b>ACUTE EXPOSURE</b>							
<b>Death</b>							
Rabbit (New Zealand)	24 hr				15433 M (LD50) mg/kg/day	Smyth et al. 1962	
<b>Systemic</b>							
Rabbit (New Zealand)	24 hr	Dermal		8.67 mg	(grade 4 skin irritation)	Smyth et al. 1962	
<b>INTERMEDIATE EXPOSURE</b>							
<b>Systemic</b>							
Rat (F344/N)	13 wk 5 d/wk 6 hr/d	Ocular	975 B ppm			NTP 1992	
Mouse (B6C3F1)	13 wk 5 d/wk 6 hr/d	Ocular	975 B ppm			NTP 1992	

B = both male and female; d = day(s); hr = hour(s); LD50 = lethal dose, 50% kill; LOAEL = lowest-observed-adverse-effect level; M = male; NOAEL = no-observed-adverse-effect level; ppm = parts per million; wk = week(s)

\*\*\*DRAFT FOR PUBLIC COMMENT\*\*\*

### 3. HEALTH EFFECTS

Irritant effects from exposure to ethylbenzene vapor have been reported in animals. Tegeris and Balster (1994) reported lacrimation and palpebral closure in mice after 20 minutes of exposure to 2,000 ppm ethylbenzene. Eye irritation was observed in guinea pigs exposed to 1,000 ppm for 8 minutes, and in animals exposed to 2,000, 5,000, and 10,000 ppm for 480, 30, and 10 minutes, respectively (Yant et al. 1930). Lacrimation was observed in rats exposed to 1,200 ppm ethylbenzene and in mice and rabbits exposed to 400 ppm ethylbenzene for 4 days (Ethylbenzene Producers Association 1986a). After 4 weeks of exposure to 382 ppm, rats showed sporadic lacrimation, whereas mice and rabbits showed no ocular effects at 782 and 1,610 ppm, respectively (Cragg et al. 1989). No ocular effects were seen in rats or mice after a 13-week exposure to 975 ppm ethylbenzene (NTP 1992).

No studies were located regarding the following health effects in humans or animals after dermal exposure to ethylbenzene:

#### **3.2.3.3 Immunological and Lymphoreticular Effects**

#### **3.2.3.4 Neurological Effects**

#### **3.2.3.5 Reproductive Effects**

#### **3.2.3.6 Developmental Effects**

#### **3.2.3.7 Cancer**

### **3.3 GENOTOXICITY**

Holz et al. (1995) reported no increase in sister chromatid exchanges, DNA adduct formation, micronuclei, or DNA single-strand breaks in the peripheral lymphocytes of workers exposed to low levels of ethylbenzene and other aromatic hydrocarbons (benzene, toluene, and xylene) in a styrene plant. NTP (1992) showed no increase in micronucleated peripheral erythrocytes in mice exposed to 1,000 ppm ethylbenzene for 13 weeks. Another *in vivo* study investigated the genotoxic effects of ethylbenzene and reported no dose-dependent increase in the frequency of micronucleated polychromatic erythrocytes in mice (Mohtashamipur et al. 1985). This study is limited by inadequate sampling time. In addition, the type of clastogenic effect occurring cannot be defined. These data are shown in Table 3-4.

## 3. HEALTH EFFECTS

**Table 3-4. Genotoxicity of Ethylbenzene *In Vivo***

Species (test system)	End point	Results		Reference
		With activation	Without activation	
Mammalian cells:				
Mouse (peripheral erythrocytes)	Micronuclei	NA	–	NTP 1999
Human (occupational exposure/peripheral lymphocytes)	DNA adducts, micronuclei, sister chromatid exchange, DNA strand breaks	NA	–	Holz et al. 1995

– = negative result; NA = not applicable

## 3. HEALTH EFFECTS

The genotoxic potential of ethylbenzene has been investigated primarily using *in vitro* assays in *Salmonella typhimurium* (Dean et al. 1985; Degirmenci et al. 2000; Florin et al. 1980; Kubo et al. 2002; Nestmann et al. 1980; NTP 1986, 1999), *Escherichia coli* (Dean et al. 1985), *Saccharomyces cerevisiae* (Dean et al. 1985; Nestmann and Lee 1983), Chinese hamster ovary cells (NTP 1986, 1999), mouse lymphoma cells (McGregor et al. 1988; NTP 1999), and human lymphocytes (Norppa and Vainio 1983a). Results of these *in vitro* genotoxicity studies are shown in Table 3-5. The available data indicate that ethylbenzene is not mutagenic in bacteria or yeast cells in the presence or absence of metabolic activation. Ethylbenzene also failed to induce sister-chromatid exchanges and chromosomal aberrations in Chinese hamster cells. However, ethylbenzene was found to be mutagenic at 80 mg/L without metabolic activation, and lethal to cells at 100 mg/L in the mouse lymphoma assays (McGregor et al. 1988). No dose-response was reported. A weak positive response was observed when ethylbenzene was tested for sister chromatid exchanges in human lymphocytes (Norppa and Vainio 1983a). Chromosomal aberrations were observed in peripheral blood lymphocytes of workers concomitantly exposed to ethylbenzene (0.2–13.1 mg/m<sup>3</sup>) and benzene (0.4–15.1 mg/m<sup>3</sup>). Although reduction in exposure (reduced ethylbenzene and benzene concentrations not reported) reduced chromosomal aberrations, due to concomitant exposure to benzene, an association between chromosomal damage and ethylbenzene exposure cannot be established (Sram et al. 2004). Metabolites of ethylbenzene (ethylhydroquinone and 4-ethylcatechol) produced oxidative damage to DNA from the human P53 tumor suppressor gene and from calf thymus (Midorikawa et al. 2004).

In summary, genotoxicity studies on ethylbenzene have provided negative results in a variety of *in vitro* assays using numerous prokaryotic organisms, *S. cerevisiae*, and Chinese hamster ovary cells and rat liver epithelial cells, and in an *in vivo* assay using mouse bone marrow cells. Ethylbenzene has, however, caused a mutagenic effect in mouse lymphoma cells and has been shown to induce a marginal, yet statistically significant, increase in sister chromatid exchanges in human lymphocytes. In addition, ethylbenzene metabolites have been shown to produce DNA damage. Thus, although the majority of the data suggest that ethylbenzene is not mutagenic in most systems, the two studies that showed positive results suggest that ethylbenzene might cause an increased potential for genotoxicity in humans.

## 3. HEALTH EFFECTS

**Table 3-5. Genotoxicity of Ethylbenzene *In Vitro***

Species (test system)	End point	Results		Reference
		With activation	Without activation	
Prokaryotic organisms:				
<i>Salmonella typhimurium</i> (plate incorporation assay)	Gene mutation	–	–	Dean et al. 1985 <sup>a</sup> ; Florin et al. 1980 <sup>b</sup> ; Nestmann et al. 1980 <sup>c</sup>
<i>S. typhimurium</i> (plate incorporation assay; strains TA87, TA98, TA100, TA1537; TA1538)	Gene mutation	–	–	NTP 1986 <sup>d</sup>
<i>S. typhimurium</i> (plate incorporation assay; strains TA97, TA98, TA100, TA1535)	Gene mutation	–	–	NTP 1999 <sup>d</sup>
<i>Escherichia coli</i> WP <sub>2</sub> , WP <sub>2</sub> uvrA	Gene mutation	–	–	Dean et al. 1985 <sup>a</sup>
Eukaryotic organisms:				
<i>Saccharomyces cerevisiae</i> JD1 gene conversion assay	Gene mutation	–	–	Dean et al. 1985
<i>S. cerevisiae</i> Dy, XV185-14C	Gene mutation	–	No data	Nestmann and Lee 1983
Mammalian cells:				
Mouse lymphoma cells	Gene mutation	No data	+	McGregor et al. 1988
Mouse lymphoma cells	Gene mutation	No data	+	NTP 1999
Rat liver (RL4) epithelial type cells/chromosome assay	Chromosome damage	–	–	Dean et al. 1985
Chinese hamster ovary cells	Sister chromatid exchange	–	–	NTP 1986
Chinese hamster ovary cells	Sister chromatid exchange	–	–	NTP 1999
Chinese hamster ovary cells	Chromosome damage	–	–	NTP 1999

<sup>a</sup>Concentrations of ethylbenzene tested: 0, 0.2, 2, 20, 500, or 2,000 µg/plate (>99% pure)

<sup>b</sup>Concentrations of ethylbenzene tested: 0, 3, 31, 318, or 3,184 µg/plate (0, 0.03, 0.3, 3, or 30 µmole/plate)

<sup>c</sup>Concentrations of ethylbenzene tested: up to 0.4 mg/plate, a concentration causing lethality

<sup>d</sup>Concentrations of ethylbenzene tested: 0, 10, 33, 110, 333, 666, or 1,000 µg/plate

– = negative result; + = positive result

## 3. HEALTH EFFECTS

**3.4 TOXICOKINETICS**

Ethylbenzene is absorbed from the lungs, gastrointestinal tract, and through the skin. Absorbed ethylbenzene is rapidly eliminated (blood  $t_{1/2} \leq 1$  hour) by metabolism and excretion of metabolites. The major metabolic pathways are side chain and ring hydroxylation with subsequent formation of O-glucuronide and sulfate conjugates. Conjugates, mandelic acid and phenylglyoxylic acid are the primary excreted metabolites. The distribution of ethylbenzene to tissues has been modeled as a flow-limited process (i.e., clearance from blood to tissues can be predicted by tissue blood flow) with rapid equilibrium achieved between blood and tissues. Measured blood:tissue partition coefficients in the rat are approximately as follows: fat, 36; liver, 2; and muscle, 0.6. These values predict the same order for tissue concentrations for any given blood concentration; however, this order has not been verified experimentally with simultaneously measured blood and tissue ethylbenzene concentrations *in vivo*.

**3.4.1 Absorption****3.4.1.1 Inhalation Exposure**

Inhalation studies in humans demonstrate that ethylbenzene is rapidly absorbed via this route. Volunteers exposed for 8 hours to ethylbenzene at concentrations of 23–85 ppm were shown to retain 64% of the inspired vapor, with only trace amounts detected in expired air at the end of the exposure period (Bardodej and Bardodejova 1970). Another inhalation study that involved humans exposed to similar levels of ethylbenzene demonstrated mean retention rates of 49% (Gromiec and Piotrowski 1984). The differences may be attributable to human variability in absorption rates although they could also be due to differences in methodology.

An initial concentration of ethylbenzene in blood of 2.6  $\mu\text{g}/\text{mL}$  and a half-life of 27.5 hours were estimated in a 44-year-old man who died after a massive inhalation and dermal exposure of  $\geq 10$  hours to gasoline (Matsumoto et al. 1992). This absorption value may have been slightly overestimated, however, because possible contributions from dermal exposure were not addressed.

In a study conducted in Italy, blood concentrations of ethylbenzene in non-smoking policemen working as traffic wardens showed no significant differences between before and after work shift values or from blood ethylbenzene concentrations in policemen working indoors (Fustinoni et al. 1995). Indoor and

### 3. HEALTH EFFECTS

outdoor mean air concentrations (measured by personal air samplers) were 21 and 37 mg/m<sup>3</sup>, respectively. Before and after shift blood ethylbenzene concentrations were 140 and 163 ng/L in indoor workers, respectively, and were 158 and 184 ng/L in outdoor workers, respectively.

Ethylbenzene concentrations in whole blood collected from workers at the end of their work shifts correlated significantly with the average concentrations of occupational exposure to ethylbenzene (Kawai et al. 1992). The maximum ethylbenzene concentration in air in the workplace was 5 ppm (Kawai et al. 1992).

Inhalation studies in animals exposed to ethylbenzene showed results similar to those found in humans. Harlan-Wistar rats rapidly absorbed radiolabeled ethylbenzene during respiration, with a retention rate of 44% (Chin et al. 1980b). This absorption value may have been slightly overestimated, however, because possible contributions from dermal exposure were not addressed. The concentrations of ethylbenzene in the blood of rats and guinea pigs exposed to ethylbenzene at 550 ppm for 8 hours reached 23 and 3 µg/mL, respectively. Ethylbenzene concentrations in blood after the last of three daily exposures (8 hours each) had diminished to 6 µg/mL in rats and to <2 µg/mL in guinea pigs (Cappaert et al. 2002). These data demonstrate a marked interspecies difference among rats and guinea pigs in the disposition of inhaled ethylbenzene. In mice, steady-state blood ethylbenzene concentrations achieved within 2 hours of initiating inhalation exposures were approximately 0.71 mg/L at 75 ppm, 2.3 mg/L at 200 ppm, and 20 mg/L at 500 ppm (Charest-Tardif et al. 2006). Ethylbenzene concentrations in blood in adult rats and their offspring increased at a rate that was greater than proportional to dose (Faber et al. 2006). Ethylbenzene levels in maternal blood, collected on PND 22, after a 6-hour exposure to 25, 100, or 500 ppm, were 0.11, 0.56, and 11 mg/L, respectively. The mean concentrations in the blood of pups (males/females), culled from the dams sampled above, in the 25-, 100-, and 500-ppm groups were 0.021/0.025, 0.26/0.24, and 11.4/12.7 mg/mL, respectively (Faber et al. 2006).

No studies describing factors specifically affecting absorption of ethylbenzene following inhalation exposure were available.

#### **3.4.1.2 Oral Exposure**

No studies were located regarding the absorption of ethylbenzene in humans following oral exposure. Studies in animals, however, indicate that ethylbenzene is quickly and effectively absorbed by this route.

### 3. HEALTH EFFECTS

Recovery of ethylbenzene metabolites in the urine of rabbits administered a single dose of 593 mg/kg was between 72 and 92% of the administered dose 24 hours following exposure (El Masry et al. 1956). Similarly, 84% of the radioactivity from a single oral dose of 30 mg/kg ethylbenzene administered to female rats was recovered within 48 hours (Climie et al. 1983). Ethylbenzene was detected at 0.49, 3.51, and 18.28 mg/L in maternal blood of rats 1 hour after the last of four daily administrations of 26, 90, or 342 mg/kg/day (distributed over three equal doses), respectively; however, ethylbenzene was not detected (limit of detection: 0.006 mg/L) in blood of weanlings culled from the same dams (Faber et al. 2006). It is unclear if the latter finding is due to low transfer of ethylbenzene to milk or if the 1-hour exposure-to-sampling time-lapse was too long to allow detection of ethylbenzene.

#### 3.4.1.3 Dermal Exposure

Studies in humans dermally exposed to liquid ethylbenzene demonstrate rapid absorption through the skin, but absorption of ethylbenzene vapors through the skin appears to be minimal (Dutkiewicz and Tyras 1967; Gromiec and Piotrowski 1984). Absorption rates of 24–33 mg/cm<sup>2</sup>/hour and 0.11–0.23 mg/cm<sup>2</sup>/hour have been measured for male subjects exposed to liquid ethylbenzene and ethylbenzene from aqueous solutions, respectively (Dutkiewicz and Tyras 1967). The average amounts of ethylbenzene absorbed after volunteers immersed one hand for up to 2 hours in an aqueous solution of 112 or 156 mg/L ethylbenzene were 39.2 and 70.7 mg ethylbenzene, respectively. These results indicate that skin absorption could be a major route of uptake of liquid ethylbenzene or ethylbenzene in water. In contrast, ethylbenzene metabolite levels in urine following dermal exposure to 150–300 ppm (650–1,300 mg/m<sup>3</sup>) ethylbenzene vapors for two hours did not differ from values taken prior to exposure, indicating minimal, if any, dermal absorption of ethylbenzene vapors (Gromiec and Piotrowski 1984).

Susten et al. (1990) conducted *in vivo* percutaneous absorption studies of ethylbenzene in mice. Results showed total absorption (sums of radioactivity found in the excreta, carcass, skin application site, and expired breath) was 3.4% of the nominal dose. The total percentage recovered (includes wipe of skin area, ethylbenzene 0.03%) was 95.2%. The amount of ethylbenzene absorbed at an estimated contact time of 5 minutes was 148.55 µg with an absorption rate of 37 µg/cm<sup>2</sup>/minute.

The volumes of ethylbenzene absorbed in rats treated dermally for 24 hours with aqueous solutions of ethylbenzene (neat [99% pure], saturated, 2/3 or 1/3 saturated), were 0.24, 0.20, 0.18, and 0.17 mL, respectively (Morgan et al. 1991). Peak blood level during exposure to neat ethylbenzene was reported at



### 3. HEALTH EFFECTS

5.6 µg/mL, attained after 1 hour of exposure, which decreased during the remainder of the exposure period. The concentration of ethylbenzene in the blood was highest after exposure to saturated aqueous solutions, followed by the 2/3 and 1/3 saturated solutions.

Results of dermal penetration studies in excised rat skin indicate that the penetration rate of pure ethylbenzene (Tsuruta 1982) is faster than that of ethylbenzene from JP-8 jet fuel (McDougal et al. 2000). The penetration rates of pure liquid ethylbenzene following 3-, 4-, and 5-hour exposure durations in rat skin were approximately 2.38, 3.12, and 3.22 µg/cm<sup>2</sup>/hour (calculated by ATSDR from reported data on exposure area, exposure time, and mass transfer); these rates are substantially lower than the rate of dermal absorption determined for humans (Tsuruta 1982). This might be attributed to differences between *in vitro* and *in vivo* testing and/or differences in rat versus human skin. McDougal et al. (2000) reported an ethylbenzene flux of 0.377 µg/cm<sup>2</sup>/hour (0.0004 mg/cm<sup>2</sup>/hour) for ethylbenzene and a permeability coefficient of 3.1x10<sup>-4</sup> cm/hour during a 4-hour period in excised rat skin which had received 2 mL of JP-8 fuel containing approximately 1,200 µg ethylbenzene/mL fuel (0.15% w/w). It was recognized that the choice of vehicle (JP-8) could affect dermal penetration of ethylbenzene. The steady state flux, permeability, and diffusivity values of ethylbenzene in pig skin treated with JP-8 *ex vivo* were 1.04 µg/cm<sup>2</sup>/hour, 0.06x10<sup>-3</sup> cm/hour, and 715x10<sup>-6</sup> cm<sup>2</sup>/hour (Muhammad et al. 2005).

## 3.4.2 Distribution

### 3.4.2.1 Inhalation Exposure

In humans exposed for 2 hours to a mixture of industrial xylene containing 40.4% ethylbenzene, the estimated solvent retention in adipose tissue was 5% of the total uptake (Engstrom and Bjurstrom 1978). Since there was no indication of differences in turnover rates of chemicals within the mixture, it is likely that the retention of ethylbenzene in adipose tissue was approximately 2% of the total uptake. No studies were located concerning the distribution of ethylbenzene in humans following exposure to ethylbenzene alone. However, studies by Pierce et al. (1996) suggest that *in vitro*, the partitioning of ethylbenzene from air into human adipose tissue is similar to that observed in rats.

In rats, the concentrations of ethylbenzene in perirenal adipose tissue were reported to increase, although not linearly, with increasing concentrations of ethylbenzene (Engstrom et al. 1985) and in a mixture of solvent vapors containing ethylbenzene (Elovaara et al. 1982). The less-than-linear increase of ethylbenzene in adipose tissue with increasing dose was partially attributed to the induction of drug-

### 3. HEALTH EFFECTS

metabolizing enzymes occurring with increasing exposure concentrations, altered blood flow to adipose tissue, changes in lung excretion, and changes in the distribution of ethylbenzene in different tissues. Ethylbenzene was shown to be efficiently distributed throughout the body in rats following inhalation exposure to radiolabeled ethylbenzene (Chin et al. 1980b). The highest amounts of radioactivity in tissues 42 hours after exposure to 230 ppm ethylbenzene for 6 hours were found in the carcass, liver, and gastrointestinal tract, with lower amounts detected in the adipose tissue.

#### 3.4.2.2 Oral Exposure

No studies were located regarding distribution of ethylbenzene in humans or animals following oral exposure.

#### 3.4.2.3 Dermal Exposure


No studies were located regarding distribution in humans following dermal exposure to ethylbenzene.

The percentages of absorbed doses following dermal application of [<sup>14</sup>C]-ethylbenzene in hairless mice were: 15.5%, carcass; 4.5%, application site; 14.3%, expired breath; and 65.5%, excreta (Susten et al. 1990).

#### 3.4.3 Metabolism

The metabolism of ethylbenzene has been studied in humans and other mammalian species. The data demonstrate that ethylbenzene is metabolized mainly through hydroxylation and then through conjugation reactions from which numerous metabolites have been isolated. Figure 3-3 summarizes the proposed metabolic pathway for ethylbenzene in humans (Engstrom et al. 1984). The major urinary metabolites have been identified (Kiese and Lenk 1974; Sullivan et al. 1976). Comparisons of *in vitro* data with data from intact animals indicate that liver microsomal enzymes participate in ethylbenzene hydroxylation (McMahon and Sullivan 1966; McMahon et al. 1969; Sams et al. 2004). In microsomes prepared from human liver, hydroxylation of ethylbenzene to 1-phenylethanol is catalyzed by cytochrome P-450 isoforms CYP2E1 and CYP2B6 (Sams et al. 2004). Adrenal cortex may be a major site of extra-hepatic ethylbenzene metabolism (Greiner et al. 1976). No significant qualitative differences in metabolism

## 3. HEALTH EFFECTS

**Figure 3-3. Metabolic Scheme for Ethylbenzene in Humans**

Source: Engstrom et al. 1984

## 3. HEALTH EFFECTS

between oral and inhalation routes were reported in humans or animals. The metabolism of ethylbenzene has been found to vary with species, sex, and nutritional status. These differences are described below.

In humans exposed via inhalation, the major metabolites of ethylbenzene are mandelic acid (approximately 64–71%) and phenylglyoxylic acid (approximately 19–25%) (Bardodej and Bardodejova 1970; Engstrom et al. 1984). Based on data from human, animal, and *in vitro* studies, the metabolic pathway for ethylbenzene in humans was proposed (Engstrom et al. 1984). This pathway is shown in Figure 3-3. Evidence indicates that the initial step in this metabolic pathway is oxidation (hydroxylation) of the side chain of ethylbenzene to produce 1-phenylethanol. Microsomal preparations from rat liver have shown that the oxidation of ethylbenzene proceeds with the incorporation of atmospheric oxygen, as opposed to oxygen from water molecules (McMahon et al. 1969). Filipovic et al. (1992) have shown that cytochrome P-450<sub>(cam)</sub> from *Pseudomonas putida* provides a useful metabolic model for ethylbenzene hydroxylation, converting ethylbenzene to 1-phenylethanol at 98%. 1-Phenylethanol is conjugated to glucuronide, which then is either excreted or converted to subsequent metabolites. Oxidation of 1-phenylethanol yields acetophenone, which is both excreted in the urine as a minor metabolite and further transformed. Continued oxidation of the side chain leads to the sequential formation of 2-hydroxyacetophenone, 1-phenyl-1,2-ethanediol, mandelic acid, and phenylglyoxylic acid. Minor pathways (e.g., ring hydroxylation) include glucuronide and sulfate conjugation with hydroxylated derivatives to form glucuronides and sulfates that are excreted in the urine. Analysis of urine from humans exposed to ethylbenzene via the inhalation route showed that approximately 70 and 25% of the retained dose of ethylbenzene is excreted as mandelic acid and phenylglyoxylic acid, respectively (Bardodej and Bardodejova 1970; Engstrom et al. 1984). Additional metabolites detected in human urine include 1-phenylethanol (4%), *p*-hydroxyacetophenone (2.6%), *m*-hydroxyacetophenone (1.6%), and trace amounts of 1-phenyl-1,2-ethanediol, acetophenone, 2-hydroxyacetophenone, and 4-ethylphenol. Following dermal exposure of humans, however, excretion of mandelic acid was shown to be only 4.6% of the absorbed dose (Dutkiewicz and Tyras 1967), which may indicate differences in the metabolic fate between inhalation and dermal exposure routes. However, the small percentage of absorbed dose accounted for limits the interpretation. No animal data were located which could confirm these metabolic differences following dermal exposure. Generally, ethylbenzene metabolites and intermediates are thought to be only slightly toxic, since no adverse effects from human experimental exposure have been reported (Bardodej and Bardodejova 1970).

Qualitative and quantitative differences in the biotransformation of ethylbenzene in animals as compared to humans have been reported (Bakke and Scheline 1970; Climie et al. 1983; El Masry et al. 1956;

## 3. HEALTH EFFECTS

Engstrom et al. 1984, 1985; Smith et al. 1954a, 1954b; Sollenberg et al. 1985). The major metabolites of ethylbenzene differ from species to species, and different percentages of the metabolites are seen in different species. The principal metabolic pathway in rats is believed to begin with oxidation (hydroxylation) of the side chain as in humans (Climie et al. 1983; Engstrom et al. 1984, 1985; Smith et al. 1954a). In rats exposed by inhalation or orally to ethylbenzene, the major metabolites were identified as hippuric and benzoic acids (approximately 38%), 1-phenylethanol (approximately 25%), and mandelic acid (approximately 15–23%), with phenylglyoxylic acid making up only 10% of the metabolites (Climie et al. 1983; Engstrom et al. 1984, 1985). The urinary excretion rate of mandelic acid in rats exposed to 250 ppm ethylbenzene, 6 hours/day for 15 days was the same after the first exposure as it was after the last exposure. In contrast, excretion in the 1,000 ppm group was 2–5 times higher after the last exposure than it was after the first exposure (Saillenfait et al. 2006). Both *in vivo* studies using rats and *in vitro* studies using rat liver microsomes showed that 4-ethylphenol was also produced from ethylbenzene, perhaps by rearrangement of corresponding arene oxides (Bakke and Scheline 1970; Kaubisch et al. 1972). Kaubisch et al. (1972) also showed that 2-hydroxyethylbenzene was produced from ethylbenzene *in vitro* in the presence of rat liver microsomes. The level of ethylbenzene exposure was shown to affect the metabolic pattern. This was thought to be due either to selective enzymatic induction in the biotransformation of ethylbenzene or to delayed excretion of certain metabolites with increasing doses.

Acetophenone was detected (quantitative data were not provided) in blood of rats and guinea pigs exposed to ethylbenzene in air at 500 ppm, 8 hours/day for 3 days (Cappaert et al. 2002). Further clarification of ethylbenzene metabolic pathways was provided by Sullivan et al. (1976). Using intraperitoneally dosed rats, the authors demonstrated that the conversion of 1-phenylethanol to mandelic acid initially involves oxidation to acetophenone. Acetophenone was considered to be the precursor of mandelic acid, benzoylformic acid, and benzoic acid. A similar study in which rabbits were intraperitoneally injected with a single dose of 250 mg ethylbenzene/kg body weight was conducted by Kiese and Lenk (1974). This study showed that between 1 and 10% of the dose was excreted as 1-phenylethanol in the urine and <1% was excreted in the urine as 2-hydroxyacetophenone, *p*-hydroxyacetophenone, and *m*-hydroxyacetophenone.

Rabbits given an oral dose of ethylbenzene showed the major metabolic pathway to be hydroxylation of the  $\alpha$ -carbon to 1-phenylethanol, which is oxidized further to a number of intermediates and metabolites (El Masry et al. 1956; Smith et al. 1954a). Many of these intermediates are subsequently conjugated to glucuronides and sulfates and excreted. In rabbits, the most important metabolite is hippuric acid, which is probably formed by oxidative decarboxylation of phenylglyoxylic acid (El Masri et al. 1958).

### 3. HEALTH EFFECTS

Oxidation of the methyl group of ethylbenzene was also shown to occur, as evidenced by the presence of phenaceturic acid in the urine. A slight increase in the excretion of thioether suggests that glutathione conjugation may also play a minor role.

The nutritional status of animals was demonstrated to have a marked effect on ethylbenzene metabolism in rats (Nakajima and Sato 1979). The *in vitro* metabolic activity of liver microsomal enzymes on ethylbenzene was shown to be significantly enhanced in fasted rats despite a marked loss of liver weight. No significant increases in the microsomal protein and cytochrome P-450 contents were detected in fasted rats compared with fed rats. In addition, the metabolic rate in fasted males was significantly higher than in fasted females, but the difference in rates decreased following food deprivation for 3 days. These results suggest possible sex differences in the rate of ethylbenzene metabolism. However, it is not known if such differences exist in the normally fed rats.

Metabolism of ethylbenzene has not been studied in children or immature animals. However, some members of two of the enzyme superfamilies involved in conjugation of phase I ethylbenzene metabolites are known to be developmentally regulated. In humans, UDP glucuronosyltransferase activity does not reach adult levels until about 6–18 months of age, although the development of this activity is isoform specific. Activity of sulfotransferases seems to develop earlier, although again, it is isoform specific. The activity of some sulfotransferase isoforms may even be greater during infancy and early childhood than in adults (Leeder and Kearns 1997).

#### 3.4.4 Elimination and Excretion

##### 3.4.4.1 Inhalation Exposure

Excretion of ethylbenzene has been studied in humans and in a number of animal species. Ethylbenzene has been shown to be rapidly metabolized and then eliminated from the body, primarily as urinary metabolites. The major metabolic products have been previously described in Section 3.4.3.

Elimination of ethylbenzene has been studied in volunteers exposed by inhalation (Bardodej and Bardodejova 1970; Dutkiewicz and Tyras 1967; Engstrom and Bjurstrom 1978; Gromiec and Piotrowski 1984; Yamasaki 1984) and in humans exposed by inhalation in the occupational setting (Holz et al. 1995; Kawai et al. 1991, 1992; Ogata and Taguchi 1988). The elimination of the ethylbenzene metabolite, mandelic acid, was reported to be rapid, with the acid detected in the first urine sample following the

## 3. HEALTH EFFECTS

initiation of an 8-hour inhalation exposure to 0, 4, 8, 18, 35, or 46 ppm ethylbenzene (Gromiec and Piotrowski 1984). Elimination of mandelic acid was reported to be biphasic, with half-lives of 3.1 hours for the rapid phase and 25 hours for the slow phase (Gromiec and Piotrowski 1984). During the 8-hour exposure, 23% of the retained ethylbenzene was eliminated in the urine, and 14 hours following termination of exposure an additional 44% of the retained ethylbenzene was eliminated. The highest excretion rate of urinary metabolites in humans exposed to ethylbenzene by inhalation occurred 6–10 hours after the beginning of exposure (Gromiec and Piotrowski 1984; Yamasaki 1984). The metabolic efficiency was reported to be independent of the exposure dose.

Concentrations of ethylbenzene metabolites in before-shift and after-shift urine were significantly higher in workers exposed to 85 to >921 ppm ethylbenzene in a styrene plant than in control workers exposed to 33.4–66.8 ppm (Holz et al. 1995).

A statistically significant correlation was observed between urinary excretion of mandelic acid and ethylbenzene exposure in workers exposed to mixed solvents (including an ethylbenzene time-weighted average [TWA] of 0.9 ppm) in a metal-coating factory (Kawai et al. 1991). No correlation was observed between ethylbenzene exposure and phenylglyoxylic acid urinary excretion. In a study of chronic-duration exposure at lower levels (2.1 and 2.3 ppm for geometric and arithmetic mean, respectively), no significant correlation was observed between ethylbenzene exposure and urinary excretion of phenylglyoxylic acid and mandelic acid (Kawai et al. 1992).

In animals, elimination of <sup>14</sup>C-ethylbenzene following inhalation exposure is rapid and occurs primarily via urinary excretion (Chin et al. 1980a, 1980b; Engstrom et al. 1984, 1985) and to a much lesser degree via the feces, and expired “gasses” and carbon dioxide (Chin et al. 1980b). Rats exposed to 230 ppm radiolabeled ethylbenzene for 6 hours via inhalation excreted virtually all of the radioactivity within 24 hours after the onset of exposure (Chin et al. 1980a, 1980b). Ninety-one percent of the radioactivity was recovered, primarily in the form of urinary metabolites. In a similar inhalation experiment using rats exposed to 300 or 600 ppm, urinary excretion was reported to be 83 and 59% of the absorbed dose within 48 hours after the onset of exposure, with 13% eliminated during the first 6 hours of exposure (Engstrom et al. 1984).

Quantitative differences between species in the percentages of metabolites excreted in the urine were also reported by Chin et al. (1980a). In this report, urinary metabolites in dogs and rats exposed to ethylbenzene by inhalation were studied. Although similarities in the types of metabolites recovered

### 3. HEALTH EFFECTS

following inhalation exposure were reported, quantitative differences, albeit minor ones, were noted in the ratio of metabolites present in the urine. These results were attributed to differences in metabolism between dogs and rats.

Blood elimination rate constants for ethylbenzene measured at the conclusion of 4-hour exposures to concentrations ranging from 75 to 1,000 ppm were  $0.21 \text{ minute}^{-1}$  ( $t_{1/2}=3.3 \text{ minute}$ ) at 75 ppm and  $0.011 \text{ minute}^{-1}$  ( $t_{1/2}=63 \text{ minutes}$ ) at 1,000 ppm (Charest-Tardif et al. 2006). The concentration dependence on elimination is consistent with a capacity limitation in metabolism of ethylbenzene.

#### 3.4.4.2 Oral Exposure

No studies were located regarding the excretion of ethylbenzene metabolites in humans following oral exposure to ethylbenzene.

Elimination of ethylbenzene and its metabolites in animals after oral exposure has been shown to be similar to that following inhalation exposure. Female rats administered a single oral dose of 30 mg radiolabeled ethylbenzene/kg/body weight showed very rapid elimination, mostly in the urine (Climie et al. 1983). Eighty-two percent of the radioactivity was detected in the urine, while 1.5% was detected in the feces. The major metabolites were mandelic acid (23%) and hippuric acid (34%), with 1-phenylethyl glucuronide detected as a minor metabolite. Relatively minor metabolites (e.g., 4-ethylphenol, 2-phenylethanol, 1-phenylethanol) were shown to be excreted in the urine of male rats exposed to a single oral dose of 100 mg/kg ethylbenzene administered by gavage in oil (Bakke and Scheline 1970). No data on the major metabolites were provided in this study.

In a similar study in which male rats were given single oral doses of 350 mg/kg/body weight ethylbenzene, the excretion of mandelic acid and phenylglyoxylic acid was detected in the first urine sample after exposures. Peak concentration was reached within 17 hours, and ethylbenzene was virtually eliminated 48 hours following the onset of exposure (Sollenberg et al. 1985).

As in inhalation experiments, quantitative and qualitative differences between species were shown to exist in the percentages of metabolites excreted in the urine. Rabbits orally exposed to ethylbenzene excreted large amounts of glucuronide conjugates in the urine (El Masry et al. 1956; Smith et al. 1954a, 1954b) instead of mandelic acid, hippuric acid, and phenylglyoxylic acid, which are the major metabolites in rats



### 3. HEALTH EFFECTS

(see above). Glucuronide conjugates accounted for 32% of the administered dose, with mandelic acid making up only 2% of the administered dose (El Masry et al. 1956). These results were confirmed in a study by Smith et al. (1954a, 1954b), who detected 32% of a single oral dose of ethylbenzene (433 mg/kg) administered to rabbits as glucuronide conjugates excreted in the urine.

#### 3.4.4.3 Dermal Exposure

In humans, the pattern of excretion of ethylbenzene metabolite following dermal exposure has been shown to differ significantly from the pattern in which humans have been exposed by inhalation. Dermal absorption of ethylbenzene in aqueous solutions was estimated as the difference of the ethylbenzene concentrations in solution before and after exposure. The urinary excretion of mandelic acid in humans dermally exposed to ethylbenzene for 2 hours was only 4.6% of the absorbed ethylbenzene (Dutkiewicz and Tyras 1967). Urine was collected periodically during the 2-hour exposure period and a 10-hour follow-up. Interpretation is difficult due to the small percentage of absorbed dose accounted for. No ethylbenzene was reported to be excreted in exhaled air. No further details on the excretion patterns were provided.

Susten et al. (1990) conducted *in vivo* percutaneous absorption studies of ethylbenzene in Hairless mice. Results showed total absorption (sums of radioactivity found in the excreta, carcass, skin application site, and expired breath) was 3.4% of the nominal dose. The absorbed dose collected in expired breath during the first 15 minutes of ethylbenzene application was 9.3%. The percentage of absorbed doses following dermal application of [<sup>14</sup>C]-ethylbenzene are as follows: 15.5% in the carcass; 4.5% at the application site; 14.3% in expired breath; and 65.5% in excreta.

#### 3.4.5 Physiologically Based Pharmacokinetic (PBPK)/Pharmacodynamic (PD) Models

Physiologically based pharmacokinetic (PBPK) models use mathematical descriptions of the uptake and disposition of chemical substances to quantitatively describe the relationships among critical biological processes (Krishnan et al. 1994). PBPK models are also called biologically based tissue dosimetry models. PBPK models are increasingly used in risk assessments, primarily to predict the concentration of potentially toxic moieties of a chemical that will be delivered to any given target tissue following various combinations of route, dose level, and test species (Clewell and Andersen 1985). Physiologically based

## 3. HEALTH EFFECTS

pharmacodynamic (PBPD) models use mathematical descriptions of the dose-response function to quantitatively describe the relationship between target tissue dose and toxic end points.

PBPK/PD models refine our understanding of complex quantitative dose behaviors by helping to delineate and characterize the relationships between: (1) the external/exposure concentration and target tissue dose of the toxic moiety, and (2) the target tissue dose and observed responses (Andersen and Krishnan 1994; Andersen et al. 1987). These models are biologically and mechanistically based and can be used to extrapolate the pharmacokinetic behavior of chemical substances from high to low dose, from route to route, between species, and between subpopulations within a species. The biological basis of PBPK models results in more meaningful extrapolations than those generated with the more conventional use of uncertainty factors.

The PBPK model for a chemical substance is developed in four interconnected steps: (1) model representation, (2) model parameterization, (3) model simulation, and (4) model validation (Krishnan and Andersen 1994). In the early 1990s, validated PBPK models were developed for a number of toxicologically important chemical substances, both volatile and nonvolatile (Krishnan and Andersen 1994; Leung 1993). PBPK models for a particular substance require estimates of the chemical substance-specific physicochemical parameters, and species-specific physiological and biological parameters. The numerical estimates of these model parameters are incorporated within a set of differential and algebraic equations that describe the pharmacokinetic processes. Solving these differential and algebraic equations provides the predictions of tissue dose. Computers then provide process simulations based on these solutions.

The structure and mathematical expressions used in PBPK models significantly simplify the true complexities of biological systems. If the uptake and disposition of the chemical substance(s) are adequately described, however, this simplification is desirable because data are often unavailable for many biological processes. A simplified scheme reduces the magnitude of cumulative uncertainty. The adequacy of the model is, therefore, of great importance, and model validation is essential to the use of PBPK models in risk assessment.

PBPK models improve the pharmacokinetic extrapolations used in risk assessments that identify the maximal (i.e., the safe) levels for human exposure to chemical substances (Andersen and Krishnan 1994). PBPK models provide a scientifically sound means to predict the target tissue dose of chemicals in humans who are exposed to environmental levels (for example, levels that might occur at hazardous waste

### 3. HEALTH EFFECTS

sites) based on the results of studies where doses were higher or were administered in different species. Figure 3-4 shows a conceptualized representation of a PBPK model.

If PBPK models for ethylbenzene exist, the overall results and individual models are discussed in this section in terms of their use in risk assessment, tissue dosimetry, and dose, route, and species extrapolations.

Several models have been developed that simulate the kinetics of inhaled ethylbenzene in animals and humans (Dennison et al. 2003; Tardif et al. 1997). The Dennison et al. (2003) and Tardif et al. (1997) inhalation models have been incorporated into models of gasoline component mixture models (Dennison et al. 2004, 2005; Haddad et al. 2001). A model of dermal absorption ethylbenzene in human has also been reported (Shatkin and Brown 1991). Models that simulate kinetics of ingested ethylbenzene have not been reported.


#### **The Tardif et al. (1997) Model**

**Description of the Model.** Tardif et al. (1997) developed a PBPK model for simulating the kinetics of ethylbenzene, toluene, and xylene in blood following inhalation exposures to the individual chemicals or the ternary mixture (in rats and humans). The structure of the model is essentially identical the generic model depicted in Figure 3-4, with tissue compartments limited to lungs, liver, fat, richly perfused tissues (RPT), and poorly perfused tissues (SPT). All metabolism was attributed to the liver and represented as functions of the concentration of parent compound in liver venous blood, affinity constant ( $K_m$ ), and maximum reaction velocity ( $V_{max}$ ). Transfers of parent compound between blood and tissues were assumed to be flow-limited, with clearance represented by tissue blood flow (L/hour). Parameters for the ethylbenzene model are presented in Table 3-6. Partition coefficients for ethylbenzene were derived from vial equilibrium studies of isolated rat tissues. Metabolism parameter values for ethylbenzene were derived by fitting the model to observations of blood ethylbenzene kinetics measured in rats during and following 4-hour exposures to ethylbenzene in a dynamic exposure chamber (Tardif et al. 1996). Physiological parameters, cardiac output (QC), alveolar ventilation rate (QP), and metabolism  $V_{max}$  were allometrically scaled across species (i.e., rat to human) as a function of body weight (BW, scaling factor= $BW^{0.75}$ )

**Validation of the Model.** Optimization of the metabolism parameters against observed blood kinetics of ethylbenzene in rats exposed for 4 hours to 100 or 200 ppm ethylbenzene achieved predicted

## 3. HEALTH EFFECTS

**Figure 3-4. Conceptual Representation of a Physiologically Based Pharmacokinetic (PBPK) Model for a Hypothetical Chemical Substance**



Note: This is a conceptual representation of a physiologically based pharmacokinetic (PBPK) model for a hypothetical chemical substance. The chemical substance is shown to be absorbed via the skin, by inhalation, or by ingestion, metabolized in the liver, and excreted in the urine or by exhalation.

Source: adapted from Krishnan and Andersen 1994

## 3. HEALTH EFFECTS

**Table 3-6. Parameter Values for Tardif et al. (1997) Ethylbenzene PBPK Models**

Parameter	Definition	Rat model	Human model
Physiological parameters			
VLC	Liver volume (fraction of body)	0.049	0.026
VFC	Fat volume (fraction of body)	0.09	0.19
VSC	Slowly-perfused tissue volume (fraction of body)	0.72	0.62
VRC	Richly-perfused tissue volume (fraction of body)	0.05	0.05
QCC	Cardiac output (L/hour-kg BW)	15 <sup>a</sup>	18 <sup>a</sup>
QPC	Alveolar ventilation rate (L/hour-kg body weight)	15 <sup>a</sup>	18 <sup>a</sup>
QLC	Liver blood flow (fraction of cardiac output)	0.25	0.26
QFC	Fat blood flow (fraction of cardiac output)	0.09	0.05
QSC	Slowly-perfused blood flow (fraction of cardiac output)	0.15	0.25
QRC	Richly-perfused blood flow (fraction of cardiac output)	0.51	0.44
Chemical parameters			
PB	Blood:air partition coefficient	42.7	28.0
PL	Liver:blood partition coefficient	1.96 <sup>b</sup> (83.8)	2.99 <sup>b</sup>
PF	Fat:blood partition coefficient	36.44 <sup>b</sup> (1,556)	55.57 <sup>b</sup>
PS	Slowly-perfused partition coefficient	0.61 <sup>b</sup> (26.0)	0.93 <sup>b</sup>
PR	Readily-perfused partition coefficient	1.41 <sup>b</sup> (60.3)	2.15 <sup>b</sup>
V <sub>max</sub> C	Maximum rate of metabolism (mg/hour-kg body weight)	7.3 <sup>a,c</sup>	7.3 <sup>a,c</sup>
K <sub>m</sub> C	Michaelis-Menten coefficient for metabolism (mg/L)	1.39 <sup>c</sup>	1.39 <sup>c</sup>

<sup>a</sup>Scaled to body weight (BW<sup>0.74</sup>)

<sup>b</sup>Tissue:blood partition coefficients calculated based on reported, experimentally determined (vial equilibrium), tissue:air partition coefficients for rats (values in parentheses) and blood:air coefficient (PB):  
tissue:blood=tissue:air/blood:air.

<sup>c</sup>Values derived by optimization to data on blood ethylbenzene concentrations in rats exposed to ethylbenzene (dynamic chamber).

## 3. HEALTH EFFECTS

blood concentration of ethylbenzene that were within 1–2 standard deviations (SD) of the observations. Most of the validation efforts reported in Tardif et al. (1997) were directed at exploring how well the mixture model predicted observed blood kinetics of ethylbenzene, toluene, or xylene in rats during and following exposures to binary or ternary mixtures of the chemicals. Interactions were simulated as competitive, noncompetitive, or uncompetitive inhibition of metabolism, with the values of the inhibition constants derived by fitting the model to observed blood kinetics during and following exposures to binary mixtures. Although the mixture model achieved predictions similar to observations (i.e., within 1–2 SD of observations), this outcome would have been highly influenced by the parameter values selected for each of the individual chemicals, including fitted interaction constants. A more direct evaluation of the ethylbenzene model was explored by comparing predictions of the human model (allometrically scaled from the rat) to ethylbenzene concentrations observed in human subjects who were exposed to ethylbenzene (33 ppm) for 7 hours/day on 4 different days (Tardif et al. 1991). Predicted blood concentrations of ethylbenzene in subjects exposed to ethylbenzene were within 1–2 SD of observations. The Tardif et al. (1997) model has been incorporated into a mixtures model of JP-8 vapor and its components (Campbell and Fisher 2007). The model included simulations of the kinetics of *m*-xylene and ethylbenzene, with other aromatic components of JP-8 vapor represented as a lumped component. Interactions between *m*-xylene and ethylbenzene were simulated as competitive inhibition of metabolism. The mixtures model predicted kinetics liver concentrations of ethylbenzene in rats during and following 4-hour exposures to JP-8 vapor (380–2,700 mg/m<sup>3</sup>) that were similar to observed kinetics (i.e., predicted liver concentrations were within 1–2 SD of observations).

**Risk Assessment.** The ethylbenzene model predicts blood kinetics of ethylbenzene and kinetics of metabolism of ethylbenzene that occur in association with inhalation exposures. These predictions are potentially useful for predicting inhalation-derived internal doses of ethylbenzene in rats and/or humans (e.g., blood concentrations, liver concentrations of parent compound, or amounts of total metabolites formed in the liver), and for making extrapolations of these internal dose metrics across species. The applicability any of the above dose metrics to risk assessment will depend on the mechanism for the specific toxicity end point being assessed, and contribution of the parent compound and/or metabolism metabolites to toxicity. Current knowledge of the mechanism of toxicity of ethylbenzene does not include an understanding of the relative contributions of parent compound or metabolites as proximate toxic agents in the major end points of ethylbenzene toxicity (i.e., kidney, liver, otic, cancer).

The Tardif et al. (1997) ethylbenzene model has been incorporated into a mixtures model for alkylbenzenes (ethylbenzene, toluene, *m*-xylene), benzene, and dichloromethane (DCM), (Haddad et al.

### 3. HEALTH EFFECTS

2001). This mixture model has been applied to the derivation of interaction coefficients for various endpoints of dichloromethane toxicity (i.e., hypoxia, central nervous system effects, and cancer) based on predictions of corresponding relevant DCM internal dose metrics (i.e., carboxyhemoglobin concentration, area under concentration-time curve for DCM in richly perfused tissues; time-integrated amount of DCM conjugated with GSH). Interactions were simulated as dose addition, with internal dose metrics representing dose and the sole interaction mechanism assumed to be competitive inhibition of cytochrome P-450-mediated metabolism of DCM. The Tardif et al. (1997) model also has been incorporated into a mixtures model of JP-8 vapor and its components (Campbell and Fisher 2007). The model included simulations of the kinetics of *m*-xylene and ethylbenzene, with other aromatic components of JP-8 vapor represented as a lumped component. Interactions between *m*-xylene and ethylbenzene were simulated as competitive inhibition of metabolism. The Tardif et al. (1997) mixtures model was also utilized to evaluate occupational exposure limits for ethylbenzene, toluene, *m*-xylene for hypothetical exposures to ternary mixtures of the chemicals (Dennison et al. 2005). These analyses demonstrate the potential utility of the ethylbenzene model for predicting metabolic interactions with other chemicals that share a common mechanism of metabolic elimination, and the potential impacts of such interactions on risk (e.g., hazard index, cancer risk, occupation exposure limits).

**Target Tissues.** The Tardif et al. (1997) ethylbenzene model was calibrated and evaluated to predict blood kinetics of ethylbenzene that occur in association with inhalation exposures. Essential to this prediction is the accurate prediction of rates of metabolism of ethylbenzene, which, in the model, is attributed solely to the liver. The model has potential utility for predicting, in addition to blood kinetics of ethylbenzene, kinetics of concentrations of ethylbenzene in important toxicity target tissues, including liver and richly perfused tissues (which includes kidney and central nervous system), and rates of metabolism of ethylbenzene and total amount of metabolites formed in liver. The model does not simulate, specifically, the kidney or central nervous system.

**Species Extrapolation.** The Tardif et al. (1997) model was initially developed and calibrated to simulate ethylbenzene kinetics in the rat, and was allometrically scaled to the human. The scaled human model was evaluated for predicting ethylbenzene blood concentrations observed in human subjects who were exposed to ethylbenzene (33 ppm) for 7 hours/day on 4 different days (Tardif et al. 1991). Predicted blood concentrations of ethylbenzene in subjects exposed to ethylbenzene were within 1–2 SD of observations. Studies of the robustness of the model for predicting ethylbenzene kinetics in other species (after allometric scaling to those species) were not located.

## 3. HEALTH EFFECTS

**Interroute Extrapolation.** Studies that evaluated the model for predicting ethylbenzene kinetics following oral or dermal exposure were not located.

**The Dennison et al. (2003, 2004) Model**

**Description of the Model.** Dennison et al. (2003, 2004) developed a PBPK model for simulating the blood and elimination kinetics of components of gasoline, including benzene, ethylbenzene, *n*-hexane, toluene, *o*-xylene, and other volatile components (represented as a single lumped composition) in rats. The structure of the model is essentially identical the generic model depicted in Figure 3-4, with tissue compartments limited to lungs, liver, fat, richly perfused tissues (RPT), and slowly perfused tissues (SPT). All metabolism was attributed to the liver and represented as functions of the concentration of parent compound in liver venous blood, affinity constant ( $K_m$ ), and maximum reaction velocity ( $V_{max}$ ). Transfers of parent compound between blood and tissues were assumed to be flow-limited, with clearance represented by tissue blood flow (L/hour). Parameters for the ethylbenzene portion of the model are presented in Table 3-7. Partition coefficients for ethylbenzene were derived from vial equilibrium studies of isolated rat tissues (Gargas et al. 1989). Metabolism parameter values for ethylbenzene were derived by fitting the model to observations of blood ethylbenzene kinetics measured in rats during closed-chamber exposures to ethylbenzene (Dennison et al. 2003). Physiological parameters, cardiac output (QC), and alveolar ventilation rate (QP), and metabolism  $V_{max}$  were allometrically scaled to body weight (BW, scaling factor= $BW^{0.74}$ )

**Validation of the Model.** Optimization of the metabolism parameters for rats against observed closed chamber air concentration kinetics achieved predicted elimination kinetics of ethylbenzene that were similar to observations (Dennison et al. 2003). Validation efforts reported in Dennison et al. (2004) were directed at exploring how well the mixture model predicted observed closed chamber air kinetics of ethylbenzene, toluene, or xylene during exposures of rats to gasoline (1, 10, 100, 1,000 ppm). Interactions were simulated as competitive inhibition of metabolism, with the values of the inhibition constants derived by fitting to chamber air concentration kinetics during exposures to binary mixtures. Although the mixture model achieved predictions similar to observations, this outcome would have been highly influenced by the parameter values selected for each of the individual chemicals (or lumped chemicals), including fitted interaction constants and, therefore, does not directly address the validity of the ethylbenzene model.



## 3. HEALTH EFFECTS

**Table 3-7. Parameter Values for Dennison et al. (2003) Ethylbenzene PBPK Model**

Parameter	Definition	Rat model
Physiological parameters		
VLC	Liver volume (fraction of body)	0.037
VFC	Fat volume (fraction of body, scaled to body weight)	0.036(body weight)+0.205
VSC	Slowly-perfused tissue volume (fraction of body)	0.91-remaining <sup>a</sup>
VRC	Richly-perfused tissue volume (fraction of body)	0.054
VLBV	Lung blood volume (fraction of body)	0.002
QCC	Cardiac output (L/hour-kg body weight)	15 <sup>b</sup>
QPC	Alveolar ventilation rate (L/hour-kg body weight)	15 <sup>b,c</sup>
QLC	Liver blood flow (fraction of cardiac output)	0.183
QSC	Fat blood flow (fraction of cardiac output)	0.07
QFC	Slowly-perfused blood flow (fraction of cardiac output)	0.237 <sup>d</sup>
QRC	Richly-perfused blood flow (fraction of cardiac output)	0.51
Chemical parameters		
PB	Blood:air partition coefficient	42.7 <sup>e</sup>
PL	Liver:blood partition coefficient	1.96 <sup>e</sup>
PF	Fat:blood partition coefficient	36.4 <sup>e</sup>
PS	Slowly-perfused partition coefficient	0.609 <sup>e</sup>
PR	Readily-perfused partition coefficient	1.96
V <sub>max</sub> C	Maximum rate of metabolism (mg/hour-kg body weight)	7.6 <sup>b,f</sup>
K <sub>m</sub> C	Michaelis-Menten coefficient for metabolism (mg/L)	0.10 <sup>f</sup>

<sup>a</sup>VSC=0.91-(VLC+VFC+VRC+VLB)

<sup>b</sup>Scaled to body weight (BW<sup>0.74</sup>)

<sup>c</sup>QPC varied with exposure: 14.9 at 500 ppm, 13.1 at 1,000 ppm, and 12.5 at 1,500 ppm.

<sup>d</sup>QSC=1-(QLC+QFC+QRC)

<sup>e</sup>Tissue:blood partition coefficients calculated based on reported, experimentally determined (vial equilibrium) tissue:air partition coefficients for rats (Tardif et al. 1997).

<sup>f</sup>Values derived by optimization to data on blood ethylbenzene concentrations in rats exposed to ethylbenzene (closed chamber).

## 3. HEALTH EFFECTS

**Risk Assessment.** The Dennison et al. (2003) ethylbenzene model predicts blood kinetics of ethylbenzene and kinetics of metabolism of inhaled ethylbenzene. These predictions are potentially useful for predicting internal doses of inhaled ethylbenzene in rats (e.g., blood concentrations, liver concentrations of parent compound, or amounts of total metabolites formed in the liver). The applicability any of the above dose metrics to risk assessment will depend on the mechanism for the specific toxicity endpoint being assessed, and contribution of the parent compound and/or metabolism to toxicity. Current knowledge of the mechanism of toxicity of ethylbenzene does not include an understanding of the relative contributions of parent compound or metabolites as proximate toxic agents in the major end points of ethylbenzene toxicity (i.e., kidney, liver, otic, cancer).

The Dennison et al. (2003) ethylbenzene model has been incorporated into a mixtures model for gasoline (benzene, ethylbenzene, *n*-hexane, toluene, *o*-xylene, and other volatile components). In the mixtures model, chemical interactions were attributed to competitive inhibition of metabolism and inhibition constants were derived by fitting model predictions of closed chamber air concentration kinetics during exposures to binary mixtures. The model was used to predict the effect of increasing exposure concentration to gasoline on blood concentrations and amounts of individual mixture components metabolized (Dennison et al. 2004).

**Target Tissues.** The Dennison et al. (2003) ethylbenzene model was calibrated and evaluated to predict elimination (i.e., metabolism) kinetics of ethylbenzene that occur in association with inhalation exposures. Essential to this prediction is the accurate prediction of rates of metabolism of ethylbenzene, which, in the model, is attributed solely to the liver. The model has potential utility for predicting, in addition to elimination kinetics of ethylbenzene, kinetics of concentrations of ethylbenzene in important toxicity target tissues, including liver, richly perfused tissues (which includes kidney and central nervous system), and rates of metabolism of ethylbenzene and total amount of metabolites formed in liver. The model does not simulate, specifically, the kidney or central nervous system.

**Species Extrapolation.** The Dennison et al. (2003) ethylbenzene model was developed and calibrated to simulate ethylbenzene kinetics in the rat; however, it could be allometrically scaled to the human. Studies of the robustness of the model for predicting ethylbenzene kinetics in species other than the rat (after allometric scaling to those species) were not located.

## 3. HEALTH EFFECTS

**Interroute Extrapolation.** Studies that evaluated the model for predicting ethylbenzene kinetics following oral or dermal exposure were not located.


**The Shatkin and Brown (1991) Model**

**Description of the Model.** Shatkin and Brown (1991) described a model of dermal absorption of several nonpolar organic nonelectrolytes in dilute aqueous solution, one of which was ethylbenzene. The structure of the model is depicted in Figure 3-5; model parameters are presented in Table 3-8. The model includes three compartments: stratum corneum, viable epidermis, and blood. Transfers of ethylbenzene in solution through the fully hydrated stratum corneum and viable epidermis are assumed to be diffusive, with passage through the stratum corneum being the rate-limiting step. A uniform thickness of 40  $\mu\text{m}$  was assumed for the stratum corneum, with adjustments for different body parts. Immersion of the hand or of the full body was assumed for the predicted models. The viable epidermis was assumed to be 200  $\mu\text{m}$ , although the thickness was varied to test the outcome of the model. Transfer from the viable epidermis to blood was assumed to be flow-limited. Elimination from blood (i.e., distribution to tissues, excretion to urine and air, and metabolism) was represented with a single first-order rate constant. A sensitivity analysis revealed a relatively high influence of epidermal blood flow (as expected for flow-limited transfer to blood), epidermal thickness (increasing thickness decreased absorption), and stratum corneum fat (increasing fat content decreased absorption).

**Validation of the Model.** Model predictions were compared to the estimates of dermal absorption of ethylbenzene in humans (Dutkiewicz and Tyras 1967, 1968). In this study, adult males ( $n=7$ ) immersed their hands into a bath solution of 151 mg/L ethylbenzene for 1 hour and the absorbed dose was estimated from the change in concentration of the exposure bath. The model predicted absorption of 34–37% of the bath ethylbenzene in 1 hour, compared to the observed mean absorption of 39% (range, 0.33–0.54). The simulated kinetics of absorption were not reported or compared to observations.

**Risk Assessment.** The Shatkin and Brown (1991) model is potentially useful for predicting dermal absorption of ethylbenzene in risk assessment applications. An example of one application is prediction of the dermal-absorbed dose of ethylbenzene for a bathing scenario (20-minute immersion in 0.1 mg ethylbenzene/L); the predicted absorbed dose, 0.47–0.50 mg, was higher than the absorbed dose predicted for ingestion of 2 L of water at the same concentration, or from inhalation during a 20-minute shower (Shatkin and Brown 1991). The model may be useful in predicting absorbed doses of ethylbenzene resulting from bathing, swimming, and other activities (Shatkin and Brown 1991).

## 3. HEALTH EFFECTS

**Figure 3-5. Schematic Representation of the Model of Dermal Absorption**

Source: Shatkin and Brown 1991

## 3. HEALTH EFFECTS

**Table 3-8. Parameters Used in the Shatkin and Brown PBPK Model of Dermal Absorption of Ethylbenzene**

Parameter <sup>a</sup>	Value	Reference
Stratum corneum/water partition coefficient ( $K_m$ )	NG	Calculated from Roberts et al. 1975
Stratum corneum diffusion coefficient ( $D_{sc}$ )	NG	Calculated from Guy and Maibach 1984
Skin surface	320 cm <sup>2</sup> (adult, hands and forearms) NG (adult, body)	Dutkiewicz and Tyras 1967, 1968 Guy and Maibach 1984
Skin surface (infant)	1,900 cm <sup>2</sup>	Guy and Maibach 1984
Epidermis diffusion coefficient ( $D_e$ )	$3.6 \times 10^{-4}$ cm <sup>2</sup> /minute	Scheuplein 1976; Scheuplein et al. 1969
Stratum corneum thickness ( $H_{sc}$ )	0.004 cm	Blank and Scheuplein 1969
Epidermis thickness ( $H_e$ )	0.02–0.1 cm	Blank and McAuliffe 1985; Blank and Scheuplein 1969; Guy et al. 1982
Epidermal blood flow ( $F_{eb}$ ) (adult, at rest)	280 mL/minute–m <sup>2</sup>	Wade et al. 1962
Epidermal blood flow ( $F_{eb}$ ) (adult, heavy exercise)	4,000 mL/minute–m <sup>2</sup>	Rowell 1986
Epidermis/blood partition coefficient ( $K_{eb}$ )	2.75	Shatkin and Brown 1991
Stratum corneum/epidermis partition coefficient ( $K_{sc/e}$ )	NG	Shatkin and Brown 1991
Blood volume ( $V_b$ ) (adults)	5,000 mL	Shatkin and Brown 1991
Blood volume ( $V_b$ ) (infants)	693 mL	Shatkin and Brown 1991
Fat in blood	0.7–0.9%	Brown and Hattis 1989
Fat in stratum corneum	3–6%	Raykar et al. 1988
Fat in epidermis	2–2.5%	Scheuplein 1976
Elimination rate constant ( $K_e$ )	0.1 minute <sup>-1</sup>	Hagemann 1979
Octanol/water partition coefficient ( $K_{ow}$ )	2,230	Shatkin and Brown 1991

<sup>a</sup>Taken from Shatkin and Brown 1991. All parameters used were either taken from published experimental work of others or calculated from previously reported mathematical relationships.

NG = value not given

### 3. HEALTH EFFECTS

**Target Tissues.** The Shatkin and Brown (1991) model was developed to simulate dermal absorption of ethylbenzene (and other volatile organics); it does not predict concentrations of ethylbenzene in specific tissues, other than skin. However, if the model were integrated into PBPK models of the distribution and elimination of absorbed ethylbenzene (e.g., Dennison et al. 2003; Tardif et al. 1997), the combined models might be useful for predicting internal doses of ethylbenzene associated with dermal exposures.

**Species Extrapolation.** The Shatkin and Brown (1991) model was developed to simulate dermal absorption of ethylbenzene in humans and has been evaluated with observations in humans. The major physiological parameters in the model are scalable or could be determined in different species (e.g., dermal thickness, dermal fat content, dermal blood flow), and the chemical parameters could be evaluated in other species (e.g., partition coefficients) or predicted from physical-chemical properties (e.g., diffusion coefficients). These features improve the feasibility of scaling the model to other species.

**Interroute Extrapolation.** The Shatkin and Brown (1991) model, in combination with existing PBPK ethylbenzene inhalation models (e.g., Dennison et al. 2003; Tardif et al. 1997), may have utility for estimating dermal exposures (i.e., concentration, time) that would be expected to yield equivalent absorbed doses from inhalation exposures.

## 3.5 MECHANISMS OF ACTION

### 3.5.1 Pharmacokinetic Mechanisms

Studies of the *in vitro* metabolism of ethylbenzene in microsomes prepared from human liver have identified high and low affinity catalytic pathways for the initial hydroxylation to 1-phenylethanol (Sams et al. 2004). In human liver microsomes, the high affinity pathway exhibited a lower  $K_m$  and lower  $V_{max}$  ( $K_m=8 \mu M$ ,  $V_{max}=689 \text{ pmol/minute/mg protein}$ ) than the low affinity pathway ( $K_m=391 \mu M$ ,  $V_{max}=3,039 \text{ pmol/min/mg protein}$ ) and was inhibited by diethyldithiocarbamate. Studies conducted in microsomes prepared from insect cells expressing recombinant human isoforms of cytochrome P-450 also revealed a relatively high affinity, low  $V_{max}$  catalysis by CYP2E1 and lower affinity, higher  $V_{max}$  catalysis by CYP1A2 and CYP2B6, suggesting that the latter two isoforms may contribute to the low affinity pathway observed in human liver microsome (Sams et al. 2004).

### 3. HEALTH EFFECTS

Blood kinetics of inhaled ethylbenzene have been successfully modeled with assumptions of flow-limited transfer of ethylbenzene to tissues and capacity-limited elimination by metabolism (Dennison et al. 2003, 2004; Tardif et al. 1997, see Section 3.4.5). These models have been successfully scaled from the rat to humans by applying species physiological parameter values (e.g., tissue volumes) and partition coefficients (i.e., blood:air partition coefficient) and allometrically scaling flows (i.e., cardiac output, alveolar ventilation rate) and metabolism parameters (i.e.,  $K_m$ ,  $V_{max}$ ) to body weight (Tardif et al. 1997). These studies suggest a general similarity of the distribution and elimination kinetics in rats and humans. The robustness of these models for predicting ethylbenzene kinetics in other species has not been reported; however, the blood elimination kinetics of inhaled ethylbenzene in the mouse show similarities to that in the rat (e.g., nonlinearity of clearance with exposure concentration, similar elimination half-times (Charest-Tardif et al. 2006; Tardif et al. 1997).

#### 3.5.2 Mechanisms of Toxicity

Mechanisms of ototoxicity, toxicity to the liver and kidney, and carcinogenicity have not been identified. Since metabolites of ethylbenzene have been shown to produce oxidative damage to DNA (Midorikawa et al. 2004), it is possible that ethylbenzene metabolites contribute to the toxicity observed following ethylbenzene exposure. Likewise, a genotoxic mechanism of carcinogenicity is plausible.

Ethylbenzene has been shown to exert adverse central nervous system effects on both humans (Yant et al. 1930) and animals (Cragg et al. 1989; Ethylbenzene Producers Association 1986a; Molnar et al. 1986; Tegeris and Balster 1994; Yant et al. 1930). *In vivo* animal studies of ethylbenzene toxicity at the cellular level indicate that changes in brain levels of dopamine and other biochemical alterations, and in evoked electrical activity in the brain may be involved in ethylbenzene central nervous system toxicity (Andersson et al. 1981; Frantik et al. 1994; Mutti et al. 1988; Romanelli et al. 1986).

Based on *in vitro* studies conducted with toluene, Cappaert et al. (2001) briefly speculated that increased intracellular calcium levels might be responsible for the obliteration of outer hair cells exposed to solvents such as ethylbenzene.

*In vitro* studies of the mechanism of toxicity have focused on the effect of ethylbenzene on cell membranes, particularly that of the astrocyte (Engelke et al. 1993; Naskali et al. 1993, 1994; Sikkema et al. 1995; Vaalavirta and Tähti 1995a, 1995b). In a review by Sikkema et al. (1995), changes in the

### 3. HEALTH EFFECTS

structure and integrity of the cell membrane after partitioning of ethylbenzene into the lipid bilayer may be a mechanism of toxicity. Changes in the integrity of the cell membrane may subsequently affect the function of membrane, particularly as a barrier and in energy transduction, and in the formation of a matrix for proteins and enzymes.

The work of Vaalavirta and Tähti (1995a, 1995b) and Naskali et al. (1993, 1994) has investigated the effect of ethylbenzene on the membrane of the rat astrocyte, as an *in vitro* model for the membrane-mediated effects of solvents on the central nervous system. Cultured astrocytes from the cerebella of neonatal Sprague-Dawley rats were sensitive to the effects of ethylbenzene, as measured by the inhibition of activity of Na<sup>+</sup>, K<sup>+</sup>-ATPase, and Mg<sup>++</sup>-ATPase (Vaalavirta and Tähti 1995a, 1995b). This effect was found to be dose-dependent (Naskali et al. 1994). Inhibition of these membrane-bound enzymes that regulate the ion channels of the membrane may disturb the ability of the cells to maintain homeostasis. Experiments with rat synaptosome preparations, similar to those using microsomal preparations by Engelke et al. (1993), showed that membrane fluidity was increased after exposure to ethylbenzene. ATPase and acetylcholinesterase activity were also decreased, as seen in the astrocyte preparations.

#### 3.5.3 Animal-to-Human Extrapolations

Species differences have been shown for ethylbenzene metabolism. In humans exposed via inhalation, the major metabolites of ethylbenzene are mandelic acid (approximately 70% of the absorbed dose) and phenylglyoxylic acid (approximately 25% of the absorbed dose), which are excreted in the urine (Bardodej and Bardodejova 1970; Engstrom et al. 1984). Evidence indicates that the initial step in this metabolic pathway is oxidation of the side chain of ethylbenzene to produce 1-phenylethanol. In rats exposed by inhalation or orally to ethylbenzene, the major metabolites were identified as hippuric and benzoic acids (approximately 38%), 1-phenylethanol (approximately 25%), and mandelic acid (approximately 15–23%), with phenylglyoxylic acid making up only 10% of the metabolites (Climie et al. 1983; Engstrom et al. 1984, 1985). In rabbits, the most important metabolite is hippuric acid, which is probably formed by oxidative decarboxylation of phenylglyoxylic acid (El Masri et al. 1958). Rabbits have been shown to excrete higher levels of glucuronidated metabolites than do humans or rats (El Masry et al. 1956; Smith et al. 1954a, 1954b). Thus, there are no animal models of ethylbenzene metabolism that are completely consistent with human metabolism. However, of the experimental models investigated, rats appear to be a more appropriate model than rabbits.



### 3. HEALTH EFFECTS

Models of the pharmacokinetic mechanisms and mechanisms of toxicity of ethylbenzene have focused on cellular processes (see Sections 3.5.1 and 3.5.2, above). In these, humans and animals appear to be similar. Although some species differences exist with respect to toxicity, adverse effects observed after ethylbenzene exposure in both humans and animals seem to be similar in scope (i.e., respiratory, hepatic, renal, and neurological). Rats may be more sensitive than mice or rabbits (Cragg et al. 1989; NTP 1992). Thus, the rat may be the most appropriate animal model for studying the mechanism of toxicity of ethylbenzene as it relates to human health effects assessment.

#### 3.6 TOXICITIES MEDIATED THROUGH THE NEUROENDOCRINE AXIS

Recently, attention has focused on the potential hazardous effects of certain chemicals on the endocrine system because of the ability of these chemicals to mimic or block endogenous hormones. Chemicals with this type of activity are most commonly referred to as *endocrine disruptors*. However, appropriate terminology to describe such effects remains controversial. The terminology *endocrine disruptors*, initially used by Thomas and Colborn (1992), was also used in 1996 when Congress mandated the EPA to develop a screening program for "...certain substances [which] may have an effect produced by a naturally occurring estrogen, or other such endocrine effect[s]...". To meet this mandate, EPA convened a panel called the Endocrine Disruptors Screening and Testing Advisory Committee (EDSTAC), and in 1998, the EDSTAC completed its deliberations and made recommendations to EPA concerning *endocrine disruptors*. In 1999, the National Academy of Sciences released a report that referred to these same types of chemicals as *hormonally active agents*. The terminology *endocrine modulators* has also been used to convey the fact that effects caused by such chemicals may not necessarily be adverse. Many scientists agree that chemicals with the ability to disrupt or modulate the endocrine system are a potential threat to the health of humans, aquatic animals, and wildlife. However, others think that endocrine-active chemicals do not pose a significant health risk, particularly in view of the fact that hormone mimics exist in the natural environment. Examples of natural hormone mimics are the isoflavonoid phytoestrogens (Adlercreutz 1995; Livingston 1978; Mayr et al. 1992). These chemicals are derived from plants and are similar in structure and action to endogenous estrogen. Although the public health significance and descriptive terminology of substances capable of affecting the endocrine system remains controversial, scientists agree that these chemicals may affect the synthesis, secretion, transport, binding, action, or elimination of natural hormones in the body responsible for maintaining homeostasis, reproduction, development, and/or behavior (EPA 1997b). Stated differently, such compounds may cause toxicities that are mediated through the neuroendocrine axis. As a result, these chemicals may play a role in altering,

### 3. HEALTH EFFECTS

for example, metabolic, sexual, immune, and neurobehavioral function. Such chemicals are also thought to be involved in inducing breast, testicular, and prostate cancers, as well as endometriosis (Berger 1994; Giwercman et al. 1993; Hoel et al. 1992).

No studies were located regarding endocrine disruption in humans or animals after exposure to ethylbenzene. Nishihara et al. (2000) concluded that ethylbenzene was not estrogenic as established in an *in vitro* yeast two-hybrid assay. No additional *in vitro* studies were located regarding endocrine disruption of ethylbenzene.

#### 3.7 CHILDREN'S SUSCEPTIBILITY

This section discusses potential health effects from exposures during the period from conception to maturity (most development is complete by early in the third decade) in humans (that most development is complete by the early 20's), when all biological systems will have fully developed. Potential effects on offspring resulting from exposures of parental germ cells are considered, as well as any indirect effects on the fetus and neonate resulting from maternal exposure during gestation and lactation. Relevant animal and *in vitro* models are also discussed.

Children are not small adults. They differ from adults in their exposures and may differ in their susceptibility to hazardous chemicals. Children's unique physiology and behavior can influence the extent of their exposure. Exposures of children are discussed in Section 6.6, Exposures of Children.

Children sometimes differ from adults in their susceptibility to hazardous chemicals, but whether there is a difference depends on the chemical (Guzelian et al. 1992; NRC 1993). Children may be more or less susceptible than adults to health effects, and the relationship may change with developmental age (Guzelian et al. 1992; NRC 1993). Vulnerability often depends on developmental stage. There are critical periods of structural and functional development during both prenatal and postnatal life, and a particular structure or function will be most sensitive to disruption during its critical period(s). Damage may not be evident until a later stage of development. There are often differences in pharmacokinetics and metabolism between children and adults. For example, absorption may be different in neonates because of the immaturity of their gastrointestinal tract and their larger skin surface area in proportion to body weight (Morselli et al. 1980; NRC 1993); the gastrointestinal absorption of lead is greatest in infants and young children (Ziegler et al. 1978). Distribution of xenobiotics may be different; for example,

## 3. HEALTH EFFECTS

infants have a larger proportion of their bodies as extracellular water, and their brains and livers are proportionately larger (Altman and Dittmer 1974; Fomon 1966; Fomon et al. 1982; Owen and Brozek 1966; Widdowson and Dickerson 1964). The infant also has an immature blood-brain barrier (Adinolfi 1985; Johanson 1980) and probably an immature blood-testis barrier (Setchell and Waites 1975). Many xenobiotic metabolizing enzymes have distinctive developmental patterns. At various stages of growth and development, levels of particular enzymes may be higher or lower than those of adults, and sometimes unique enzymes may exist at particular developmental stages (Komori et al. 1990; Leeder and Kearns 1997; NRC 1993; Vieira et al. 1996). Whether differences in xenobiotic metabolism make the child more or less susceptible also depends on whether the relevant enzymes are involved in activation of the parent compound to its toxic form or in detoxification. There may also be differences in excretion, particularly in newborns who have a low glomerular filtration rate and have not developed efficient tubular secretion and resorption capacities (Altman and Dittmer 1974; NRC 1993; West et al. 1948). Children and adults may differ in their capacity to repair damage from chemical insults. Children also have a longer remaining lifetime in which to express damage from chemicals; this potential is particularly relevant to cancer.

Certain characteristics of the developing human may increase exposure or susceptibility, whereas others may decrease susceptibility to the same chemical. For example, although infants breathe more air per kilogram of body weight than adults breathe, this difference might be somewhat counterbalanced by their alveoli being less developed, which results in a disproportionately smaller surface area for alveolar absorption (NRC 1993).

There are no data describing the effect of exposure to ethylbenzene in children. Respiratory and eye irritation, and dizziness are the most prevalent signs of exposure to high levels of ethylbenzene (Yant et al. 1930), and it is expected that children would also exhibit these effects, as well as other effects observed in adults. Minor birth defects have occurred in newborn rats, but not rabbits, whose mothers were exposed by breathing air contaminated with ethylbenzene (NIOSH 1981; Ungváry and Tátrai 1985). These defects consisted of urinary tract anomalies (not specified) and supernumerary ribs. Supernumerary ribs were observed in the presence of minimal maternal changes. Although developmental effects were reported in the offspring of animals exposed to <500 ppm ethylbenzene (Ungváry and Tátrai 1985) several longer duration studies have shown developmental effects at biologically or statistically significant levels only in the offspring of rats exposed to >500 ppm ethylbenzene (Faber et al. 2006, 2007; Saillenfait et al. 2003, 2006, 2007). Furthermore, the report by Ungváry and Tátrai (1985) lacks pertinent experimental details, including specific data on the urinary

### 3. HEALTH EFFECTS

tract anomalies, dictating caution in the interpretation of study findings. Section 3.2.1.6, Developmental Effects, contains a more detailed discussion of these results. It is not known whether these developmental effects observed in animals would be observed in people. Ethylbenzene has been detected in human breast milk at unspecified concentrations (Pellizzari et al. 1982), but no pharmacokinetic experiments have been done to confirm that it is actually transferred to breast milk in mammals. No specific information was found concerning ethylbenzene concentrations in placenta, cord blood, or amniotic fluid. Since there is no information about health effects in children, it is unknown whether they differ from adults in their susceptibility to health effects from ethylbenzene. However, in general, the principle that early-in-life exposures may increase susceptibility to carcinogens may apply to ethylbenzene (EPA 2005).

There is no specific information about the metabolism of ethylbenzene in children or immature adults. However, since two of the enzyme families responsible for the conjugation and elimination of ethylbenzene are developmentally regulated, it is possible that the activity of these enzymes would differ in children or immature animals compared to adults. In humans, UDP glucuronosyltransferase activity does not reach adult levels until about 6–18 months of age, although the development of this activity is isoform specific. Activity of sulfotransferases (which is also isoform specific) seems to develop earlier. The activity of some sulfotransferase isoforms may even be greater during infancy and early childhood than in adulthood (Leeder and Kearns 1997). In addition, age-dependence of elimination kinetics (e.g., glomerular filtration and tubular secretion of organic anion metabolites of ethylbenzene), potentially, could contribute to age-related differences in sensitivity to ethylbenzene.

### 3.8 BIOMARKERS OF EXPOSURE AND EFFECT

Biomarkers are broadly defined as indicators signaling events in biologic systems or samples. They have been classified as markers of exposure, markers of effect, and markers of susceptibility (NAS/NRC 1989).

Due to a nascent understanding of the use and interpretation of biomarkers, implementation of biomarkers as tools of exposure in the general population is very limited. A biomarker of exposure is a xenobiotic substance or its metabolite(s) or the product of an interaction between a xenobiotic agent and some target molecule(s) or cell(s) that is measured within a compartment of an organism (NAS/NRC 1989). The preferred biomarkers of exposure are generally the substance itself, substance-specific metabolites in

### 3. HEALTH EFFECTS

readily obtainable body fluid(s), or excreta. However, several factors can confound the use and interpretation of biomarkers of exposure. The body burden of a substance may be the result of exposures from more than one source. The substance being measured may be a metabolite of another xenobiotic substance (e.g., high urinary levels of phenol can result from exposure to several different aromatic compounds). Depending on the properties of the substance (e.g., biologic half-life) and environmental conditions (e.g., duration and route of exposure), the substance and all of its metabolites may have left the body by the time samples can be taken. It may be difficult to identify individuals exposed to hazardous substances that are commonly found in body tissues and fluids (e.g., essential mineral nutrients such as copper, zinc, and selenium). Biomarkers of exposure to ethylbenzene are discussed in Section 3.8.1.

Biomarkers of effect are defined as any measurable biochemical, physiologic, or other alteration within an organism that, depending on magnitude, can be recognized as an established or potential health impairment or disease (NAS/NRC 1989). This definition encompasses biochemical or cellular signals of tissue dysfunction (e.g., increased liver enzyme activity or pathologic changes in female genital epithelial cells), as well as physiologic signs of dysfunction such as increased blood pressure or decreased lung capacity. Note that these markers are not often substance specific. They also may not be directly adverse, but can indicate potential health impairment (e.g., DNA adducts). Biomarkers of effects caused by ethylbenzene are discussed in Section 3.8.2.

A biomarker of susceptibility is an indicator of an inherent or acquired limitation of an organism's ability to respond to the challenge of exposure to a specific xenobiotic substance. It can be an intrinsic genetic or other characteristic or a preexisting disease that results in an increase in absorbed dose, a decrease in the biologically effective dose, or a target tissue response. If biomarkers of susceptibility exist, they are discussed in Section 3.10, Populations That Are Unusually Susceptible.

#### **3.8.1 Biomarkers Used to Identify or Quantify Exposure to Ethylbenzene**

Information on ethylbenzene concentrations in human tissue or fluids is available. Exposure to ethylbenzene may be determined by the detection of mandelic acid and phenylglyoxylic acid in urine (Bardodej and Bardodejova 1970) or by direct detection of ethylbenzene in whole human blood (Antoine et al. 1986; Ashley et al. 1992; Cramer et al. 1988). However, mandelic acid and phenylglyoxylic acid are also metabolites of styrene (Agency for Toxic Substances and Disease Registry 1992).

### 3. HEALTH EFFECTS

The 1982 National Human Adipose Tissue Survey conducted by EPA measured ethylbenzene in 96% of the 46 composite samples analyzed for volatile organic compounds (EPA 1986a). A wet tissue concentration range of not detected (detection limit=2 ng/g) to 280 ng/g was reported, but an average concentration was not provided.

Numerous studies indicate that environmental exposures to ethylbenzene can result in detectable levels in human tissues (Antoine et al. 1986; Cramer et al. 1988; Pellizzari et al. 1982; Wolff 1976; Wolff et al. 1977) and in expired air (Conkle et al. 1975; Engstrom and Bjurstrom 1978; EPA 1984e). Analysis of blood specimens from a test population of 250 patients (Antoine et al. 1986) and composite samples obtained from blood donations of laboratory personnel with potentially low-level exposure (Cramer et al. 1988) indicated ethylbenzene concentrations in the blood to range from below detection limits to 59 ppb. Similarly, ethylbenzene was detected in 8 of 12 milk samples from lactating women living in various urban areas of the United States with high probability of emissions of pollutants (Pellizzari et al. 1982). Subcutaneous fat samples taken from individuals exposed to an average of 1–3 ppm ethylbenzene in the workplace contained ethylbenzene levels as high as 0.7 ppm (Wolff 1976; Wolff et al. 1977).

Studies examining the correlation of ethylbenzene concentrations in ambient air with concentrations measured in expired or alveolar air have also been conducted (Conkle et al. 1975; Engstrom and Bjurstrom 1978; EPA 1984e). Ethylbenzene concentrations in breath samples were reported to correlate well with ethylbenzene concentrations in indoor samples taken with personal air monitors (EPA 1984e). A correlation was also found between ethylbenzene uptake and ethylbenzene concentrations in alveolar air during, but not after, inhalation exposure in volunteers (Engstrom and Bjurstrom 1978). Rates of ethylbenzene expiration measured in volunteers with no known previous exposure to ethylbenzene ranged from 0.78 to 14 µg/hour, with higher rates detected in smokers than in nonsmokers (Conkle et al. 1975).

#### **3.8.2 Biomarkers Used to Characterize Effects Caused by Ethylbenzene**

For more information on biomarkers for renal and hepatic effects of chemicals see ATSDR/CDC Subcommittee Report on Biological Indicators of Organ Damage (Agency for Toxic Substances and Disease Registry 1990) and for information on biomarkers for neurological effects see OTA (1990).

### 3. HEALTH EFFECTS

No specific biomarkers of effect for ethylbenzene were identified. Most of the information on humans is from case reports in which the effects are general and non-specific, such as eye and throat irritation and chest constriction (Yant et al. 1930).

#### 3.9 INTERACTIONS WITH OTHER CHEMICALS

The metabolism of ethylbenzene includes pathways involving mono-oxygenases (e.g., cytochrome P-450) and formation of glucuronide and sulfate conjugates. Therefore, the metabolism of ethylbenzene could be markedly altered by inhibitors (e.g., carbon monoxide, SKF 525A) and inducers (e.g., phenobarbital, described above) of drug-metabolizing enzymes (Gillette et al. 1974) and by the availability of conjugation reactants (e.g., glucuronic acid, sulfate) that facilitate the excretion of ethylbenzene metabolites. Mono-oxygenases (MOs) are a class of enzymes involved in the detoxication of xenobiotics, including ethylbenzene. Substances that induce MO enzymes may decrease the toxicity of ethylbenzene by increasing the rate of production of its less toxic metabolites. Conversely, MO enzyme inhibitors would be expected to have the opposite effect. Compounds that affect glucuronic acid availability could also affect the excretion rate of ethylbenzene metabolites.

Numerous studies have demonstrated interactions between ethylbenzene and chemicals that inhibit cytochrome P-450 (e.g., carbon monoxide; Maylin et al. 1973), compete with ethylbenzene for metabolism by cytochrome P-450 (e.g., alkylbenzenes, ethanol; Angerer and Lehnert 1979; Elovaara et al. 1984; Engstrom et al. 1984; Romer et al. 1986), or induce cytochrome P-450 (e.g. phenobarbital; Maylin et al. 1973; McMahon and Sullivan 1966). Competitive inhibition of metabolism by alkylbenzenes, including ethylbenzene, has been introduced into PBPK models of alkylbenzene mixtures and gasoline component mixtures (Dennison et al. 2003, 2004; Haddad et al. 2001; Tardif et al. 1997).

#### 3.10 POPULATIONS THAT ARE UNUSUALLY SUSCEPTIBLE

A susceptible population will exhibit a different or enhanced response to ethylbenzene than will most persons exposed to the same level of ethylbenzene in the environment. Reasons may include genetic makeup, age, health and nutritional status, and exposure to other toxic substances (e.g., cigarette smoke). These parameters result in reduced detoxification or excretion of ethylbenzene, or compromised function of organs affected by ethylbenzene. Populations who are at greater risk due to their unusually high exposure to ethylbenzene are discussed in Section 6.7, Populations with Potentially High Exposures.

### 3. HEALTH EFFECTS

Even though ethylbenzene is not known to bioaccumulate (Aster 1995; Meylan et al. 1999; Nuns and Benville 1979; Ogata et al. 1984), human and animal studies suggest that several factors can contribute to an increased probability of adverse health effects following ethylbenzene exposure (NIOSH/OSHA 1978). Exposure to ethylbenzene has been shown to produce hearing loss in humans and animals; therefore, individuals with pre-existing hearing loss (e.g., congenital or infection-related) or individuals participating in activities that may result in hearing loss (e.g., sharpshooting) may be more susceptible to the ototoxic effects of ethylbenzene. Exposure of individuals with impaired pulmonary function to ethylbenzene in air has been shown to exacerbate symptoms because of ethylbenzene's irritant properties. Because ethylbenzene is detoxified primarily in the liver and excreted by the kidney, individuals with liver or kidney disease might be more susceptible to ethylbenzene toxicity, as would persons taking medications or other drugs (e.g., alcohol) that are known hepatotoxins. Persons with dermatitis or other skin diseases may be at greater risk, since ethylbenzene is a defatting agent and may aggravate these symptoms. Children's susceptibility is discussed in Section 3.7.

In summary, groups that might be more susceptible to the toxic effects of ethylbenzene are individuals with hearing loss and diseases of the respiratory system, liver, kidney, or skin; young children; fetuses; pregnant women; and individuals taking certain medications such as hepatotoxic medications or drugs.

#### 3.11 METHODS FOR REDUCING TOXIC EFFECTS

This section will describe clinical practice and research concerning methods for reducing toxic effects of exposure to ethylbenzene. However, because some of the treatments discussed may be experimental and unproven, this section should not be used as a guide for treatment of exposures to ethylbenzene. When specific exposures have occurred, poison control centers and medical toxicologists should be consulted for medical advice. The following texts provide specific information about treatment following exposures to ethylbenzene:

Leikin JB, Poloucek FP. 2002. Poisoning and toxicology handbook. Hudson, OH: Lexi-Comp, Inc., 554.

Proctor NH, Hughes JP. 1978. Chemical hazards of the workplace. Philadelphia, PA: J.B. Lippincott Company, 251-252.



### 3. HEALTH EFFECTS

#### **3.11.1 Reducing Peak Absorption Following Exposure**

Human exposure to ethylbenzene can occur by inhalation, oral, or dermal contact. General recommendations for reducing absorption of ethylbenzene following exposure include removing the exposed individual from the contaminated area and removing the contaminated clothing. Removal of the patient from the source of contamination is an initial priority along with proper ventilation and cardiac monitoring. If the eyes and skin were exposed, they should be flushed with water. Emesis or lavage is not recommended following oral exposure due to the risk of aspiration pneumonia (Leikin and Paloucek 2002). Activated charcoal may be administered to adsorb ethylbenzene (Leikin and Paloucek 2002). Benzodiazepines may be used to control seizures (Leikin and Paloucek 2002). Administration of catecholamines should be avoided due to the risk of ventricular arrhythmia (Leikin and Paloucek 2002).

#### **3.11.2 Reducing Body Burden**

Following absorption into the blood, ethylbenzene is rapidly distributed throughout the body. The initial stage of ethylbenzene metabolism in humans is the formation of 1-phenylethanol via hydroxylation of the side chain. Further oxidation leads to the formation of mandelic acid and phenylglyoxylic acid, the major urinary metabolites of ethylbenzene in humans. Detoxication pathways generally involve the formation of glucuronide or sulfate conjugates of 1-phenylethanol or its subsequent metabolites. Urinary excretion is the primary route of elimination of metabolized ethylbenzene. Studies in humans and animals indicate that urinary excretion occurs in several phases, with half-lives of hours. Hence, ethylbenzene and its metabolites have relatively short half-lives in the body, and while some of these metabolites are clearly toxic, substantial body burdens are not expected.

No methods are currently used for reducing the body burden of ethylbenzene. It is possible that methods could be developed to enhance the detoxication and elimination pathways.

#### **3.11.3 Interfering with the Mechanism of Action for Toxic Effects**

Treatments interfering with the mechanism of action for toxic effects have not been identified.

## 3. HEALTH EFFECTS

**3.12 ADEQUACY OF THE DATABASE**

Section 104(I)(5) of CERCLA, as amended, directs the Administrator of ATSDR (in consultation with the Administrator of EPA and agencies and programs of the Public Health Service) to assess whether adequate information on the health effects of ethylbenzene is available. Where adequate information is not available, ATSDR, in conjunction with the National Toxicology Program (NTP), is required to assure the initiation of a program of research designed to determine the health effects (and techniques for developing methods to determine such health effects) of ethylbenzene.

The following categories of possible data needs have been identified by a joint team of scientists from ATSDR, NTP, and EPA. They are defined as substance-specific informational needs that if met would reduce the uncertainties of human health assessment. This definition should not be interpreted to mean that all data needs discussed in this section must be filled. In the future, the identified data needs will be evaluated and prioritized, and a substance-specific research agenda will be proposed.


**3.12.1 Existing Information on Health Effects of Ethylbenzene**

The existing data on health effects of inhalation, oral, and dermal exposure of humans and animals to ethylbenzene are summarized in Figure 3-6. The purpose of this figure is to illustrate the existing information concerning the health effects of ethylbenzene. Each dot in the figure indicates that one or more studies provide information associated with that particular effect. The dot does not necessarily imply anything about the quality of the study or studies, nor should missing information in this figure be interpreted as a “data need”. A data need, as defined in ATSDR’s *Decision Guide for Identifying Substance-Specific Data Needs Related to Toxicological Profiles* (Agency for Toxic Substances and Disease Registry 1989), is substance-specific information necessary to conduct comprehensive public health assessments. Generally, ATSDR defines a data gap more broadly as any substance-specific information missing from the scientific literature.

Figure 3-6 graphically describes the existing health effects information on ethylbenzene by route and duration of exposure. Little information concerning humans exposed via inhalation to ethylbenzene is available. Most of the information concerning health effects in humans is reported in occupational studies, which are difficult to interpret given the limitations of the studies (e.g., simultaneous exposure to other hazardous substances, unquantified exposure concentrations, and exposure probably occurring by a combination of routes). No data were available concerning human health effects following oral exposures

3. HEALTH EFFECTS

**Figure 3-6. Existing Information on Health Effects of Ethylbenzene**



● Existing Studies

### 3. HEALTH EFFECTS

to ethylbenzene. Dermal effects in humans exposed to ethylbenzene vapors include respiratory and ocular irritation.

In animals, the lethality of ethylbenzene is documented for all routes of exposure. Systemic, immunologic, neurologic, developmental, and reproductive effects have been reported following acute-, intermediate-, or chronic-duration inhalation exposures to ethylbenzene. Limited data on the health effects resulting from oral or dermal exposure to ethylbenzene were located.

#### 3.12.2 Identification of Data Needs

In general, data on the toxic effects of ethylbenzene in humans and animals are limited. In many areas for which studies have been conducted, the lack of reliable data precludes any definitive conclusions from being drawn.

**Acute-Duration Exposure.** The database for acute-duration inhalation exposure to ethylbenzene is largely composed of inhalation studies in laboratory animals with a limited number of human studies. The available acute-duration studies in humans (Sliwinska-Kowalska et al. 2001; Yant et al. 1930) and animals (Andersson et al. 1981; Cappaert et al. 1999, 2000, 2001, 2002; Ethylbenzene Producers Association 1986a; Molnar et al. 1986; Tegeris and Balster 1994; Yant et al. 1930) indicate that the nervous system, and particularly the auditory system, is sensitive to the toxic effects of ethylbenzene. The available reports and studies in humans are of limited use for dose-response assessment because insufficient information was provided to clearly characterize the exposure to ethylbenzene or because exposures were for mixtures of solvents, not ethylbenzene alone. Ethylbenzene is an acute ocular and respiratory irritant in humans (Cometto-Muñiz and Cain 1995; Thienes and Haley 1972; Yant et al. 1930); however, animal studies suggest that acute sublethal inhalation exposures do not result in pulmonary histopathology (Ethylbenzene Producers Association 1986a). Developmental and reproductive effects were reported in animals exposed to ethylbenzene by inhalation during gestation (Ungváry and Tátrai 1985); however, the latter study is limited by incomplete description of the results and the absence of an analysis on a per litter basis. Increased organ weight (liver, kidneys) has been observed in a number of studies in animals (Ethylbenzene Producers Association 1986a; Toftgard and Nilsen 1982); however, no findings are made upon microscopic examination of the liver or kidneys (Ethylbenzene Producers Association 1986a). An acute-duration inhalation MRL of 10 ppm was derived based on ototoxicity in animals. No studies describing acute-duration oral exposure of humans to

## 3. HEALTH EFFECTS

ethylbenzene were found in the literature. Although two animal studies have examined the acute oral toxicity of ethylbenzene (Gagnaire and Langlais 2005; Ungvary 1986), they were not adequate for the derivation of an acute-duration oral MRL. Mild irritation (Smyth et al. 1962), reddening, exfoliation, and blistering (Wolf et al. 1956) have been reported in rabbits when ethylbenzene was applied directly on the skin. Slight irritation of the eye (Wolf et al. 1956) and corneal injuries (Smyth et al. 1962; Wolf et al. 1956) were observed in rabbits when ethylbenzene was instilled onto the eyes. There is a data need for additional acute-duration oral and dermal toxicity studies in animals exposed to ethylbenzene.

**Intermediate-Duration Exposure.** The database of intermediate-duration inhalation studies includes several studies in animals, but no studies in humans. It has been shown that the auditory system is sensitive to the toxic effects of ethylbenzene after intermediate-duration inhalation exposure (Gagnaire et al. 2007). Systemic effects have been observed at concentrations equal to or higher than those that elicited ototoxic effects in rats. Effects at even higher concentrations include neurological and hematological effects (Cragg et al. 1989; Wolf et al. 1956) and increased organ weight (Cragg et al. 1989; Elovaara et al. 1985; NIOSH 1981; NTP 1992; Wolf et al. 1956). Organs showing increased weight did not show treatment-related histopathological effects (Cragg et al. 1989; NTP 1992). Developmental and/or reproductive effects have been reported in offspring of animals following intermediate-duration inhalation exposures to ethylbenzene during gestation (Faber et al. 2006, 2007; NIOSH 1981; Saillenfait et al. 2003, 2006, 2007) at concentrations that were higher than those that elicited ototoxic effects. An intermediate-duration inhalation MRL of 0.7 ppm was derived based on the observed ototoxic effects in animals (Gagnaire et al. 2007). The intermediate-duration oral database for ethylbenzene is limited to the critical study by Mellert et al. (2007) evaluating the effects of oral exposure of rats to ethylbenzene for 4 and 13 weeks, and a poorly reported 6-month exposure study in rats (Wolf et al. 1956). Results of the 13-week gavage study in rats observed effects indicative of liver toxicity, including increased activity of serum liver enzymes (ALT and GGT), increased absolute and relative liver weights, and a dose-related increase in the incidence of centrilobular hepatocyte hypertrophy. Results of the 4-week exposure study in rats are similar to those observed in the 13-week study, showing that the liver is the primary target organ for oral ethylbenzene; effects consistent with hepatotoxicity, including increased absolute and relative liver weights, increased incidence of hepatocyte centrilobular, and increased serum liver enzyme activity (ALT) (Mellert et al. 2007). Wolf et al. (1956) reported slight weight and histopathological effects in the liver and kidney of female rats. An intermediate-duration oral MRL of 0.5 mg/kg/day was derived based on the observed liver effects in animals exposed for 13 weeks (Mellert et al. 2007).

## 3. HEALTH EFFECTS

**Chronic-Duration Exposure and Cancer.** The database of chronic-duration/carcinogenicity inhalation studies with ethylbenzene includes a chronic duration study in rats and mice (NTP 1999) and a limited number of studies in humans. Hematological effects were observed in workers exposed to solvents containing ethylbenzene (Angerer and Wulf 1985), but no hematological effects, liver lesions or effects on liver function, or cases of malignancy were reported in a study of workers exposed chronically (>20 years) to ethylbenzene (Bardodej and Cirek 1988). The severity of nephropathy was significantly increased in female and male rats exposed to  $\geq 75$  or 750 ppm ethylbenzene, respectively, for 2 years (NTP 1999). At higher concentrations rats showed significant increases in renal tubule hyperplasia; male rats showed an increased incidence of interstitial cell adenoma in the testis. Effects observed in male or female mice exposed to ethylbenzene for 2 years include an increased incidence of hyperplasia of the pituitary gland pars distalis, increased incidence of follicular cell hyperplasia in the thyroid gland, an increased incidence of syncytial alterations of the hepatocytes, hypertrophy, and hepatic necrosis, and an increased incidence of eosinophilic foci (NTP 1999). Ethylbenzene showed clear evidence of carcinogenic activity in male rats based on increased incidences of renal tubule neoplasms, some evidence of carcinogenic activity in female rats based on increased incidences of renal tubule adenomas, some evidence of carcinogenic activity in male mice based on increased incidences of alveolar/bronchiolar neoplasms, and some evidence of carcinogenic activity in female mice based on increased incidences of hepatocellular neoplasms (NTP 1999). The 2-year inhalation study in rats suggests that an increase in the severity of nephropathy in female rats is the most sensitive end point of ethylbenzene exposure. This end point was selected to estimate a chronic-duration inhalation MRL of 0.3 ppm. There is no need to conduct additional carcinogenicity studies of ethylbenzene via inhalation. A statistically significant increase in total malignant tumors was reported in female rats and in combined male and female groups exposed to 500 mg/kg/day via gavage for 104 weeks (Maltoni et al. 1985). No data on specific tumor type were presented, only one dose was tested, and no information on survival was provided. It might be useful to conduct a toxicity and carcinogenicity study of ethylbenzene administered orally to at least two animal species. It might be useful to conduct chronic-duration studies in at least two species with an emphasis in ototoxic effects.

**Genotoxicity.** Available human data (Holz et al. 1995) indicate that ethylbenzene may be marginally genotoxic. A weak induction of sister chromatid exchanges in human lymphocytes following ethylbenzene exposure was seen (Norppa and Vainio 1983a). Data are available regarding the genotoxic potential of ethylbenzene from *in vitro* assays in bacteria, yeast, and mammalian cell cultures (McGregor et al. 1988; NTP 1999). Although the results generally indicate that ethylbenzene is not genotoxic, marginal genotoxic effects have been reported in some tests. Independent confirmation or refutation of

### 3. HEALTH EFFECTS

these studies, as well as further genotoxicity studies, especially in mammalian systems, would help provide clarification of these conflicting results. In particular, chromosome aberrations in occupationally exposed persons would provide useful information.

**Reproductive Toxicity.** No studies were located regarding reproductive effects in humans following inhalation exposure to ethylbenzene. Reproductive end points have been assessed after acute- (Ungváry and Tátrai 1985) and intermediate-duration exposures of animals exposed during gestation (Saillenfait et al. 2003, 2006, 2007) and in a two-generation reproductive toxicity study (Faber et al. 2006, 2007). Effects on reproductive organs (Cragg et al. 1989; NTP 1992, 1999; Wolf et al. 1956) in animals exposed to ethylbenzene have also been evaluated. The only available oral-exposure reproduction study reported decreased hormone levels and blockage or delay of the estrus cycle in female rats (Ungváry 1986). Additional inhalation exposure reproductive toxicity studies are not deemed necessary at this time. It might be useful to conduct additional oral exposure reproductive toxicity studies in at least two species.

**Developmental Toxicity.** No studies of developmental effects in humans following inhalation exposure to ethylbenzene were located. The available studies have reported developmental effects in the offspring of animals exposed to ethylbenzene during gestation (NIOSH 1981; Saillenfait et al. 2003, 2006, 2007; Ungváry and Tátrai 1985). The report by Ungváry and Tátrai (1985) has many deficiencies, including poor reporting of the experimental conditions and poor description of the maternal and fetal observations. Maternal toxicity has been generally reported at the highest doses tested (Saillenfait et al. 2003, 2006, 2007; Ungváry and Tátrai 1985). Biologically or statistically significant developmental or neurodevelopmental effects were not observed in the offspring of animals in a two-generation inhalation study (Faber et al. 2006, 2007). No studies were located regarding developmental effects in humans and animals following oral or dermal exposure to ethylbenzene. A data need exists for oral and dermal developmental toxicity studies.

**Immunotoxicity.** No studies were found regarding immunological effects in humans following inhalation exposure to ethylbenzene. Studies were located that examined organs of the immune system in animals after intermediate- (Cragg et al. 1989; NIOSH 1981; NTP 1992) or chronic-duration (NTP 1999) exposure to ethylbenzene. No studies were located regarding immunological effects in humans or animals following oral or dermal exposure to ethylbenzene. No additional immunological studies are deemed to be necessary at this time.

### 3. HEALTH EFFECTS

**Neurotoxicity.** Human studies have established that acute exposure to ethylbenzene may result in dizziness and vertigo (Yant et al. 1930) and that hearing loss is significantly increased in workers exposed to solvent mixtures that include ethylbenzene (Sliwinska-Kowalska et al. 2001). The role of ethylbenzene in the observed hearing losses cannot be ascertained from this study given that ethylbenzene was only one of several solvents.

Animal studies indicate that the auditory system is the most sensitive target of ethylbenzene toxicity after acute- (Cappaert et al. 1999, 2000, 2001, 2002) or intermediate-duration (Gagnaire et al. 2007) inhalation exposures and after acute-duration oral exposures to ethylbenzene (Gagnaire and Langlais 2005). The effects of ethylbenzene on the central nervous system have been assessed in animals after acute-duration exposure to ethylbenzene (Ethylbenzene Producers Association 1986a; Molnar et al. 1986; Tegeris and Balster 1994; Yant et al. 1930). Neurobiochemical and electrical activity alterations have been reported in animals after acute-duration exposure to ethylbenzene (Andersson et al. 1981; Frantik et al. 1994; Mutti et al. 1988; Romanelli et al. 1986). No adverse histopathological findings were observed in brain tissue of animals after intermediate- (NTP 1992) or chronic-duration (NTP 1999) exposure to ethylbenzene. No studies were located regarding neurological effects in humans following oral exposure to ethylbenzene. Ototoxicity is also observed in animals after acute-duration oral exposure to ethylbenzene (Gagnaire and Langlais 2005). Additional studies are needed to establish the mechanism of action by which ethylbenzene elicits ototoxicity, as no information on the mechanism of ethylbenzene-induced ototoxicity was identified. Furthermore, due to the large differences between rats and guinea pigs in susceptibility to ethylbenzene-induced ototoxicity, additional studies on hearing and ear physiology in rodents are needed to evaluate which species is most similar to humans. No studies were located regarding neurological effects in humans or animals following dermal exposure to ethylbenzene. Additional inhalation studies are needed to establish an intermediate-duration NOAEL for ototoxic effects. Additional studies are also needed to characterize the concentration-response pattern for ototoxicity after acute- and intermediate-duration oral exposures to ethylbenzene.

**Epidemiological and Human Dosimetry Studies.** The few available epidemiological studies on the health effects of ethylbenzene were primarily limited to occupational studies in which quantitative estimates of exposure were lacking and other limitations (e.g., multiple exposure routes, simultaneous exposure to other hazardous chemicals) were present. Studies using volunteers exposed to low concentrations of ethylbenzene have provided useful information on effects of acute-duration inhalation exposure on the central nervous system (Yant et al. 1930). No studies were available in which humans were exposed orally or dermally to ethylbenzene. Epidemiological studies conducted in populations



### 3. HEALTH EFFECTS

exposed to ethylbenzene alone may provide useful information on the effects of ethylbenzene in humans. Emphasis should be placed in the detection of ototoxic effects as this end point is the most sensitive effect observed in animal studies.

**Biomarkers of Exposure and Effect.** Sensitive methods are available for determining ethylbenzene and ethylbenzene metabolites in biological tissues and fluids. However, limited data are available associating levels of ethylbenzene in human tissues and fluids with adverse health effects. Additional animal or epidemiological studies evaluating the association between levels in tissue or fluids and adverse health effects would be useful to devise more sensitive and more specific early biomarkers of effect.

**Exposure.** Exposure to ethylbenzene can be monitored through levels of ethylbenzene in breath, blood, or tissue, or levels of its metabolites, mandelic or phenylglyoxylic acid in urine. A statistically significant correlation was observed between urinary excretion of mandelic acid and ethylbenzene exposure in workers exposed to mixed solvents (including an ethylbenzene TWA of 0.9 ppm) in a metal-coating factory (Kawai et al. 1991). However, neither one of the metabolites is specific to ethylbenzene. Additional studies to identify a biomarker or biomarkers of exposure specific to ethylbenzene are needed.

**Effect.** There are currently no known specific biomarkers of effect for ethylbenzene. Development of methods to identify biomarkers that would indicate toxic effects, and the extent of those toxic effects after exposure to ethylbenzene, would be helpful in managing health effects that occur after significant exposure to ethylbenzene.

**Absorption, Distribution, Metabolism, and Excretion.** Ethylbenzene is absorbed by humans following inhalation (Bardodej and Bardodejova 1970; Gromiec and Piotrowski 1984) and dermal (Dutkiewicz and Tyras 1967) exposures. Absorption rates were 49–64% by inhalation. Dermal absorption rates were in the range of 24–33 and 0.11–0.23 mg/cm<sup>2</sup>/hour for male subjects exposed to liquid ethylbenzene and ethylbenzene from aqueous solutions, respectively (Dutkiewicz and Tyras 1967). Animal data support these findings and indicate that absorption rates are high following oral exposures as well (Climie et al. 1983; El Masry et al. 1956).

Only one study (Engstrom and Bjurstrom 1978) is available that outlines the distribution of ethylbenzene in humans following inhalation exposure. This study indicates rapid distribution to adipose tissues throughout the body. Inhalation studies in animals support these results (Elovaara et al. 1982; Engstrom

## 3. HEALTH EFFECTS

et al. 1985). Ethylbenzene is accumulated primarily in the intestine, liver, kidney, and fat, which provides some basis for ethylbenzene-induced effects observed in the liver and kidney. No data on distribution of ethylbenzene following dermal exposure were located. Such information would be useful because absorption of liquid ethylbenzene via this route is rapid in humans and because the potential exists in humans for dermal exposure.

The metabolism of ethylbenzene in humans and animals has been studied. Although some differences in the metabolic pattern according to route of exposure, sex, nutritional status (Nakajima and Sato 1979), and species (Bakke and Scheline 1970; Climie et al. 1983; El Masry et al. 1956; Engstrom et al. 1984, 1985; Smith et al. 1954a, 1954b; Sollenberg et al. 1985) have been documented, pharmacokinetic data show no significant differences in metabolism between oral and inhalation routes in either humans or animals (Climie et al. 1983; Engstrom et al. 1984, 1985). Further studies that correlate these differences in metabolism with differences in health effects would be useful. Data on metabolism following dermal exposure are sparse, because it is difficult to accurately measure absorption of volatile compounds. Additional data on metabolism following dermal exposure would be useful as these exposures could occur both from contaminated soil or groundwater.

Ethylbenzene has been shown to be rapidly eliminated from the body following inhalation exposure (primarily in the urine) in both humans and animals. These studies (Gromiec and Piotrowski 1984; Yamasaki 1984) are sufficient to characterize the elimination of ethylbenzene following inhalation exposure. A small number of studies in animals exposed orally and humans exposed dermally support these findings. Further studies on elimination of ethylbenzene via these exposure routes would be useful, especially because differences in the excretion patterns have been observed with different routes of exposure.

PBPK models have been developed for predicting ethylbenzene kinetics (including metabolism) in rats and humans exposed by inhalation (Dennison et al. 2003, 2004; Tardif et al. 1997). No models have been developed for simulating kinetics or oral exposures. Oral models would be potentially useful for route-to-route extrapolations (e.g., inhalation to oral) of internal doses of ethylbenzene.

**Comparative Toxicokinetics.** Quantitative and qualitative variations in the absorption, distribution, metabolism, and excretion of ethylbenzene were observed depending on exposure routes, sex, nutritional status, and species, as previously outlined. Further studies that focus on these differences and their implications for human health would be useful. Additionally, *in vitro* studies using human tissue and

### 3. HEALTH EFFECTS

PBPK modeling would contribute significantly to the understanding of the kinetics of ethylbenzene, since they would provide information on half-lives and saturation kinetics associated with the metabolism of ethylbenzene.

**Methods for Reducing Toxic Effects.** No information was found that specifically addressed the reduction of toxic effects after absorption of ethylbenzene. Development of clinical procedures for minimizing the effects of ethylbenzene on the respiratory, hepatic, and renal systems, and the central nervous system would be useful in situations where significant exposure had occurred.

**Children's Susceptibility.** Data needs relating to both prenatal and childhood exposures, and developmental effects expressed either prenatally or during childhood, are discussed in detail in the Developmental Toxicity subsection above.

There are no data describing the effects of ethylbenzene exposure in children or developing postnatal animals. Data needs relating to development are discussed in more detail above under developmental effects. In order to evaluate whether ethylbenzene presents a unique hazard to children, additional information on the health effects, pharmacokinetics, metabolism, and mechanism of action in children is needed. It is unknown whether children differ from adults in their susceptibility to health effects from exposure to ethylbenzene. Pharmacokinetic studies investigating whether ethylbenzene or its active metabolites cross the placenta or are transferred into breast milk would be useful. Studies to determine whether there are specific biomarkers of exposure in children would be helpful in monitoring the exposure of children to this chemical. In addition, information describing methods of reducing toxic effects and decreasing body burden in children might be helpful.

Child health data needs relating to exposure are discussed in Section 6.8.1, Identification of Data Needs: Exposures of Children.

#### 3.12.3 Ongoing Studies

Ongoing studies pertaining to ethylbenzene have been identified and are shown in Table 3-9 (FEDRIP 2007).

## 3. HEALTH EFFECTS

**Table 3-9. Ongoing Studies on Ethylbenzene**

Investigator	Affiliation	Research description	Sponsor
Thrall KD	Battelle Pacific Northwest Laboratories	Dermatopharmacokinetics of paint solvents.	National Institute for Occupational safety and Health
Backes WL	Louisiana State University	Identify conditions under which individuals may be susceptible to alkylbenzene-induced toxicity.	National Institute of environmental Health Sciences
Burke J	Environmental Protection Agency	A critical review and probabilistic model input distribution development for microenvironmental exposures to benzene.	Environmental Research Laboratories
Davis-Hoover W	Environmental Protection Agency	Determining if biologically active <i>in situ</i> BioNets could bioremediate methyl- <i>tert</i> -butyl ether and BTEX contaminated groundwater.	Risk Management Resource Library
Venosa A	Environmental Protection Agency	Treatability of co-mingled groundwater plume contaminated with polycyclic aromatic hydrocarbons.	Risk Management Resource Library
Vroblesky DA	Department of the Interior, U.S. Geological Survey, Water Resources Division	Remediation of JP-4 contamination using hydraulic containment and <i>in situ</i> biodegradation at the Defense Fuel Supply Center, Charleston, South Carolina.	Department of the Interior, U.S. Geological Survey, Water Resources Division
Jayarao BM	Pennsylvania State University, Veterinary Science	Bioreporter-based technology for detection of organic toxicants directly from milk and milk products.	Pennsylvania State University, Veterinary Science
Sylva TY	University of Hawaii, Molecular Biosciences and Biosystems	Application of bioremediation to hydrocarbon contaminated soils.	University of Hawaii, Molecular Biosciences and Biosystems
Holm RH	Harvard University, Department of Chemistry	Transformations catalyzed by the molybdenum and tungsten oxotransferases and hydroxylases.	National Science Foundation
Miknis F	FETC-MGN	Noncatalytic concept for the direct conversion of fossil fuels and hydrocarbon-containing materials to transportation fuels with simultaneous reduction in the heteroatom content.	Office of Fossil Energy
Starr RC	Idaho National Engineering and Environmental Laboratory	Development and testing of an <i>in situ</i> system for remediating groundwater contaminated with BTEX.	Office of Fossil Energy
Friesen DT	Bend Research, Inc.	High-performance membranes for gas, vapor, and liquid separations.	Office of Energy Research
Sibold J	Golden Technologies Company, Inc.	Investigating the use of ceramic membranes in dehydrogenation reactions.	Energy Efficiency, Department of Energy

## 3. HEALTH EFFECTS

**Table 3-9. Ongoing Studies on Ethylbenzene**

Investigator	Affiliation	Research description	Sponsor
Ittrell J	SE, Inc.	Advanced low temperature emissions control technology for MTB destruction.	SE, Inc.
aPierre R	Recision Combustion, Inc	Investigating ano-zeolite coatings on microlith substrates for high selectivity chemical reactions.	Recision Combustion, Inc.

BTEX = benzene, toluene, ethylbenzene, and xylenes

Source: FEDRIP 2007

3. HEALTH EFFECTS

This page is intentionally blank.

## 4. CHEMICAL AND PHYSICAL INFORMATION

### 4.1 CHEMICAL IDENTITY


Ethylbenzene is an aromatic hydrocarbon that occurs naturally in petroleum and is a component of aviation and automotive fuels. It is used as a solvent and in the production of synthetic rubber and styrene. Information regarding the chemical identity of ethylbenzene is located in Table 4-1.

### 4.2 PHYSICAL AND CHEMICAL PROPERTIES

Ethylbenzene is a colorless liquid with an aromatic odor. Information regarding the physical and chemical properties of ethylbenzene is located in Table 4-2. Ethylbenzene is a flammable and combustible liquid. Vapors are heavier than air and may travel to a source of ignition and flash back. Liquid ethylbenzene floats on water and may travel to a source of ignition and spread fire. Combustion may produce irritants and toxic gases (NFPA 1994). Ethylbenzene may accumulate static electricity and will react with oxidizing materials (NFPA 1994).

## 4. CHEMICAL AND PHYSICAL INFORMATION

**Table 4-1. Chemical Identity of Ethylbenzene**

Characteristic	Information	Reference
Chemical name	Ethylbenzene	Budavari and O'Neil 1989
Synonym(s)	EB; ethyl benzene; ethylbenzol; phenylethane; etilbenzene; ethylbenzeen; aethylbenzol	HSDB 2007
Registered trade name(s)	No data	
Chemical formula	C <sub>8</sub> H <sub>10</sub>	Budavari and O'Neil 1989
Chemical structure		Verschueren 1983
Identification numbers:		
CAS registry	100-41-4	Budavari and O'Neil 1989
NIOSH RTECS	NIOSH/DA0700000	RTECS 2007
EPA hazardous waste	F003	HSDB 2007
OHM/TADS	7216709	HSDB 1995
DOT/UN/NA/IMDG shipping	UN 1175; IMDG 3.2	HSDB 2007
HSDB	84	HSDB 2007
NCI	NCI-C56393	HSDB 2007
STCC	49 091 63	HSDB 2007

CAS = Chemical Abstracts Service; DOT/UN/NA/IMDG = Department of Transportation/United Nations/North America/International Maritime Dangerous Goods Code; EPA = Environmental Protection Agency; HSDB = Hazardous Substances Data Bank; NCI = National Cancer Institute; NIOSH = National Institute for Occupational Safety and Health; OHM/TADS = Oil and Hazardous Materials/Technical Assistance Data System; RTECS = Registry of Toxic Effects of Chemical Substances; STCC = Standard Transport Commodity Code



## 4. CHEMICAL AND PHYSICAL INFORMATION

**Table 4-2. Physical and Chemical Properties of Ethylbenzene**

Property	Information	Reference
Molecular weight	106.17	Lide 1994
Color	Colorless	Budavari and O'Neil 1989
Physical state	Liquid	Budavari and O'Neil 1989
Melting point	-95 °C	Lide 1994
Boiling point	136.2 °C	Lide 1994
Density at 20 °C/4 °C	0.8670	Lide 1994
at 25 °C/25 °C	0.866	Budavari and O'Neil 1989
Odor	Sweet, gasoline-like	CHRIS 1985
Odor threshold:		
Water	0.029 mg/L	Amoore and Hautala 1983
	0.140 mg/L	Rosen et al. 1963; Verschueren 1983
Air	2.3 ppm	Amoore and Hautala 1983
	2–2.6 mg/m <sup>3</sup>	Verschueren 1983
Solubility:		
Water at 0 °C	197 mg/L	Polak and Lu 1973
at 15 °C	140 mg/L	Verschueren 1983
at 20 °C	152 mg/L	Verschueren 1983
at 25 °C	160 mg/L	Amoore and Hautala 1983
at 25 °C	177 mg/L	Polak and Lu 1973
at 25 °C	208 mg/L	Bohon and Claussen 1951
Organic solvents	Miscible with usual organic solvents	Budavari and O'Neil 1989
	Soluble in alcohol and ether	Lide 1994
Partition coefficients:		
Log K <sub>ow</sub>	4.34	EPA 1982
	3.13	Yalkowsky and Valvani 1976
	3.15	Hansch and Leo 1979
Log K <sub>oc</sub>	2.22 (calculated)	Chiou et al. 1983
	2.38 (measured)	Hodson and Williams 1988
	2.40 (calculated)	Vowles and Mantoura 1987
Vapor pressure		
at 20 °C	7 mm Hg	Verschueren 1983
at 25 °C	1.27 kPa (9.53 mm Hg)	Mackay and Shiu 1981
at 25.9 °C	10 mm Hg	Sax and Lewis 1989
at 30 °C	12 mm Hg	Verschueren 1983
Henry's law constant:		
at 20 °C	6.6x10 <sup>-3</sup> atm-m <sup>3</sup> /mol	EPA 1982
at 20 °C	8.7x10 <sup>-3</sup> atm-m <sup>3</sup> /mol	Lyman et al. 1982
at 25 °C	8.43x10 <sup>-3</sup> atm-m <sup>3</sup> /mol	Mackay et al. 1979
at 25 °C	7.9x10 <sup>-3</sup> atm-m <sup>3</sup> /mol	Mackay and Shiu 1981

## 4. CHEMICAL AND PHYSICAL INFORMATION

**Table 4-2. Physical and Chemical Properties of Ethylbenzene**

Property	Information	Reference
Autoignition temperature	810 °F (432 °C)	NFPA 1994
Flash point	70 °F (21 °C)	NFPA 1994
Flammability limits	0.8 (lower) vol% –6.7 (upper) vol%	NFPA 1994
Conversion factors (25 °C, 1 atm)	1 mg/m <sup>3</sup> =0.230 ppm 1 ppm=4.35 mg/m <sup>3</sup>	Verschueren 1983

## 5. PRODUCTION, IMPORT/EXPORT, USE, AND DISPOSAL

### 5.1 PRODUCTION

Ethylbenzene is primarily produced by the alkylation of benzene with ethylene in liquid-phase slurry reactors promoted with aluminum trichloride catalysts or by vapor-phase reaction of benzene with dilute ethylene-containing feedstock with a boron trifluoride catalyst supported on alumina (Clayton and Clayton 1981; HSDB 2007; Ransley 1984). Other methods of manufacturing ethylbenzene include preparation from acetophenone, dehydrogenation of naphthenes, catalytic cyclization and aromatization, separation from mixed xylenes via fractionation, reaction of ethylmagnesium bromide and chlorobenzene, extraction from coal oil, and recovery from benzene-toluene-xylene (BTX) processing (Clayton and Clayton 1981; HSDB 2007; Ransley 1984). Commercial grades of ethylbenzene may also contain small amounts of *m*-xylene, *p*-xylene, cumene, and toluene (HSDB 2007).

Ethylbenzene is traditionally ranked as one of the top 50 chemicals produced in the United States. Table 5-1 shows the historical production volumes of ethylbenzene from 1983 to 2005 (C&EN 1994a, 1994b, 1995, 2006; Kirschner 1995).

Table 5-2 lists the facilities in each state that manufacture or process ethylbenzene, the intended use, and the range of maximum amounts of ethylbenzene that are stored on site. There are currently 3,558 facilities that produce, process, or use ethylbenzene in the United States. The data listed in Table 5-2 are derived from the Toxics Release Inventory (TRI05 2007). These data should be used with caution however since only certain types of facilities are required to report (EPA 1995d). Therefore, this is not an exhaustive list.

Currently, there are eight major producers of ethylbenzene in the United States, with a combined annual production capacity of approximately 15.8 billion pounds (SRI 2006). These producers and their respective plant locations are provided in Table 5-3.

### 5.2 IMPORT/EXPORT

According to the Chemical Marketing Reporter, import volumes were negligible in 2002 and were  $4.95 \times 10^7$  kg (109 million pounds) in 2003 (CMR 2004). Import volumes for ethylbenzene have been

## 5. PRODUCTION, IMPORT/EXPORT, USE, AND DISPOSAL

**Table 5-1. Ethylbenzene Production in the United States from 1983 to 2005**

Year	Production in thousands of metric tons	Production in billions of pounds
1983	3,583	7.9
1984	3,447	7.6
1985	3,357	7.4
1986	4,082	9.0
1987	4,218	9.3
1988	4,491	9.9
1989	4,173	9.2
1990	3,810	8.4
1991	5,171	11.4
1992	5,035	11.1
1993	5,352	11.8
1994	5,398	11.9
1995	6,194	13.7
1996	4,699	10.4
1997	5,432	12.0
1998	5,743	12.7
1999	5,945	13.1
2000	5,968	13.2
2001	4,642	10.2
2002	5,412	11.9
2003	5,578	12.3
2004	5,779	12.7
2005	5,251	11.6

Source: C&EN 1994a, 1994b, 1995, 2006; Kirschner 1995

## 5. PRODUCTION, IMPORT/EXPORT, USE, AND DISPOSAL

**Table 5-2. Facilities that Produce, Process, or Use Ethylbenzene**

State <sup>a</sup>	Number of facilities	Minimum amount on site in pounds <sup>b</sup>	Maximum amount on site in pounds <sup>b</sup>	Activities and uses <sup>c</sup>
AK	21	0	49,999,999	1, 2, 3, 4, 5, 7, 8, 9, 10, 12
AL	105	0	99,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
AR	48	0	9,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
AS	1	100,000	999,999	9
AZ	33	100	9,999,999	1, 2, 4, 5, 7, 8, 9, 10, 11, 12, 13
CA	230	0	99,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
CO	32	0	9,999,999	1, 2, 3, 4, 6, 7, 8, 9, 10, 11, 12, 13
CT	37	0	999,999,999	1, 2, 3, 4, 6, 7, 8, 9, 10, 11, 12, 13, 14
DE	17	0	49,999,999	1, 2, 3, 6, 7, 8, 10, 11, 12, 13
FL	61	0	499,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 14
GA	81	0	99,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
GU	7	100	9,999,999	2, 3, 4, 7, 9, 12
HI	20	100	9,999,999	1, 2, 3, 4, 5, 6, 7, 9, 10, 12, 13, 14
IA	53	0	9,999,999	1, 2, 3, 6, 7, 8, 9, 10, 11, 12, 13
ID	4	1,000	999,999	1, 5, 7, 9, 11, 12
IL	149	0	499,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
IN	131	0	49,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
KS	90	0	499,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
KY	90	0	49,999,999	1, 2, 3, 4, 5, 7, 8, 9, 10, 11, 12, 13, 14
LA	223	0	999,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
MA	42	100	99,999,999	1, 2, 4, 5, 7, 8, 9, 10, 11, 12, 14
MD	52	100	9,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
ME	15	100	49,999,999	2, 3, 4, 7, 9, 10, 11, 12
MI	178	0	499,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
MN	79	0	99,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
MO	92	0	9,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13
MP	7	0	999,999	2, 3, 4, 7, 9
MS	72	0	49,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
MT	19	10,000	9,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 12, 13, 14
NC	67	0	49,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
ND	11	1,000	9,999,999	1, 2, 3, 4, 6, 7, 9, 10, 12
NE	22	0	9,999,999	1, 2, 3, 7, 8, 10, 11, 12
NH	15	0	999,999	2, 7, 9, 10, 11, 12, 13
NJ	101	0	499,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
NM	29	1,000	9,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 12, 13
NV	13	100	999,999	1, 2, 4, 7, 8, 9, 11, 12
NY	81	0	49,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
OH	168	0	499,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14

## 5. PRODUCTION, IMPORT/EXPORT, USE, AND DISPOSAL

**Table 5-2. Facilities that Produce, Process, or Use Ethylbenzene**

State <sup>a</sup>	Number of facilities	Minimum amount on site in pounds <sup>b</sup>	Maximum amount on site in pounds <sup>b</sup>	Activities and uses <sup>c</sup>
OK	57	100	99,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
OR	35	0	9,999,999	1, 2, 3, 4, 5, 7, 8, 9, 10, 11, 12, 13
PA	136	0	49,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
PR	57	100	10,000,000,000	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13
SC	52	0	9,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
SD	8	100	99,999	7, 10, 11
TN	78	0	49,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
TX	393	0	10,000,000,000	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
UT	45	100	9,999,999	1, 2, 3, 4, 6, 7, 8, 9, 10, 11, 12, 13
VA	66	0	49,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13
VI	8	10,000	49,999,999	1, 2, 3, 4, 6, 7, 8, 9
VT	5	0	999,999	7, 11
WA	66	0	499,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
WI	72	0	9,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14
WV	58	0	9,999,999	1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13
WY	35	1,000	9,999,999	1, 2, 3, 4, 5, 6, 7, 9, 10, 11, 12, 13, 14

<sup>a</sup>Post office state abbreviations used

<sup>b</sup>Amounts on site reported by facilities in each state

<sup>c</sup>Activities/Uses:

- |                          |                          |                             |
|--------------------------|--------------------------|-----------------------------|
| 1. Produce               | 6. Impurity              | 11. Chemical Processing Aid |
| 2. Import                | 7. Reactant              | 12. Manufacturing Aid       |
| 3. Onsite use/processing | 8. Formulation Component | 13. Ancillary/Other Uses    |
| 4. Sale/Distribution     | 9. Article Component     | 14. Process Impurity        |
| 5. Byproduct             | 10. Repackaging          |                             |

Source: TRI05 2007 (Data are from 2005)

## 5. PRODUCTION, IMPORT/EXPORT, USE, AND DISPOSAL

**Table 5-3. Manufacturers and Annual Production Capacity of Ethylbenzene**

Manufacturer	Plant location	Annual capacity (millions of pounds)
Chevron Phillips Chemical Company	St. James, Louisiana	2,083
	Pascagoula, Mississippi	289
Cos-Mar Company	Carville, Louisiana	2,822
The Dow Chemical Company	Freeport, Texas	1,896
INEOS America	Texas City, Texas	1,124
Lyondell Chemical Company	Channelview, Texas	3,245
NOVA Chemical Corporation	Bayport, Texas	1,940
Sterling Chemicals Incorporated	Texas City, Texas	1,920
Westlake Styrene Corporation	Sulphur, Louisiana	450
<b>Total capacity</b>		<b>15,769</b>

Source: SRI 2006

## 5. PRODUCTION, IMPORT/EXPORT, USE, AND DISPOSAL

relatively small as compared to annual production, typically representing  $\leq 1\%$  of the annual domestic production volume.

U.S. exports for 2002 and 2003 were reported as  $1.86 \times 10^7$  kg (41 million pounds) and  $1.50 \times 10^7$  kg (33 million pounds), respectively (CMR 2004). Export volumes for ethylbenzene have been relatively small typically representing  $\leq 1\%$  of the annual domestic production volume.

### 5.3 USE

Ethylbenzene is used primarily as a precursor in the production of styrene (ACGIH 2002; Ransley 1984; Verschueren 1983). It is estimated that  $>99\%$  of the ethylbenzene manufactured in the United States is ultimately used in styrene production, while the remainder is exported or sold in solvent applications (CMR 2004; HSDB 2007). Minor uses of ethylbenzene include use as a solvent, as a constituent of asphalt and of naphtha, and in fuels (ACGIH 2002; Verschueren 1983). Ethylbenzene is also used in the manufacture of acetophenone, cellulose acetate, diethylbenzene, ethyl anthraquinone, ethylbenzene sulfonic acids, propylene oxide, and  $\alpha$ -methylbenzyl alcohol (HSDB 2007; Verschueren 1983).

### 5.4 DISPOSAL

Regulations governing the treatment and disposal of wastes containing ethylbenzene are detailed in Chapter 8. Recommended methods for the disposal of ethylbenzene include burial in a landfill and rotary kiln incineration, liquid injection incineration, and fluidized bed incineration (EPA 1981d; HSDB 2007). Ethylbenzene may be disposed of by adsorbing it in vermiculite, dry sand, earth, or a similar material and then by burial in a secured sanitary landfill or by atomizing in a suitable combustion chamber (IRPTC 1985). Ethylbenzene is a good candidate for liquid injection incineration at a temperature range of 650–1,600 °C and a residence time of 0.1–2 seconds; a candidate for rotary kiln incineration at a temperature range of 820–1,600 °C and a residence time of seconds for gases and liquids and hours for solids; and a good candidate for fluidized bed incineration at a temperature range of 450–980 °C and a residence time of seconds for gases and liquids, and longer for solids (HSDB 2007).

The following waste water treatment technologies have been investigated for disposal of ethylbenzene; biological treatment, air and steam stripping, or activated carbon treatment (HSDB 2007). Spent ethylbenzene solvents and still bottoms from the recovery of these solvents are designated hazardous wastes



## 5. PRODUCTION, IMPORT/EXPORT, USE, AND DISPOSAL

and, as such, are subject to the Resource Conservation and Recovery Act (RCRA) of 1976 handling and record-keeping requirements (EPA 1992c).

According to the TRI, in 2005, an estimated 177,331 pounds (80,436 kg) were transferred off-site, which includes releases to publicly owned treatment works (POTWs) (TRI05 2007). No additional information was located on the trends in disposal methods related to ethylbenzene.

5. PRODUCTION, IMPORT/EXPORT, USE, AND DISPOSAL

This page is intentionally blank.

## 6. POTENTIAL FOR HUMAN EXPOSURE

### 6.1 OVERVIEW

Ethylbenzene has been identified in at least 829 of the 1,689 hazardous waste sites that have been proposed for inclusion on the EPA National Priorities List (NPL) (HazDat 2007). However, the number of sites evaluated for ethylbenzene is not known. The frequency of these sites can be seen in Figure 6-1. Of these sites, 825 are located within the United States, 2 are located in the Commonwealth of Puerto Rico, and 2 are located in the Virgin Islands (not shown).


Ethylbenzene is an aromatic hydrocarbon naturally present in crude petroleum. It is also a combustion byproduct of biomass. It is widely distributed in the environment because of human activities such as the use of fuels and solvents (which account for the bulk of emissions) and through chemical manufacturing and production activities. Because of its volatile nature, ethylbenzene tends to partition to the atmosphere when it is released to the environment; therefore, exposure to this chemical is most likely to occur by inhalation. However, it is also present in trace amounts in some water supplies and food items. Thus, ingestion also may be an important exposure pathway in some cases. Exposures from contaminated water may also occur via inhalation and dermal absorption during showering and other household activities (Beavers et al. 1996).

Physical, chemical, and biological processes can remove ethylbenzene from the medium of concern and reduce human exposures. In the atmosphere, ethylbenzene exists primarily in the vapor phase. Vapor phase ethylbenzene is removed from air by reacting with photochemically produced hydroxyl radicals, with an approximate half-life of 2 days. Photolytic transformations may also take place in surface water in the presence of naturally occurring humic materials (sensitized photolysis). Biologically induced transformations take place largely in soil and surface water in the presence of oxygen; however, anaerobic degradation can also occur in soil, sediment, and groundwater, but at a much slower rate than aerobic biodegradation. Although chemical transformations can result in reduced exposures to ethylbenzene in the atmosphere, one toxic by-product of ethylbenzene photodegradation, peroxyacetylnitrate (PAN), may be of concern. Ethylbenzene, as well as a variety of other hydrocarbons, has been implicated in the atmospheric formation of PAN in smog (Yanagihara et al. 1977).

The kinetics of partitioning and/or transformation processes are site-specific and depend upon many external factors. For example, the extent of biodegradation observed in an environmental medium

6. POTENTIAL FOR HUMAN EXPOSURE

**Figure 6-1. Frequency of NPL Sites with Ethylbenzene Contamination**



## 6. POTENTIAL FOR HUMAN EXPOSURE

depends upon the type and population of microorganisms present, the concentration of ethylbenzene, the presence of other compounds that may act as a substrate, and the presence or absence of oxygen. Biodegradation in soil will also compete with transport processes such as volatilization and infiltration to groundwater. Because ethylbenzene migration is only moderately retarded by adsorption onto soil, leaching of the compound to an anaerobic environment (groundwater) before biotransformation in soil is possible and may allow ethylbenzene to persist in an aquifer.

Although information is limited on dietary exposures, ethylbenzene does not appear to significantly bioaccumulate in aquatic or terrestrial food chains, and human exposure through this route is not likely to be of concern.

Exposure of the general population to ethylbenzene is possible through contact with gasoline, automobile emissions, solvents, pesticides, printing ink, varnishes, coatings, and paints. Cigarette smoke also has been identified as a source of exposure to this chemical. Ethylbenzene is widely present at low concentrations in rural, suburban, and urban atmospheres with the highest concentrations generally detected in areas of gasoline stations, tunnels, highways, and parking lots. Ethylbenzene is also present in indoor air. Very often ethylbenzene levels in indoor air exceed the levels typically found in outdoor air. Occupational exposures are expected within the petroleum industry; within industries using solvents, paints, and coatings; and during the manufacture and handling of ethylbenzene and styrene (which is manufactured from ethylbenzene).

Several groups within the general population may have potentially higher exposures to ethylbenzene by inhalation, oral, or dermal contact with contaminated drinking water or soil. These groups include individuals living near manufacturing and processing facilities, petroleum refineries, and hazardous waste disposal sites. Exposures associated with the consumption of contaminated drinking water as well as with inhalation and dermal exposure during showering and bathing in contaminated water would be expected for individuals that derive their primary drinking water supply from residential wells downgradient of uncontrolled landfills, hazardous waste sites, and leaking underground storage tanks that are contaminated with ethylbenzene. Individuals living near these sites may also be exposed via dermal contact with, or ingestion of soil contaminated with ethylbenzene.

## 6. POTENTIAL FOR HUMAN EXPOSURE

**6.2 RELEASES TO THE ENVIRONMENT**

The Toxics Release Inventory (TRI) data should be used with caution because only certain types of facilities are required to report (EPA 2005). This is not an exhaustive list. Manufacturing and processing facilities are required to report information to the TRI only if they employ 10 or more full-time employees; if their facility is included in Standard Industrial Classification (SIC) Codes 10 (except 1011, 1081, and 1094), 12 (except 1241), 20–39, 4911 (limited to facilities that combust coal and/or oil for the purpose of generating electricity for distribution in commerce), 4931 (limited to facilities that combust coal and/or oil for the purpose of generating electricity for distribution in commerce), 4939 (limited to facilities that combust coal and/or oil for the purpose of generating electricity for distribution in commerce), 4953 (limited to facilities regulated under RCRA Subtitle C, 42 U.S.C. section 6921 et seq.), 5169, 5171, and 7389 (limited S.C. section 6921 et seq.), 5169, 5171, and 7389 (limited to facilities primarily engaged in solvents recovery services on a contract or fee basis); and if their facility produces, imports, or processes  $\geq 25,000$  pounds of any TRI chemical or otherwise uses  $>10,000$  pounds of a TRI chemical in a calendar year (EPA 2005).

**6.2.1 Air**

Estimated releases of 4,887,109 pounds (~2,217 metric tons) of ethylbenzene to the atmosphere from 1,508 domestic manufacturing and processing facilities in 2005, accounted for about 83% of the estimated total environmental releases from facilities required to report to the TRI (TRI05 2007). These releases are summarized in Table 6-1.

The majority of ethylbenzene releases to the environment occur to the atmosphere. Because of its frequent use, and production in manufacturing operations, ethylbenzene is an important industrial chemical. Ethylbenzene is consistently ranked among the top 50 chemicals produced in the United States, with total production ranging from approximately 11 to 13 billion pounds annually (C&EN 1995, 2006; Kirschner 1995). In 2005, 11.6 billion pounds of ethylbenzene were produced by U.S. manufacturers (C&EN 2006). Its release can occur during manufacturing, processing, and handling. In 1978, emissions of ethylbenzene in the United States from catalytic reformat production alone were estimated at over 2 million pounds (Fishbein 1985). Fuels and solvents, however, are considered to account for the bulk of emissions (Fishbein 1985). Ethylbenzene has been measured from tail pipe emissions of gasoline-powered vehicles at a weighted average rate of 12 mg/km (considering both catalyst and noncatalyst equipped cars) (Hampton et al. 1983). Exposures to ethylbenzene can also occur while individuals are

## 6. POTENTIAL FOR HUMAN EXPOSURE

**Table 6-1. Releases to the Environment from Facilities that Produce, Process, or Use Ethylbenzene<sup>a</sup>**

State <sup>c</sup>	RF <sup>d</sup>	Reported amounts released in pounds per year <sup>b</sup>							
		Air <sup>e</sup>	Water <sup>f</sup>	UI <sup>g</sup>	Land <sup>h</sup>	Other <sup>i</sup>	Total release		
							On-site <sup>j</sup>	Off-site <sup>k</sup>	On- and off-site
AK	10	6,087	16	0	119	7	6,222	7	6,229
AL	33	255,783	735	0	225	333	256,523	553	257,076
AR	13	27,082	1	0	27	0	27,083	27	27,110
AZ	15	37,016	17	0	5	250	37,038	250	37,288
CA	95	70,285	41	20	9,996	2,179	79,382	3,139	82,521
CO	11	3,821	0	0	255	0	3,821	255	4,076
CT	11	3,902	1	0	0	0	3,903	0	3,903
DE	4	5,326	1,200	0	38	0	6,526	38	6,564
FL	35	85,985	10	0	0	227	85,995	227	86,222
GA	33	138,453	3	0	282	2,591	138,456	2,873	141,329
GU	2	2,528	1	0	0	164	2,529	164	2,693
HI	8	2,193	50	0	420	16	2,248	431	2,679
IA	22	50,060	0	0	0	0	50,060	0	50,060
ID	3	1,234	No data	0	14	49,480	1,246	49,482	50,728
IL	71	198,784	439	0	17,644	6,922	199,369	24,420	223,789
IN	73	302,906	561	0	45	562	303,477	597	304,074
KS	26	140,531	23	50	1,075	5	140,855	829	141,684
KY	39	172,670	30	0	17,524	9	172,701	17,532	190,234
LA	71	277,504	797	0	1,465	8	278,347	1,427	279,774
MA	17	8,392	32	0	53	5,647	8,468	5,655	14,124
MD	22	23,765	6	0	2	21	23,771	23	23,794
ME	4	1,110	10	0	0	1,301	1,120	1,301	2,421
MI	72	477,436	6	2	19,915	839	477,441	20,756	498,197
MN	24	68,457	13	0	70	16	68,470	86	68,556
MO	47	262,200	1	0	251	335	262,201	586	262,787
MP	2	165	0	0	0	1	165	1	166
MS	24	165,820	39	0	288	0	165,859	288	166,147
MT	6	5,177	1	0	55	0	5,182	52	5,234
NC	28	70,213	0	0	63	321	70,220	378	70,598
ND	2	3,800	1	0	0	2	3,801	2	3,803
NE	6	3,784	No data	0	3,253	0	3,830	3,207	7,037
NH	3	253	No data	0	0	0	253	0	253
NJ	42	38,157	255	0	1,701	131	39,737	507	40,244
NM	10	11,878	5	5	14	1,843	11,895	1,850	13,745
NV	4	733	No data	0	0	0	733	0	733
NY	53	44,128	257	0	2,560	3,126	45,664	4,407	50,071

## 6. POTENTIAL FOR HUMAN EXPOSURE

**Table 6-1. Releases to the Environment from Facilities that Produce, Process, or Use Ethylbenzene<sup>a</sup>**

State <sup>c</sup>	RF <sup>d</sup>	Reported amounts released in pounds per year <sup>b</sup>							
		Air <sup>e</sup>	Water <sup>f</sup>	UI <sup>g</sup>	Land <sup>h</sup>	Other <sup>i</sup>	Total release		
							On-site <sup>j</sup>	Off-site <sup>k</sup>	On- and off-site
OH	112	386,690	79	87	3,991	1,945	387,970	4,822	392,792
OK	19	64,380	27	18	659	705	64,939	850	65,789
OR	13	19,002	0	0	85	0	19,002	85	19,087
PA	74	153,444	111	0	1,660	2,528	153,555	4,187	157,742
PR	11	24,646	6	0	47	17	24,699	17	24,715
RI	2	576	4	0	0	1,228	580	1,228	1,808
SC	14	50,350	7	17	39	11,326	50,357	11,382	61,739
SD	4	32,447	No data	0	0	0	32,447	0	32,447
TN	36	340,519	23	0	760	250	340,542	1,010	341,552
TX	168	571,385	2,884	788,674	8,853	2,814	1,364,743	9,866	1,374,610
UT	12	3,955	750	0	18	22	4,710	35	4,745
VA	24	82,340	141	0	254	0	82,482	254	82,736
VI	3	10,738	0	0	10	0	10,738	10	10,748
VT	1	510	No data	0	0	0	510	0	510
WA	19	20,050	10	0	54	18	20,082	51	20,133
WI	34	69,451	5	0	826	453	69,456	1,278	70,735
WV	15	81,962	8	0	250	398	81,970	648	82,618
WY	6	7,046	0	0	505	0	7,296	255	7,551
<b>Total</b>	<b>1,508</b>	<b>4,887,109</b>	<b>8,606</b>	<b>788,874</b>	<b>95,372</b>	<b>98,040</b>	<b>5,700,669</b>	<b>177,331</b>	<b>5,878,000</b>

<sup>a</sup>The TRI data should be used with caution since only certain types of facilities are required to report. This is not an exhaustive list. Data are rounded to nearest whole number.

<sup>b</sup>Data in TRI are maximum amounts released by each facility.

<sup>c</sup>Post office state abbreviations are used.

<sup>d</sup>Number of reporting facilities.

<sup>e</sup>The sum of fugitive and point source releases are included in releases to air by a given facility.

<sup>f</sup>Surface water discharges, waste water treatment-(metals only), and publicly owned treatment works (POTWs) (metal and metal compounds).

<sup>g</sup>Class I wells, Class II-V wells, and underground injection.

<sup>h</sup>Resource Conservation and Recovery Act (RCRA) subtitle C landfills; other on-site landfills, land treatment, surface impoundments, other land disposal, other landfills.

<sup>i</sup>Storage only, solidification/stabilization (metals only), other off-site management, transfers to waste broker for disposal, unknown

<sup>j</sup>The sum of all releases of the chemical to air, land, water, and underground injection wells.

<sup>k</sup>Total amount of chemical transferred off-site, including to POTWs.

RF = reporting facilities; UI = underground injection

Source: TRI05 2007 (Data are from 2005)



## 6. POTENTIAL FOR HUMAN EXPOSURE

traveling in the passenger compartment of automobiles, and the chemical has been found at much higher concentrations during automobile engine malfunctions (Lawryk and Weisel 1996; Lawryk et al. 1995).

Emissions from gasoline-powered vehicles were found to be somewhat higher than from diesel trucks (Hampton et al. 1983). Similarly, ethylbenzene has been measured in jet fuel emissions (Katzman and Libby 1975) and has been reported in waste incinerator stack emissions (Jay and Steiglitz 1995; Junk and Ford 1980). Ethylbenzene has also been shown to be released into the atmosphere from volatile organic compound (VOC)-laden waste water in municipal sewer systems (Quigley and Corsi 1995).

Emissions of ethylbenzene can arise from transport of hot asphalt from a manufacturing plant to a paving site and from subsequent road paving operations. Kitto et al. (1997) measured the emissions of volatile organic compounds from Type I and Type II hot asphalts. At 150 °C, the concentration of the ethylbenzene emissions from Type I asphalt was 800 µg/m<sup>3</sup>; at 200 °C, the concentration was 2,200 µg/m<sup>3</sup>, an increase by a factor of 2.8. At 150 °C, the concentration of the ethylbenzene emissions from Type II asphalt was 7,000 µg/m<sup>3</sup>; at 200 °C, the concentration was 21,000 µg/m<sup>3</sup>, an increase by a factor of 3.

Mukund et al. (1996) conducted chemical mass balance source apportionment modeling on a data set of 142 3-hour integrated air samples collected at six different sites in three separate campaigns during the summer of 1989 in Columbus, Ohio. The contributions (± standard error) to the observed atmospheric levels of ethylbenzene from the sources considered, expressed as percentage of measured average concentration, were: 55±11 from vehicle exhaust; 0.7±0.2 from gasoline vapor; 0±3 from natural gas; 20±4 from industrial solvents; and 0±1 from the dry cleaning/degreasing/waste water composite source. These five sources contributed an estimated 76±12% of the measured average concentration of 1.1 µg/m<sup>3</sup>.

Ethylbenzene releases to the air especially in indoor environments can occur with the use of consumer products such as pesticides, liquid process photocopiers and plotters, solvents, carpet glue, paints, varnishes, automotive products, adhesives, and fabric and leather treatments that contain ethylbenzene (Hodgson et al. 1991; Lillo et al. 1990; NAS 1980; Otson et al. 1994; Sack et al. 1992; Wallace et al. 1987b). Ethylbenzene (in addition to other aromatic hydrocarbons, such as benzene, styrene, and xylenes) has also been measured in cigarette smoke (Barrefors and Petersson 1993; Wallace et al. 1986, 1987c). An analysis of indoor air in a home using gasoline-contaminated tap water found that exposures to ethylbenzene could occur via inhalation during showering and other household activities (Beavers et al. 1996). Ethylbenzene concentrations in the shower area were often one to two orders of magnitude higher than in other areas of the home.

## 6. POTENTIAL FOR HUMAN EXPOSURE

Ethylbenzene has been identified in air samples collected at 121 of the 829 NPL hazardous waste sites respectively, where it was detected in some environmental media (HazDat 2007).

**6.2.2 Water**

Estimated releases of 8,606 pounds (~3.9 metric tons) of ethylbenzene to surface water from 1,508 domestic manufacturing and processing facilities in 2005, accounted for <1% of the estimated total environmental releases from facilities required to report to the TRI (TRI05 2007). An additional 177,331 pounds (80.4 metric tons) were transferred off-site or released to publicly owned treatment works (POTWs) (TRI05 2007). These releases are summarized in Table 6-1.

Releases to water can occur as a result of industrial discharges (Snider and Manning 1982), fuel spillage (Gschwend et al. 1982; Tester and Harker 1981), leaking petroleum pipelines or underground storage tanks (Cotruvo 1985), landfill leachate (Barker 1987; Beavers et al. 1996; Chen and Zoltek 1995; Hallbourg et al. 1992), and the inappropriate disposal of wastes containing ethylbenzene (Eiceman et al. 1986). Ethylbenzene emissions to oceans occur as a result of offshore oil production, hydrocarbon venting, oil field brines, and tanker oil spills (Sauer et al. 1978). Sauer and Tyler (1995) reported that ethylbenzene was one of the most commonly detected VOCs in motor vehicle waste fluids released from routine vehicle maintenance shops entering catch basins and septic tanks in Wisconsin. Ethylbenzene was detected at a mean concentration of 11 ppb (range 3–98 ppb) in catch basin waste water, 1.5 ppb (range 7–23 ppb) in septic tank effluent, and 8 ppb (range 9–53 ppb) in septic tank sludge.

Ethylbenzene has been identified in surface water at 123 sites and groundwater collected at 557 of the 829 NPL hazardous waste sites respectively, where it was detected in some environmental media (HazDat 2007).

**6.2.3 Soil**

Estimated releases of 95,372 pounds (~43.3 metric tons) of ethylbenzene to soils from 1,508 domestic manufacturing and processing facilities in 2005, accounted for about 2% of the estimated total environmental releases from facilities required to report to the TRI (TRI05 2007). An additional 788,874 pounds (~357.8 metric tons), constituting about 13% of the total environmental emissions, were released via underground injection (TRI05 2007). These releases are summarized in Table 6-1.

## 6. POTENTIAL FOR HUMAN EXPOSURE

Ethylbenzene can be released to soils through the spilling of gasoline and other fuels (Sauer and Tyler 1995; Tester and Harker 1981); through the disposal of solvents and household products such as paint, cleaning and degreasing solvents, varnishes, and pesticides; through emissions from leaking underground storage tanks (Cotruvo 1985); and leaching from landfill sites (Barker 1987).

Ethylbenzene has been identified in soil and sediment samples collected at 469 and 144 of the 829 NPL hazardous waste sites respectively, where it was detected in some environmental media (HazDat 2007).

### 6.3 ENVIRONMENTAL FATE

#### 6.3.1 Transport and Partitioning

The large vapor pressure and Henry's law constant of ethylbenzene (Table 4-2) suggests a moderate to strong tendency for ethylbenzene to partition into the atmosphere where it will exist predominantly in the vapor phase (Eisenreich et al. 1981; Mackay 1979; Masten et al. 1994). Depending upon site-specific conditions, releases to surface soil can result in substantial losses to the atmosphere in addition to subsurface infiltration. Since it has a moderately high vapor pressure, ethylbenzene will evaporate fairly rapidly from dry soil. Vapor phase transport will occur from subsurface releases (i.e., from leaking underground storage tanks) and during migration through unsaturated soil pore spaces (Rhue et al. 1988). Atmospheric reaction with hydroxyl radicals can limit the atmospheric transport of ethylbenzene (Dewulf and van Langenhove 1997).

The large Henry's law constant (Table 4-2), which measures partitioning between water and air, indicates that a significant proportion of ethylbenzene will partition from water into air (Mackay 1979; Masten et al. 1994). Ethylbenzene dissolved in surface water, soil pore water, or groundwater will thus migrate into an available atmospheric compartment until its saturated vapor concentration is reached. The volatilization half-life of ethylbenzene in a constructed wetland (length=228 m, width=60 m, depth=0.5–1.5 m) located in Phoenix, Arizona ranged from approximately 40 to 200 hours (Keefe et al. 2004).

Based on log  $K_{oc}$  values in the range of 2.2–2.4 (Table 4-2) and using the classification scheme of Swann et al. (1983), ethylbenzene is classified as having moderate mobility in soils. Sorption and retardation by soil organic carbon content will occur to a moderate extent, but sorption is not significant enough to completely prevent migration in most soils. Particularly in soils with low organic carbon content,

## 6. POTENTIAL FOR HUMAN EXPOSURE

ethylbenzene will tend to leach into groundwater. Mobility is also possible in aquifers that contain very little solid-phase organic matter, a condition common to sand and gravel aquifers (Ptacek et al. 1984). Sorption and desorption experiments performed by Dewulf et al. (1996) demonstrated that the sorption process of ethylbenzene on marine sediments is reversible and that the sorption is even lower than expected from the log  $K_{ow}$  data and the organic carbon content of the sediment. They concluded that the marine sediment compartment is not an important sink for the VOCs investigated when they are released to water.

When ethylbenzene is part of a complex mixture of hydrocarbons associated with a petroleum spill or leak, the proportion of ethylbenzene that will bind to soil versus the amount that will migrate toward groundwater depends primarily on the type of soil, the particular petroleum product in which the ethylbenzene is dissolved, the size of the spill, and the amount of rainfall (Stokman 1987). For example, the solubility of ethylbenzene varies in accordance with the presence of other petroleum products (Ptacek et al. 1984). While the pure compound solubility of ethylbenzene in water is 180 mg/L, its solubility in water equilibrated with JP-jet fuel is 10.6 mg/L (Burris and MacIntyre 1984). Potter (1993) also reported that the equilibrium aqueous solubility of ethylbenzene was 2.4 mg/L with gasoline, 0.18 mg/L with diesel fuel, and 0.007 mg/L with #6 fuel oil equilibrated with groundwater. Both of these authors calculated the solubility concentrations of ethylbenzene in water equilibrated with various petroleum products. In addition, solvent spills of chemicals such as ethylbenzene may enhance the mobility of other organic chemicals, which do strongly adsorb to soil (Rao et al. 1985). No information was found concerning bioavailability of ethylbenzene from soil for human dermal or oral uptake.

Boyd et al. (1990) reported that corn residues high in organic matter that were left on the surface of a no tillage field, adsorbed a significantly greater amount of ethylbenzene as compared with surface soil. The authors suggested that the highly lipophilic plant cuticle appears to be the sorptive component. Kango and Quinn (1989) also reported that humic acid adsorbed higher amounts of ethylbenzene and xylenes ranging from 40 to 77 times greater than soil.

Once in the atmosphere, ethylbenzene will be transported until it is removed by physical or chemical processes. Physical removal processes, which involve partitioning into clouds or rainwater, are relevant to ethylbenzene, which has been measured in Los Angeles rainwater (Kawamura and Kaplan 1983). The concentrations of several dissolved organic chemicals in rainwater and in the atmosphere during rainfall events were measured by Ligocki et al. (1985). The authors found that the concentration of ethylbenzene in rain water was approximately equal to the inverse of the dimensionless Henry's law constant

## 6. POTENTIAL FOR HUMAN EXPOSURE

(Table 4-2) at atmospheric temperatures. This indicates that ethylbenzene is removed from the atmosphere through precipitation, but it can re-enter the atmospheric environment upon evaporation.

In comparison to chemicals such as polychlorinated biphenyls (PCBs), DDT, and other chlorinated pesticides, which are of great concern with respect to bioaccumulation, ethylbenzene does not significantly bioaccumulate in aquatic food chains. A measured bioconcentration factor (BCF) of 15 was reported for ethylbenzene in goldfish (Ogata et al. 1984). A BCF value of 53 was estimated in fish, using a log  $K_{ow}$  of 3.15 and a regression derived equation (Meylan et al. 1999). A 3% weighted average lipid content in fish and shellfish was assumed by EPA in the calculation. The calculated BCF is a theoretical value based on known constants, and is a conservative estimate of the bioconcentration of this chemical in fish. A calculated BCF of 167 was also estimated for fathead minnows (*Pimephales promelas*) (ASTER 1995). In a shellfish study, the ethylbenzene concentration in clam tissue was 5 times higher than that measured in water after an 8-day continuous-flow exposure to the water-soluble fraction of Cook Inlet crude oil (Nunes and Benville 1979).

Ethylbenzene has also been found to partition into human tissues; primarily as a result of inhalation exposures (see Section 6.5). Ethylbenzene has been detected in human adipose tissue (Sections 3.4.2.1 and 3.8.1), blood (Section 3.4.1.1), and in breast milk (Section 3.7). No information was located concerning the bioavailability of ethylbenzene from contaminated soil or sediment either with respect to dermal exposure or oral intake via consumption of soil particles from unwashed hands.

### 6.3.2 Transformation and Degradation

#### 6.3.2.1 Air

Ethylbenzene undergoes atmospheric transformations through reaction with photochemically generated hydroxyl radicals (Atkinson et al. 1978; Ohta and Ohya 1985; Ravishankara et al. 1978),  $\text{NO}_3$  radicals (Atkinson et al. 1987), and atomic oxygen (Grovenstein and Mosher 1970; Herron and Huie 1973). Gas phase reactions with ozone and structurally similar molecules such as toluene have been observed (Atkinson and Carter 1984). The predominant degradation pathway for ethylbenzene in the atmosphere occurs via reaction with hydroxyl radicals and nitrate radicals (which are only present during non daylight hours), with the other degradation mechanisms being of only minor importance. The rate constant for the vapor phase reaction of ethylbenzene with photochemically generated hydroxyl radicals was measured as  $7.1 \times 10^{-12} \text{ cm}^3$  per molecule-second (Kwok and Atkinson 1994). This corresponds to an atmospheric half-

## 6. POTENTIAL FOR HUMAN EXPOSURE

life of approximately 2 days using a hydroxyl radical concentration of  $5 \times 10^5$  hydroxyl radicals per  $\text{cm}^3$ . The rate constant for the degradation of ethylbenzene with nitrate radicals was measured as  $6 \times 10^{-16} \text{ cm}^3$  per molecule-second (Atkinson et al. 1987). Using a nighttime nitrate radical concentration of  $5 \times 10^8$  nitrate radicals per  $\text{cm}^3$ , a half-life of approximately 26 days is estimated. Atmospheric degradation occurs more rapidly during summer months as opposed to winter since the concentration of hydroxyl radicals in the atmosphere peaks during summer (Ravishankara et al. 1978; Singh et al. 1981), and is also faster under photochemical smog conditions (Dilling et al. 1976). Oxidation by-products from the reaction with hydroxyl radicals and nitrogen oxides include ethylphenols, benzaldehyde, acetophenone, and *m*- and *p*-nitroethylbenzene (Hoshino et al. 1978). The major degradation pathways for ethylbenzene in the atmosphere are summarized in Figure 6-2.


Experiments conducted with various hydrocarbons on the formation of photochemical aerosols or the haze associated with smog revealed that aromatics such as ethylbenzene produced only low yields of aerosol when compared with more reactive compounds such as alkenes (O'Brien et al. 1975). The formation of PAN is related to the photoreactivity of the reacting hydrocarbon. The photoreactivity of ethylbenzene is intermediate relative to other atmospheric hydrocarbons, and it is less reactive than gasoline, toluene, and alkenes such as propene (Yanagihara et al. 1977).

### 6.3.2.2 Water

In surface water, transformations of ethylbenzene may occur through two primary processes—photooxidation and biodegradation. Since ethylbenzene does not contain hydrolysable functional groups at environmental pH (pH 5–9), hydrolysis is not considered an important environmental fate process. Although ethylbenzene does not absorb light in the environmental ultraviolet spectrum, it is capable of undergoing photooxidation in water through an indirect reaction with other light-absorbing molecules, a process known as sensitized photolysis. The compounds 1-methylphenyl ketone (acetophenone), 1-phenylethanol, and benzaldehyde were identified as degradation products from the laboratory photooxidation of ethylbenzene in both distilled water and seawater with anthraquinone used as a sensitizer (Ehrhardt and Petrick 1984). In the environment, similar degradation is expected to occur in the presence of ubiquitous, naturally occurring humic material sensitizers. The major degradation pathways for ethylbenzene in water are summarized in Figure 6-3.


Biodegradation in aerobic surface water will compete with sensitized photolysis and transport processes such as volatilization. Volatilization and biodegradation of ethylbenzene in seawater have been observed

## 6. POTENTIAL FOR HUMAN EXPOSURE

**Figure 6-2. Major Degradation Pathways for Ethylbenzene in the Atmosphere**

Source: Hoshino et al. 1978

## 6. POTENTIAL FOR HUMAN EXPOSURE

**Figure 6-3. Major Degradation Pathways for Ethylbenzene in Water, Sediment, and Soil**

Source: Burbach and Perry 1993; Ehrhardt and Petrick 1984; Van der Linden and Thijsse 1965



## 6. POTENTIAL FOR HUMAN EXPOSURE

by Gschwend et al. (1982), Masten et al. (1994), and Wakeham et al. (1983). Migration from surface water to subsurface soil with low amounts of oxygen or to aquifers with lower microbial populations, however, will limit the rate of transformation. No significant disappearance of ethylbenzene during 11 weeks of incubation with bacteria under low oxygen (anoxic) conditions was observed by Bouwer and McCarty (1983). Slow degradation of ethylbenzene was reported in anaerobic aquifer materials known to support methanogenesis, although a long acclimation period or lag time was required (Wilson et al. 1986). Less than 1% of the initial concentration of ethylbenzene remained after 120 weeks, indicating that, given sufficient time, ethylbenzene will be essentially completely biodegraded.

Laboratory microcosm tests were conducted to determine optimum conditions for ethylbenzene biodegradation by aquifer microorganisms under denitrifying condition (Hutchins 1991). Ethylbenzene was degraded to <5 µg/L when present as a sole source substrate and stoichiometric calculations indicated that nitrate removal was sufficient to account for 70–80% of the compound being mineralized. Biodegradation did not occur without the presence of nitrate, and nitrate removal was minimal without the presence of the ethylbenzene over a 55-day incubation period. In a laboratory microcosm containing aquifer material and groundwater from the North Bay site in Ontario, Canada, no significant loss of ethylbenzene was observed compared to unamended controls over a period of 187 days. In another experiment conducted at the North Bay site that used *in situ* biodegradation columns, ethylbenzene was completely degraded in at least 1 of the 8 *in situ* columns in <100 days (Acton and Barker 1992). In all cases, the authors attributed the ethylbenzene attenuation to biodegradation by methanogenic and fermentative bacteria. In another study using a laboratory scale flow-through aquifer column system, low dissolved oxygen (<1 mg/L) conditions were initiated with the nitrate-amended column influent in order to mimic contaminated groundwater conditions distal from a nutrient injection well (Anid et al. 1993). The authors reported that 40% of the ethylbenzene was removed after several months of operation. In a similar study, using batch incubations seeded with four different aquifer materials, ethylbenzene was not degraded within 4 months in any of the denitrifying enrichments tested, even though nitrate reduction occurred. Burback and Perry (1993) reported that *Mycobacterium vaccae* can catabolize a number of major groundwater pollutants, including ethylbenzene. At a concentration of 100 ppm, ethylbenzene was not measurably degraded; however, at 50 ppm, 80% of the added ethylbenzene was degraded. A product peak of 4-ethylphenol was detected as well as a small amount of 1-phenylethanol.

The contrast between biodegradation rates in the presence or absence of oxygen was demonstrated by a biofilm reactor study designed to simulate an aquifer (Bouwer and McCarty 1984). Continuous-flow laboratory column studies under aerobic and methanogenic conditions were performed with mixed

## 6. POTENTIAL FOR HUMAN EXPOSURE

bacterial cultures on glass beads. In the aerobic biofilm column, 99% of the ethylbenzene initially present was degraded within a 20-minute detention time, while under methanogenic (anaerobic) conditions, only 7% was degraded within a 2-day detention time.

### 6.3.2.3 Sediment and Soil

Biodegradation of ethylbenzene by aerobic soil microbes has been reported by various researchers. The common soil microorganism *Pseudomonas putida* is able to utilize ethylbenzene as a sole source of carbon and energy (Fukuda et al. 1989; Gibson et al. 1973). In some instances, co-oxidation or co-metabolism was observed (i.e., ethylbenzene was degraded by *Nocardia sp.* in the presence of other compounds that are more readily metabolized by the microorganism) (Jamison et al. 1970; Van der Linden and Thijsse 1965). Yadav and Reddy (1993) reported that the white-rot fungus *Phanerochaete chrysosporium* efficiently degraded ethylbenzene as well as other benzene, toluene, ethylbenzene, and xylenes (BTEX) compounds when these chemicals were added either individually or as a composite mixture. In addition, substantially greater degradation of all the BTEX compounds was observed in static rather than in shaken liquid cultures. Furthermore, degradation was greater at 25 °C than at 37 °C, but pH variations between 4.5 and 7 had little effect on the extent of the degradation. Chen and Taylor (1995) reported that two thermophilic bacterial strains, *Thermus aquaticus* and an unidentified *Thermus sp.* degraded ethylbenzene (in a mixture with other BTEX chemicals) by 18% after 45 days of incubation at 70 °C and by 32% after 45 days of incubation at 60 °C, respectively. Zappi et al. (1996) reported that ethylbenzene degraded rapidly in a pilot scale bioslurry reactor under aerobic conditions. The initial concentration (0.35 mg/kg) was degraded by 94% in 2 days.

Biotic transformations by aerobic soil microbes involve oxidation of the ethyl side chain to form phenylacetic acid (Van der Linden and Thijsse 1965) and 1-phenylethanol (Bestetti and Galli 1984); ring hydroxylation to form 2,3-dihydroxy-1-ethylbenzene (Gibson et al. 1973), 2-hydroxyphenylacetic acid, 4-hydroxyphenylacetic acid, and 2,5- and 3,4-dihydroxyphenylacetic acid (Van der Linden and Thijsse 1965); and ultimate ring cleavage to form straight chain carboxylic acids such as fumaric and acetoacetic acids (Van der Linden and Thijsse 1965). The major degradation pathways for ethylbenzene are summarized in Figure 6-3.

Anaerobic degradation of ethylbenzene based on observations from studies conducted under anaerobic conditions in other media and as discussed above (Bouwer and McCarty 1983, 1984; Wilson et al. 1986), would be much slower than that observed under aerobic conditions. Ramanand et al. (1995) studied the

## 6. POTENTIAL FOR HUMAN EXPOSURE

biodegradation of several organic pollutants including ethylbenzene in soil columns under denitrifying conditions. These authors reported that one of the significant factors governing biodegradation is the availability of suitable electron acceptors. The biodegradation of ethylbenzene, toluene, and xylenes has been demonstrated in laboratory samples obtained from subsurface habitats or in pure cultures under denitrifying conditions (Hutchins 1991; Hutchins et al. 1991). Ramanand et al. (1995) reported that soil column bacteria, after sufficient acclimation time, metabolized 100–500  $\mu\text{M}$  of toluene and ethylbenzene in <6 days under denitrifying conditions. These compounds were successfully degraded under anoxic conditions by the addition of nitrate and by stimulating the indigenous soil denitrifying bacteria.

The kinetics of biodegradation appear to be site specific, and depend upon factors such as the type and population of microbes present, the environmental temperature, the concentration of ethylbenzene, the presence of other compounds that may act as a substrate, and the amount of oxygen and electron acceptors present. Biodegradation in soil will also compete with migration processes such as volatilization and infiltration to groundwater.

### 6.4 LEVELS MONITORED OR ESTIMATED IN THE ENVIRONMENT

Reliable evaluation of the potential for human exposure to ethylbenzene depends in part on the reliability of supporting analytical data from environmental samples and biological specimens. Concentrations of ethylbenzene in unpolluted atmospheres and in pristine surface waters are often so low as to be near the limits of current analytical methods. In reviewing data on ethylbenzene levels monitored or estimated in the environment, it should also be noted that the amount of chemical identified analytically is not necessarily equivalent to the amount that is bioavailable. The analytical methods available for monitoring ethylbenzene in a variety of environmental media are detailed in Chapter 7.

#### 6.4.1 Air

Ambient air levels of volatile organic compounds, including ethylbenzene, were monitored as a part of a multi-media study known as the Lower Rio Grande Valley Environmental Scoping Study. Monitoring was performed at a “central” site and at a “border” site in the Brownsville, Texas, air shed in the spring and summer of 1993. The median ambient concentration of ethylbenzene at the central site was  $0.80 \mu\text{g}/\text{m}^3$  (0.18 ppbv) ( $n=22$ ; range= $0.20$ – $1.7 \mu\text{g}/\text{m}^3$  [ $0.046$ – $0.39$  ppbv]) in the spring and  $0.4 \mu\text{g}/\text{m}^3$  (0.09 ppb) ( $n=14$ ; range= $0.2$ – $1.0 \mu\text{g}/\text{m}^3$  [ $0.04$ – $0.2$  ppbv]) in the summer. These concentrations are either lower or comparable to those found in previous EPA and other monitoring investigations (Ellenson et al.

## 6. POTENTIAL FOR HUMAN EXPOSURE

1997). The median indoor concentration of ethylbenzene for nine Rio Grande Valley residences measured in the spring was  $1.00 \mu\text{g}/\text{m}^3$  (0.230 ppbv) compared to a median outdoor concentration of  $0.70 \mu\text{g}/\text{m}^3$  (0.16 ppbv); in the summer, the median indoor concentration of ethylbenzene for five residences was  $1.40 \mu\text{g}/\text{m}^3$  (0.321 ppbv) compared to a median outdoor concentration of  $0.35 \mu\text{g}/\text{m}^3$  (0.080 ppbv) (Mukerjee et al. 1997). The mean indoor concentration of ethylbenzene at the homes of 46 high school students residing in New York City was  $3.57 \mu\text{g}/\text{m}^3$  (0.821 ppbv) in the winter months as compared to a mean indoor concentration of  $1.99 \mu\text{g}/\text{m}^3$  (0.458 ppbv) during the summer months (Kinney et al. 2002). The corresponding mean outdoor levels of ethylbenzene were 1.27 (0.292 ppbv) and  $1.88 \mu\text{g}/\text{m}^3$  (0.432 ppbv) in the winter and summer months, respectively.

An update of the 1980 National Ambient Volatile Organic Compounds (VOC) database prepared for EPA summarized concentrations of ethylbenzene by site type (EPA 1988c). Median values are reported because they are less biased by a few high or low concentrations and, thus, may better represent the data than would average values. The median indoor concentration of ethylbenzene detected at 95 locations was 1.0 ppbv ( $4.4 \mu\text{g}/\text{m}^3$ ) (mean 2.9 ppbv), while personal air monitoring of 1,650 individuals found a median concentration of 1.3 ppbv ( $5.6 \mu\text{g}/\text{m}^3$ ) (mean 3.2 ppbv).

Of particular interest is that personal air monitoring of indoor air found higher concentrations of ethylbenzene than those observed in outdoor air. This was also observed during the Total Exposure Assessment Methodology (TEAM) Study conducted by EPA between 1979 and 1985 in an effort to measure exposures to 20 VOCs in personal air, outdoor air, and drinking water. The major cause for the higher personal air concentrations was felt to be the presence of ethylbenzene sources in the home. In the TEAM study, tobacco smoke was reported to be a main source of exposure to volatile aromatic compounds such as ethylbenzene (Wallace et al. 1987a, 1987c). Based on the results of a stepwise regression carried out on data collected during the fall in New Jersey from 352 participants, overnight geometric mean ethylbenzene exposures of persons living in homes with smokers were approximately 1.5 times the geometric mean exposures of persons living in homes without smokers. The amount of ethylbenzene measured in mainstream smoke of a single cigarette containing 16 mg of tar and nicotine was  $8 \mu\text{g}$  (Wallace et al. 1987c). Wallace et al. (1989) reported that a maximum outdoor air concentration of ethylbenzene of  $7.4 \mu\text{g}/\text{m}^3$  (1.7 ppbv) was detected in nine outdoor samples collected at each of three houses while maximum indoor air concentrations at these same residences ranged from 5 to  $110 \mu\text{g}/\text{m}^3$  (1–25.3 ppbv). Mean personal exposures averaged  $28 \mu\text{g}/\text{m}^3$  (6.4 ppbv) (range  $4.6$ – $144 \mu\text{g}/\text{m}^3$  [1.0–33.1 ppbv]) and the personal/outdoor ratio for ethylbenzene was 16.

## 6. POTENTIAL FOR HUMAN EXPOSURE

The poor quality of indoor air has been linked to a number of symptoms (headache; nausea; irritation of the eyes, mucous membranes, and respiratory system; drowsiness; fatigue; and general malaise) which have been defined as "sick building" syndrome. Kostianen (1995) identified over 200 VOCs in the indoor air of 26 normal houses. Ethylbenzene was detected in 100% of the houses studied at an average concentration of  $3.2 \mu\text{g}/\text{m}^3$  [0.74 ppbv] (median  $2.41 \mu\text{g}/\text{m}^3$  [0.554 ppbv], minimum  $0.62 \mu\text{g}/\text{m}^3$  [0.14 ppbv], and maximum  $10.54 \mu\text{g}/\text{m}^3$  [2.42 ppbv] concentration). The median concentration of ethylbenzene ( $2.41 \mu\text{g}/\text{m}^3$  [0.554 ppbv]) in these normal houses was lower in all but one case than ethylbenzene concentrations detected in houses with "sick building" syndrome where the concentrations ranged from 2.25 to  $747.24 \mu\text{g}/\text{m}^3$  (0.517–172 ppbv).

A nationwide study of indoor air concentration of 26 VOCs was conducted in Canada in 1991 (Fellin and Otson 1994). These authors reported that mean indoor ethylbenzene concentrations were  $6.46 \mu\text{g}/\text{m}^3$  (1.48 ppbv),  $8.15 \mu\text{g}/\text{m}^3$  (1.87 ppbv),  $4.35 \mu\text{g}/\text{m}^3$  (1.00 ppbv), and  $13.98 \mu\text{g}/\text{m}^3$  (3.21 ppbv) in the winter, spring, summer and fall months, respectively and that the concentrations declined with an increase in ambient air temperature. At  $\leq 0$ , 0–15, and  $\geq 15$  °C, the mean ethylbenzene concentrations were  $12.76 \mu\text{g}/\text{m}^3$  (2.93 ppbv),  $7.78 \mu\text{g}/\text{m}^3$  (1.79 ppbv), and  $6.46 \mu\text{g}/\text{m}^3$  (1.48 ppbv), respectively. These authors concluded that indoor sources of ethylbenzene (primarily from household products) are likely to have a more significant influence on indoor air concentrations than climatic variables.

Concentrations of ethylbenzene were measured in soil gas, and indoor and outdoor air of a home located near a landfill in California (Hodgson et al. 1992). During the first sampling in September, ethylbenzene concentrations were not detected in soil gas or outdoor air, but were detected at 0.6 ppbv ( $3 \mu\text{g}/\text{m}^3$ ) in basement air. In October, ethylbenzene concentrations averaged 3.3 ppbv ( $14 \mu\text{g}/\text{m}^3$ ) in soil gas, 0.8 ppbv ( $4 \mu\text{g}/\text{m}^3$ ) in basement air, and 0.7 ppbv ( $3 \mu\text{g}/\text{m}^3$ ) in bedroom air. In this study, the authors found that the existence of soil gas contamination alone is not sufficient to result in significantly elevated indoor exposures. The entry rate of ethylbenzene and VOCs from the soil into the house was low. The limited entry that occurred at the conditions of the study was apparently the result of diffusive and advective flux of VOC through the cement blocks used in the basement wall construction. The authors suggest that there is a general need to identify variables associated with residential sites with the highest potential for significantly elevated indoor exposures resulting from soil gas contamination.

Indoor VOC concentrations were analyzed in 12 California office buildings as part of the California Healthy Building Study (Daisey et al. 1994). These authors reported that ethylbenzene was detected at a geometric mean of  $0.50 \mu\text{g}/\text{m}^3$  (0.11 ppbv) (range 0.27– $0.98 \mu\text{g}/\text{m}^3$  [0.062–0.22 ppbv]). These authors

## 6. POTENTIAL FOR HUMAN EXPOSURE

also reported that an estimated 82% of indoor air concentrations were contributed from motor vehicle emissions. Hodgson et al. (1991) reported that concentrations of ethylbenzene in indoor air of a new office building ranged from 7 to 18.7  $\mu\text{g}/\text{m}^3$  (2–4.30 ppbv) over the course of a 14-month sampling period. Furthermore, ethylbenzene indoor air concentrations were higher than those in outdoor air and that the dominant source of VOCs in the building was liquid-process photocopiers and plotters which emitted a characteristic mixture of C<sub>10</sub>–C<sub>11</sub> isoparaffinic hydrocarbons.

Wadden et al. (1995) reported average VOC concentrations for indoor air monitored in a sheetfed offset printing shop. These authors reported mean ethylbenzene concentrations ranging from 0.27 to 0.84  $\text{mg}/\text{m}^3$  (0.062–0.19 ppmv) based on 12 1-hour samples.

Levels of ethylbenzene monitored in ambient air show great variation (Jonsson et al. 1985). Generally, air concentrations are much lower in rural areas than in urban areas, where vehicle emissions are thought to be a major contributor of ethylbenzene to ambient air. Ethylbenzene concentrations range from below detection limits in rural areas to 100  $\mu\text{g}/\text{m}^3$  (23.0 ppbv) on busy urban streets (Jonsson et al. 1985). Kelly et al. (1994) reported a median concentration of ethylbenzene of 1.1  $\mu\text{g}/\text{m}^3$  (0.25 ppbv) for 8,723 samples collected from 93 locations throughout the United States.

Median outdoor air concentrations of ethylbenzene for 6 remote and 122 rural locations are reported as 0.156 and 0.013 ppbv (0.679 and 0.056  $\mu\text{g}/\text{m}^3$ ), respectively (EPA 1988c). Median concentrations of 0.62 ppbv (2.7  $\mu\text{g}/\text{m}^3$ ) were reported for 886 suburban and 1,532 urban locations. The daily median concentration of ethylbenzene considering all site types including source dominated areas and workplace air was 0.60 ppbv (2.6  $\mu\text{g}/\text{m}^3$ ). Table 6-2 lists some monitoring results reported for ethylbenzene in various cities.

Ethylbenzene concentrations at four locations along U.S. Highway 70 near Raleigh, North Carolina, during the month of May were reported to range from 10 to 16 ppbv (44–70  $\mu\text{g}/\text{m}^3$ ) that were corrected to include upwind concentrations (Zweidinger et al. 1988).

Concentrations of ethylbenzene were measured in two tunnels: the Fort McHenry Tunnel in Baltimore, Maryland (June 18–24, 1992) and the Tuscarora Mountain Tunnel in Pennsylvania (September 2–8, 1992) (Zielinska et al. 1996). These authors reported minimum and maximum ethylbenzene concentrations (on a carbon basis) for the Fort McHenry Tunnel of 6.3 and 89.2 ppbC (0.79 and 11.2 ppbv) for bore #3, respectively, and 0.5 and 114.1 ppbC (0.06 and 14.26 ppbv) for bore #4,

## 6. POTENTIAL FOR HUMAN EXPOSURE

**Table 6-2. Ethylbenzene Concentrations in Ambient Air Samples Collected in the United States**

Location	Concentration	Comments	Reference
Downey, California	4.6±3.7 ppb (mean±SD) 16.1 ppb <sup>a</sup>	February 18–27, 1984; n=100	Singh et al. 1985
Los Angeles, California	3–12 ppb (range)	September 29– November 13, 1981	Grosjean and Fung 1984
Riverside, California	1.3±0.8 ppb (mean±SD) 4.0 ppb <sup>a</sup>	July 1–13, 1980; n=100	Singh et al. 1985
Denver, Colorado	2.2±3.1 ppb (mean±SD) 18.5 ppb <sup>a</sup>	June 15–28, 1980; n=100	Singh et al. 1985
Chicago, Illinois	0.8±1.2 ppb (mean±SD) 9.5 ppb <sup>a</sup>	April 20–May 2, 1981; n=100	Singh et al. 1985
St. Louis, Missouri	0.6±0.5 ppb (mean±SD) 2.1 ppb <sup>a</sup>	May 29–June 9, 1980; n=100	Singh et al. 1985
Camden, New Jersey	0.17 ppb (mean)	July 6–August 16, 1981; n=35	Harkov et al. 1983
Elizabeth, New Jersey	0.26 ppb (mean)	July 6–August 16, 1981; n=37	Harkov et al. 1983
Newark, New Jersey	0.33 ppb (mean)	July 6–August 16, 1981; n=38	Harkov et al. 1983
Staten Island, New York	1.7±2.5 ppb (mean±SD) 17.2 ppb <sup>a</sup>	March 26–April 5, 1981; n=100	Singh et al. 1985
Staten Island, New York	2.7±4.2 ppb (mean±SD) 16.7 ppb <sup>a</sup>	April 25–May 1, 1984; n=100	Singh et al. 1985
Philadelphia, Pennsylvania	0.8±0.8 ppb (mean±SD) 7.3 ppb <sup>a</sup>	April 4–22, 1983 n=100	Singh et al. 1985
Pittsburgh, Pennsylvania	0.8±1.6 ppb (mean±SD) 10.5 ppb <sup>a</sup>	April 7–17, 1981; n=100	Singh et al. 1985
Houston, Texas	1.5±1.6 ppb (mean±SD) 8.2 ppb <sup>a</sup>	March 8–17, 1984; n=100	Singh et al. 1985
Jones State Forest, Texas	2.8 ppb <sup>b</sup>	January 4–6, 1978	EPA 1979

<sup>a</sup>Maximum measured concentration<sup>b</sup>Median concentration in 10 bag samples (median concentration in 5 can samples was 1.0 ppb)

n = number of samples; SD = standard deviation

## 6. POTENTIAL FOR HUMAN EXPOSURE

respectively, and concentrations for the Tuscarora Tunnel of 1.2 and 11.1 ppbC (0.15 and 6.04 ppbv) , respectively. The total number of light-duty vehicles (LDV) and heavy-duty vehicles (HDV) that passed through each tunnel was 12,273 LDV and 187 HDV for bore #3 and 11,788 LDV and 2,417 HDV for bore #4 of the Fort McHenry Tunnel and 4,887 LDV and 1,041 HDV for the Tuscarora Tunnel.

Ethylbenzene and other VOCs have been found to be removed from waste water in municipal sewers and were emitted to the ambient atmosphere prior to entering a downstream waste water treatment facility in Toronto, Ontario (Quigley and Corsi 1995). These authors measured concentrations of ethylbenzene during four monitoring events and found that concentrations ranged from not detectable to 5 ppm. Headspace concentrations of ethylbenzene exhibited a significant weekday/weekend trend. Significant emissions of all VOCs monitored occurred during three of the four monitoring events. Ethylbenzene had the second highest emissions during all periods and ranged from 7 to 14 g/hour (62–130 kg/year) for event 1 and from 1 to 13 g/hour (9–115 kg/year) for event 2. Ethylbenzene emissions at five municipal treatment facilities ranged from 0.08 to 93 g/day (0.003–3.9 g/hour). Results of this study suggest that sewers that accept VOC-laden waste water, and that are characterized by significant ventilation and drop structures, can be significant sources of VOC emissions (including ethylbenzene) relative to municipal waste water treatment facilities.

Assmuth and Kalevi (1992) reported that ethylbenzene was detected in municipal solid waste landfill gas at minimum and maximum concentrations of 6.6–7.6 mg/m<sup>3</sup> (1.5–1.7 ppmv), <0.1–9.6 mg/m<sup>3</sup> (<0.02–2.2 ppmv), 0.2–1.2 mg/m<sup>3</sup> (0.04–0.28 ppmv), and 85–98 mg/m<sup>3</sup> (20–22 ppmv) at four different landfill sites in Finland. Concentrations of ethylbenzene measured in a biogas collection system at the Miron Quarry Municipal Waste Landfill Site in Montreal, Quebec ranged from 2 to 36 mg/m<sup>3</sup> (0.5–8.3 ppmv) (Goldberg et al. 1995).

#### 6.4.2 Water

The median ethylbenzene concentration in ambient surface waters in the United States in 1980–1982 was <5.0 µg/L (ppb) according to EPA's STORET water quality database (Staples et al. 1985). The chemical was detected in 10% of the 1,101 samples collected during that period. Ethylbenzene was also detected in 7.4% of the 1,368 industrial effluent samples collected during 1980–1982 at a median concentration of <3.0 µg/L (ppb). More recent data from the STORET database indicated that ethylbenzene was only detected in 15 out of 548 surface water samples obtained from January 2005 to March 2007, at a maximum concentration of 2 ppb (EPA 2007i).



## 6. POTENTIAL FOR HUMAN EXPOSURE

From 1989 to 1993, New York City municipal waste waters were analyzed to determine the frequency of detection of organic priority pollutants, including ethylbenzene (Stubin et al. 1996). Ethylbenzene was detected in 14 of 84 (17%) influent samples at concentrations ranging from 1 to 11  $\mu\text{g/L}$  (ppb) and in only 1 of 84 (1%) effluent samples at a concentration of 2  $\mu\text{g/L}$  (ppb).

Ethylbenzene and other VOCs have been detected in waste water in municipal sewers prior to entering a downstream waste water treatment facility in Toronto, Ontario (Quigley and Corsi 1995). These authors measured concentrations of ethylbenzene in waste water during several monitoring events and found that concentrations ranged from 0.059 to 0.086 mg/L (ppm) in one event and from 7 to 11 mg/L (ppm) in another event. The authors also determined that the stripping efficiency across two drop structures with waste water fall heights of 1.4–3 meters within the sewer system removed 31–36% of the ethylbenzene in the waste water. Results of this study suggest that sewers that accept VOC-laden waste water, and that are characterized by significant ventilation and drop structures, can be significant sources of VOC emissions (including ethylbenzene) relative to municipal waste water treatment facilities.

As part of EPA's Nationwide Urban Runoff Program, ethylbenzene was measured in 4% of the municipal runoff samples collected in 15 cities throughout the United States (Cole et al. 1984). The measured ethylbenzene concentration range was 1–2  $\mu\text{g/L}$  (ppb). Ethylbenzene was detected in 41 out of 249 (16.5%) storm water runoff samples collected at 46 different sampling locations in North Carolina over a 1-year period (Borden et al. 2002). The mean, median, and maximum ethylbenzene levels were 0.10, 0.07, and 0.36  $\mu\text{g/L}$  (ppb), respectively.

Ethylbenzene was measured in seawater at an average concentration of 0.011  $\mu\text{g/L}$  (ppb) and a concentration range of 0.0018–0.022  $\mu\text{g/L}$  (ppb) over a 15-month observation period at Vineyard Sound, Massachusetts (Gschwend et al. 1982). Ethylbenzene also has been reported in surface waters of the Gulf of Mexico at a concentration range of 0.0004–0.0045  $\mu\text{g/L}$  (ppb) (Sauer et al. 1978).

Ethylbenzene has been detected in a relatively remote location (Mt. Mitchell, North Carolina) in cloud water at a mean concentration of 170 ng/L (range 0–450 ng/L) (Aneja 1993). The average concentration of ethylbenzene in precipitation was 34 ng/L. Ethylbenzene has also been detected in snow samples from two remote sites in the province of Québec, Canada (Kos and Ariya 2006). Ethylbenzene levels reported in  $\mu\text{g/L} \pm 3\sigma$  were: 2.65 $\pm$ 1.28 (Resolute Bay); 0.22 $\pm$ 0.02 (Gaspé Peninsula); and 0.31 $\pm$ 0.06 (Gaspé Peninsula).

## 6. POTENTIAL FOR HUMAN EXPOSURE

From 1989 to 1990 and from 1992 to 1993, ethylbenzene was monitored in wetland-treated leachate water at a municipal solid waste landfill in central Florida (Chen and Zoltek 1995). During the first sampling period, ethylbenzene was detected in surface water samples ranging from 0.06 to 0.09 ppb and in groundwater samples ranging from 0.06 to 9.75 ppb. During the second sampling period (1992–1993), ethylbenzene was not detected in surface water samples, but was detected in groundwater samples at concentrations ranging from below detection limits to 10.55 ppb. Ethylbenzene was detected in a study of three landfills in central Florida (Hallbourg et al. 1992). These authors reported concentrations of ethylbenzene in groundwater of 1.63–9.75, <1–83.8, and <1–8.6 µg/L (ppb) at the three different landfill sites. The mean concentration of ethylbenzene detected in landfill leachate from these disposal areas was 17.5 µg/L.

Ethylbenzene was measured in all three drinking water plants sampled as part of the New Orleans Area Water Supply Study conducted by EPA in 1974 (Keith et al. 1976). The reported concentrations were 1.6, 1.8, and 2.3 µg/L (ppb). The 1982 Ground Water Supply Survey conducted by EPA reported ethylbenzene in only 3 out of 466 random samples at a mean concentration of 0.8 µg/L (ppb) and a maximum concentration of 1.1 µg/L (ppb) (Cotruvo 1985). Chemical monitoring of 617 private and 1,174 public groundwater wells in the state of Wisconsin revealed that ethylbenzene was detected in 3 community and 12 private wells (Krill and Sonzogni 1986). The concentration of ethylbenzene detected exceeded the state's recommended drinking water advisory limit of 1,400 µg/L (ppb) in 9 of the 12 private wells, but no exceedences were observed in the public wells.

Ethylbenzene was infrequently detected in a comprehensive survey conducted by the United States Geological Survey (USGS) of volatile organic compounds in private and public groundwater wells used for drinking water (USGS 2006). Ethylbenzene was identified in 18 out of 3,497 aquifer samples at a median concentration of 0.035 µg/L for the 18 samples having positive detections. In an analysis of domestic groundwater wells, the median concentration of ethylbenzene was reported as 0.041 µg/L for samples having positive detections. Ethylbenzene was identified in 7 out of 1,083 samples obtained from public wells across the United States at a median concentration of 0.32 µg/L for samples having positive detections.

Although ethylbenzene does not appear to be a frequent contaminant in public water supplies, private residential wells near landfills, hazardous waste sites, or gas stations are more likely to contain detectable levels of this compound. Ethylbenzene was listed as one of the 58 most frequently detected chemicals

## 6. POTENTIAL FOR HUMAN EXPOSURE

associated with groundwater contamination near superfund sites (Knox and Canter 1994). Ethylbenzene was listed as having a medium priority with respect to its frequency of occurrence. Ethylbenzene has been detected in wells downgradient from landfills in Southern Ontario at concentrations ranging from 12 to 74 µg/L (ppb) (Barker 1987). Ethylbenzene was detected at levels of 1–22, 1–5, and <1 µg/L in groundwater 0–37, 50–114, and 170–254 meters, respectively, downgradient from a municipal landfill located in Grindsted, Denmark (Baun et al. 2000).

Borden and Yanoschak (1990) compared ground and surface water quality impacts associated with North Carolina sanitary landfills. These authors found that ethylbenzene was detected at ≈25% of the waste water effluents (receiving secondary treatment) and only 3% of the groundwater sampled in the vicinity of sanitary landfill sites. Groundwater monitoring at 479 hazardous waste disposal sites indicated that ethylbenzene, like the other 9 VOCs monitored, was detected at more than 100 of the 479 sites tested (Plumb 1991). Ethylbenzene was also one of the VOCs detected in groundwater samples from hazardous waste sites in all 10 EPA regions. Rosenfeld and Plumb (1991) reported that ethylbenzene was detected in groundwater at 19% of wood-treatment industry sites based on its frequency of detection and average concentration. Groundwater near an underground coal gasification site in northeastern Wyoming contained concentrations of ethylbenzene ranging from 92 to 400 µg/L (ppb) (Stuermer et al. 1982). Groundwater samples near a fuel spill in the Great Ouse Basin in Great Britain contained ethylbenzene concentrations as high as 1,110 µg/L (ppb) (Tester and Harker 1981).

### 6.4.3 Sediment and Soil

The median ethylbenzene concentration (dry weight) detected in sediment in the United States in 1980–1982 was 5 µg/kg (ppb) according to EPA's STORET water quality database (Staples et al. 1985). The compound was detected in 11% of 350 sediment samples analyzed. More recent data from the STORET database indicated that ethylbenzene was identified, but not quantified, in 25 out of 68 sediment samples obtained from January 2005 to March 2007 (EPA 2007i).

### 6.4.4 Other Environmental Media

Data from the FDA Total Diet Study Market Basket Surveys collected between September 1991 and October 2003 indicate that ethylbenzene was detected in 82 different food items at a maximum concentration of 0.129 ppm (FDA 2006b). In a previous Market Basket Survey, ethylbenzene was identified in 15 out of 234 table-ready food items at an average concentration of 0.0146 ppm and a range

## 6. POTENTIAL FOR HUMAN EXPOSURE

of 0.00637–0.0387 ppm (Heikes et al. 1995). Trace concentrations of ethylbenzene have been reported in split peas (0.013 mg/kg [ppm]), lentils (0.005 mg/kg [ppm]), and beans (mean concentration 0.005 mg/kg [ppm]; maximum concentration 0.011 mg/kg [ppm]) (Lovegren et al. 1979). Ethylbenzene was reported as one of 227 organic chemicals present in roasted filbert nuts (Kinlin et al. 1972). Gorna-Binkul et al. (1996) reported concentrations of ethylbenzene in orange peel (0.0236 µg/g [ppm] dry weight) and in parsley leaves (0.2567 µg/g [ppm] dry weight). The author reported that the differences in concentrations of the VOCs were dependent on the plant species and the morphological part of the plant analyzed. In underground parts (i.e., roots and bulbs) not directly exposed to polluted ambient air during growth, no VOC concentrations were detected. Biedermann et al. (1995) reported concentrations of several VOCs in extra virgin olive oil collected in northwest Italy. These authors measured ethylbenzene levels in raw olives of 6 µg/kg (ppb), which increased with time as they were milled to 25 µg/kg (ppb). Levels in the finished olive oils ranged from 11 to 27 µg/kg (ppb) depending on the preparation method used. These authors reported that while some of the ethylbenzene was accumulated in the olives in the orchards, a larger proportion was accumulated as a result of exposure of the oil to air in the milling areas. Ethylbenzene concentrations in olive oil increased from 6 to 235 ppb after 2 days of exposure. The authors concluded that the production process increased the concentration of ethylbenzene in the oil as a result of uptake from the air that was likely to be contaminated with gasoline vapors associated with small vehicles used to move the olives from area to area within the olive oil mill.

Ethylbenzene was also found to migrate from thermoset polyester cooking containers (composed of cross-linking chains of styrene) into belly pork during cooking (Gramshaw and Vandenburg 1995). Migration ranged from <6 to 34 µg/kg for ethylbenzene. The authors also found that the migration measured during the second use of the cookware was generally higher than that during the first use. These authors also reported that ethylbenzene concentrations in food cooked in foil-covered dishes was higher than that in the same food cooked uncovered. This was especially true for ethylbenzene that was more volatile than the styrene tested. Ehret-Henry et al. (1994) also reported migration of ethylbenzene from polystyrene containers into dairy products. Concentrations of ethylbenzene were 2–4 µg/kg for yogurt and 4 µg/kg for chocolate dessert.

Sack et al. (1992) conducted a survey of VOCs in 1,159 household items, including automotive products, household cleaners and polishes, paint related products, fabric and leather treatments, cleaners for electronic equipment, oils, greases, and lubricants, adhesive-related products, and miscellaneous products. Ethylbenzene was detected in 157 of 658 (24%) of the products tested. The highest mean ethylbenzene concentrations and percentage of products in each category in which ethylbenzene was detected are as

## 6. POTENTIAL FOR HUMAN EXPOSURE

follows; 7.2% w/w (wet weight) in 7.5% of automotive products, 2.4% w/w in 47.8% of paint-related products, and 1.0% w/w in 11.8% of fabric and leather treatments.

Hodgson et al. (1996) determined the contribution of environmental tobacco smoke (ETS) to concentrations of VOCs in smoking environments. These authors reported that the average emission factor for ethylbenzene for six brands of cigarettes was 101  $\mu\text{g}/\text{cigarette}$  (range 83–142  $\mu\text{g}/\text{cigarette}$ ). The average concentration of ethylbenzene in five smoking areas ranged from 1.3 to 8.7  $\mu\text{g}/\text{m}^3$  (0.3–2 ppbv). Martin et al. (1997) determined the ETS yield of selected analytes, including ethylbenzene, for the 50 top-selling U.S. cigarette brand styles in 1991 and for the University of Kentucky Research cigarette, K1R4F. The ETS was generated by smokers in an environmental test chamber. The ethylbenzene concentrations measured were 8.68  $\mu\text{g}/\text{m}^3$  for full flavor cigarettes, 8.24  $\mu\text{g}/\text{m}^3$  for full flavor low tar cigarettes, and 8.72  $\mu\text{g}/\text{m}^3$  for ultra-low-tar cigarettes. The mean ethylbenzene concentration for all cigarettes was 8.50  $\mu\text{g}/\text{m}^3$ . The mean ethylbenzene yields by tar category weighted by market share were 81.18  $\mu\text{g}/\text{cigarette}$  for full flavor cigarettes, 76.79  $\mu\text{g}/\text{cigarette}$  for full flavor low tar cigarettes, and 81.66  $\mu\text{g}/\text{cigarette}$  for ultra low tar cigarettes. The mean ethylbenzene yield for all cigarettes was 79.57  $\mu\text{g}/\text{cigarette}$ .

Ethylbenzene was not detected (at a detection limit of 0.025 mg/kg [ppm] wet weight) in any of the 97 biota samples collected from all STORET stations in 1980–1983 (Staples et al. 1985). Ethylbenzene was detected at low concentrations (0.8 ng/g [0.8 ppb]) in oyster tissue, but not in clam tissue from Lake Pontchartrain at Passes, Louisiana (Ferrario et al. 1985). The highest average ethylbenzene concentration measured in tissue of bottomfish from Commencement Bay in Tacoma, Washington was reported as 0.01 mg /kg (ppm) (Nicola et al. 1987).

## 6.5 GENERAL POPULATION AND OCCUPATIONAL EXPOSURE

The highest exposure to ethylbenzene for the general public is most likely to occur via inhalation associated with the use of self-service gasoline pumps or while driving a gasoline-powered motor vehicle especially in high traffic areas or in tunnels (Lawryk et al. 1995). Backer et al. (1997) performed a study that measured exposures associated with the pumping two different blends of fuel under cold conditions in Fairbanks, Alaska. The subjects in the study had significantly higher levels of gasoline components in their blood after pumping gasoline than before. The changes in VOC levels in blood were similar whether the individuals pumped regular or oxygenated gasoline. Prior to pumping regular gasoline, the median concentration of ethylbenzene in blood was 0.10 ppb (n=26) with a range of 0.02–0.73 ppb; after

## 6. POTENTIAL FOR HUMAN EXPOSURE

pumping, the median concentration was 0.16 ppb with a range of 0.06–1.40 ppb. Before pumping an oxygenated fuel blend that was 10% ethanol, the median concentration of ethylbenzene in blood was 0.11 ppb (n=22) with a range of 0.04–0.55 ppb; after pumping, the ethanol blend, the median concentration was 0.16 ppb with a range of 0.06–0.64 ppb.

Lawryk and Weisel (1996) measured in-vehicle concentrations of selected gasoline-derived volatile organic compounds on 113 commutes through suburban New Jersey and 33 New Jersey/New York commutes. In a typical suburban commute, the mean in-vehicle concentration of ethylbenzene was  $11.5 \pm 18.8 \mu\text{g}/\text{m}^3$  ( $2.64 \pm 4.32$  ppbv; n=52) under low ventilation conditions and  $8.5 \pm 11.2 \mu\text{g}/\text{m}^3$  ( $1.9 \pm 2.57$  ppbv; n=43) under high ventilation conditions. On the New Jersey turnpike and in the Lincoln Tunnel, the mean in-vehicle concentrations of ethylbenzene were  $8.8 \pm 10.8 \mu\text{g}/\text{m}^3$  ( $2.0 \pm 2.48$  ppbv; n=32) and  $14.3 \pm 10.2 \mu\text{g}/\text{m}^3$  ( $3.29 \pm 2.34$  ppbv; n=32), respectively.

Ethylbenzene is ubiquitous in urban and rural atmosphere resulting from vehicular and industrial emissions (EPA 1988c). Tobacco smoke also provides a general source of exposure to ethylbenzene in indoor air (Wallace et al. 1987c). Wallace et al. (1989) also reported that two activities, painting and the use of automotive products (carburetor cleaner), led to increased indoor exposure to ethylbenzene by 100-fold. Information on exposure from foods is limited, but is not likely to be a significant source of ethylbenzene for the general population.

Human exposure to styrene and ethylbenzene was assessed by considering inhalation exposure (including cigarette smoking) and food intake (Tang et al. 2000). The daily exposure to ethylbenzene for the general population was calculated as  $1.8 \mu\text{g}/\text{kg}$  bodyweight/day, with up to 99% of the exposure due to inhalation routes and only 1–2% caused by food consumption.

One-half of the household drinking water used in the United States is supplied by groundwater, and contamination of groundwater by petroleum products is an increasingly common problem (Beavers et al. 1996). Beavers et al. (1996) conducted a study in a New England household that used groundwater contaminated by gasoline from a leaking underground storage tank. A total daily dose of  $379 \mu\text{g}$  ethylbenzene ( $204 \mu\text{g}$  ingested and  $175 \mu\text{g}$  inhaled) was estimated for an exposed subject compared to a median daily dose of  $32 \mu\text{g}$  for unexposed subjects. Of the  $175 \mu\text{g}$  inhaled by the exposed subject,  $108 \mu\text{g}$  was attributed to shower activities. The exposed subject and the three non-exposed subjects all were smokers.

## 6. POTENTIAL FOR HUMAN EXPOSURE

The 1982 National Human Adipose Tissue Survey conducted by EPA measured ethylbenzene in 96% of the 46 composite samples analyzed for VOCs (EPA 1986a). A wet tissue concentration range of not detected (detection limit=2 ng/g) to 280 ng/g (ppb) was reported, but an average concentration was not provided.

Ethylbenzene has been detected in breast milk samples collected from 8 of 12 women from various cities in the United States; however, the concentrations were not reported (Pellizzari et al. 1982). The 12 women sampled in the study were residents of Bayonne, New Jersey (6 women), Jersey City, New Jersey (2 women), Bridgeville, Pennsylvania (2 women), and Baton Rouge, Louisiana (2 women).

Mean and median concentrations of ethylbenzene detected in 631 blood samples from participants in the Third National Health and Nutrition Examination Survey (NHANES III 1998–1994 data) were 0.11 and 0.06 ppb (95 percentile value of 0.25 ppb), respectively (Ashley et al. 1994). In an earlier study (Ashley et al. 1992), these authors reported a mean ethylbenzene concentration of 0.12 ppb in 13 blood samples. Hajimiragha et al. (1989) conducted a study of 13 nonsmokers and 14 smokers with no known occupational or hobby-related exposure to volatile organic hydrocarbons. These authors reported a mean and median ethylbenzene concentration of 651 ng/L (0.651 ppb) and 431 ng/L (0.431 ppb) for the nonsmokers and 837 ng/L (0.837 ppb) and 533 ng/L (0.533 ppb) for the smokers. Ethylbenzene concentrations tended to occur at higher concentrations in the blood of smokers than in nonsmokers; however, the difference was not significant. Ashley et al. (1995) also reported that smoking elevated the blood levels of ethylbenzene and was highly correlated with blood levels of 2,5-dimethylfuran. These authors reported a mean concentration of 0.10 ng/mL (ppb) (median 0.048 ng/mL; range from below detection limit to 2.7 ng/mL) for nonsmokers and a mean concentration of 0.17 ng/mL (ppb) (median 0.16 ng/mL; range 0.036–0.88 ng/mL) for smokers. To aid in understanding the kinetics of uptake and elimination of volatile organics (including ethylbenzene), Ashley and Prah (1997) measured blood concentrations before, during, and after exposure of five individuals to a mixture of volatile organics in a controlled chamber. The half-lives of the compounds measured were <0.5 hour, but the elimination time courses were multiexponential and suggested that, with repeated exposure, bioaccumulation may occur in humans.

Occupational exposure to ethylbenzene in the petroleum industry has been reported in a study that measured ethylbenzene concentrations in air for 49–56 workers during the summer of 1984 (Rappaport et al. 1987). The average air concentrations of ethylbenzene measured over the full work shift for gasoline service station attendants, transport drivers, and outdoor refinery personnel were comparable at 0.063,

## 6. POTENTIAL FOR HUMAN EXPOSURE

0.079, and 0.079 mg/m<sup>3</sup>, respectively (14.5, 18.2, and 18.2 ppbv, respectively). The authors noted that exposures of service station attendants were significantly lower when vapor recovery systems were present.

Personal air monitoring of 35 varnish workers (spraymen) has revealed an average ethylbenzene concentrations of 4.0 ppm, while the average concentration in blood was 61.4 µg/L (Angerer and Wulf 1985). Concentrations of ethylbenzene were monitored in auto paint shops in Spain that used organic solvents (de Medinilla and Espigares 1988). These authors reported air concentrations of ethylbenzene ranging from 0.50 to 125.0 mg/m<sup>3</sup> (0.12–28.75 ppmv).

The indoor air of screen printing plant workrooms located directly below houses in Amsterdam, Holland was found to contain median TWA concentrations of ethylbenzene ranging from <0.03 mg/m<sup>3</sup> (7 ppbv) to 1.30 mg/m<sup>3</sup> (299 ppbv) and maximum TWA concentrations ranging from 0.11 mg/m<sup>3</sup> (25 ppbv) to 3.21 mg/m<sup>3</sup> (738 ppbv) (Verhoeff et al. 1988).

Spray-painting and gluing operations can also result in exposure to ethylbenzene; personal air monitoring of workers measured average exposures of approximately 0.50 ppmv (2.2 mg/m<sup>3</sup>) (Whitehead et al. 1984). Most of the operations measured during the study were performed in ventilation hoods.

Holz et al. (1995) reported that ethylbenzene air concentrations detected from air sampling in all areas of a styrene production facility located in the former German Democratic Republic ranged from 365 to 2,340 µg/m<sup>3</sup> (0.08–0.53 ppmv).

According to the National Occupational Exposure Study (NOES) conducted by NIOSH from 1981 to 1983, an estimated 201,838 workers were potentially exposed to ethylbenzene in the workplace (NIOSH 1990). The NOES database does not contain information on the frequency, concentration, or duration of occupational exposure to any of the chemicals listed. The survey provides only estimates of the numbers of workers for whom potential exposure in the workplace is an issue.

The Occupational Safety and Health Administration (OSHA) has set a Permissible Exposure Limit (PEL) based on a TWA of 100 ppm (≈435 mg/m<sup>3</sup> at 1 atm and 25 °C) in the workplace (OSHA 1974). The American Conference of Governmental Industrial Hygienists also recommends a Threshold Limit Value (TLV-TWA) of 100 ppm (≈435 mg/m<sup>3</sup>) for occupational exposures (ACGIH 1992). The recommended exposure limit (REL) for occupational exposures (TWA) set by the NIOSH is also 100 ppm



## 6. POTENTIAL FOR HUMAN EXPOSURE

( $\approx 435 \text{ mg/m}^3$ ) for ethylbenzene based on a 10-hour average workday and a 40-hour workweek (NIOSH 2005).

## 6.6 EXPOSURES OF CHILDREN

This section focuses on exposures from conception to maturity at 18 years in humans. Differences from adults in susceptibility to hazardous substances are discussed in Section 3.7, Children's Susceptibility.

Children are not small adults. A child's exposure may differ from an adult's exposure in many ways. Children drink more fluids, eat more food, breathe more air per kilogram of body weight, and have a larger skin surface in proportion to their body volume. A child's diet often differs from that of adults. The developing human's source of nutrition changes with age: from placental nourishment to breast milk or formula to the diet of older children who eat more of certain types of foods than adults. A child's behavior and lifestyle also influence exposure. Children crawl on the floor, put things in their mouths, sometimes eat inappropriate things (such as dirt or paint chips), and spend more time outdoors. Children also are closer to the ground, and they do not use the judgment of adults to avoid hazards (NRC 1993).

Children can be exposed to ethylbenzene by inhalation in urban and rural atmospheres contaminated by vehicular and industrial emissions. Tobacco smoke also provides a general source for exposure of children to ethylbenzene in indoor air, especially in the homes where one or both parents smoke. Some household activities, such as painting, can lead to short-term exposures to higher levels of ethylbenzene if ventilation is inadequate. The limited information available on exposure from foods indicates that food is not likely to be a significant source of ethylbenzene for children. Ethylbenzene is heavier than air, and since young children are closer to the ground or floor because of their height, during accidental exposures they may be exposed to more ethylbenzene vapors than adults.

A 2-year monitoring study (2000–2001) involving 134 children aged 6–10 was conducted in Minneapolis, Minnesota in order to assess exposure to VOCs, including ethylbenzene (Sexton et al. 2005). The distribution of ethylbenzene measured in the blood of these children (416 samples) is provided in Table 6-3. Comparing these data to monitoring results from NHANES III, the levels of ethylbenzene in children's blood is approximately 2 or more times lower than in non-occupationally exposed adults (Sexton et al. 2005). Ethylbenzene has been detected in breast milk samples collected from 8 of 12 women from various cities in the United States; however, the concentrations were not reported (Pellizzari et al. 1982). The 12 women sampled in the study were residents of Bayonne, New

## 6. POTENTIAL FOR HUMAN EXPOSURE

**Table 6-3. Distribution of Blood Ethylbenzene Concentrations in Children (ng/mL)**

Sampling period	Samples	Percentage							
		above detection limit	10th	25th	50th	75th	90th	95th	99th
February 2000	92	79.1	0.02	0.02	0.03	0.05	0.07	0.08	0.12
May 2000	86	66.7	0.01	0.02	0.03	0.04	0.05	0.07	0.17
February 2001	63	61.1	0.02	0.02	0.02	0.03	0.03	0.03	0.04
May 2001	88	98.9	0.03	0.04	0.05	0.06	0.08	0.09	0.10

Source: Sexton et al. 2005

## 6. POTENTIAL FOR HUMAN EXPOSURE

Jersey (6 women); Jersey City, New Jersey (2 women); Bridgeville, Pennsylvania (2 women); and Baton Rouge, Louisiana (2 women). No direct pharmacokinetic experiments have been done to investigate whether significant amounts of ethylbenzene are transferred to breast milk in mammals. No studies were located that expressed the level of ethylbenzene or its metabolites in amniotic fluid, meconium, cord blood or neonatal blood.

Although no data were found in the literature, it is possible that children playing near hazardous waste sites could be dermally exposed to ethylbenzene in soil or orally exposed by hand-to-mouth activity and/or soil pica. Ethylbenzene, however, is only moderately adsorbed by soil. Since it has a moderately high vapor pressure, it will evaporate fairly rapidly from dry soil. However, under certain soil conditions, ethylbenzene may persist for longer periods of time; it has been detected in soil samples collected at 469 of the 829 NPL hazardous waste sites where it has been detected in some environmental media (HazDat 2007). No information was found concerning dermal and oral bioavailability of ethylbenzene in soil. In the home, intentionally sniffing solvents could lead to high levels of exposure. No information was found concerning differences in the weight-adjusted intakes of ethylbenzene by children.

No exposures of children to ethylbenzene by contamination of workers' homes were found in the Workers' Home Contamination Study conducted under the Worker's Family Protection Act (NIOSH 1995).

### 6.7 POPULATIONS WITH POTENTIALLY HIGH EXPOSURES

In addition to individuals who are occupationally exposed to ethylbenzene (see Section 6.5), there are several groups within the general population that may receive potentially high exposures (higher than background levels) to ethylbenzene. These populations include individuals living in proximity to sites where ethylbenzene is produced or used in manufacturing or sites where ethylbenzene is disposed, and includes individuals living near the 829 NPL hazardous waste sites where ethylbenzene has been detected in some environmental media (HazDat 2007). Ethylbenzene has been detected in air and groundwater at 121 and 557 NPL hazardous waste sites, respectively.

Individuals living or working near petroleum refineries or chemical manufacturing plants may receive higher inhalation exposures than those experienced by the general population. Residents living in the vicinity of gasoline stations, high traffic areas, tunnels, parking lots, and highways may also receive a higher than average inhalation exposure since ethylbenzene is a component of gasoline. Residential wells

## 6. POTENTIAL FOR HUMAN EXPOSURE

downgradient of leaking underground storage tanks, landfills, and hazardous waste sites contaminated with petroleum products and solvents may contain high levels of ethylbenzene. If these residential wells are the primary source of drinking water, this may pose a risk to human health via consumption of contaminated water as well as increased inhalation of and dermal contact with ethylbenzene during showering and bathing. A study of indoor air in a home using gasoline-contaminated drinking water found that exposures to ethylbenzene could occur via inhalation during showering and other household activities (Beavers et al. 1996). Ethylbenzene concentrations in shower air were often one to two orders of magnitude higher than non-shower air. These authors reported a total daily household dose of ethylbenzene of 379  $\mu\text{g}$ , with 204  $\mu\text{g}$  derived from ingestion of drinking water and 175  $\mu\text{g}$  derived from inhalation (108  $\mu\text{g}$  from shower-related inhalation and 67  $\mu\text{g}$  from non-shower-related inhalation) to the exposed subject living in the home. The daily dose of ethylbenzene for an unexposed smoker by comparison was estimated to be 32  $\mu\text{g}$ .

### 6.8 ADEQUACY OF THE DATABASE

Section 104(i)(5) of CERCLA, as amended, directs the Administrator of ATSDR (in consultation with the Administrator of EPA and agencies and programs of the Public Health Service) to assess whether adequate information on the health effects of ethylbenzene is available. Where adequate information is not available, ATSDR, in conjunction with NTP, is required to assure the initiation of a program of research designed to determine the health effects (and techniques for developing methods to determine such health effects) of ethylbenzene.

The following categories of possible data needs have been identified by a joint team of scientists from ATSDR, NTP, and EPA. They are defined as substance-specific informational needs that if met would reduce the uncertainties of human health assessment. This definition should not be interpreted to mean that all data needs discussed in this section must be filled. In the future, the identified data needs will be evaluated and prioritized, and a substance-specific research agenda will be proposed.

#### 6.8.1 Identification of Data Needs

**Physical and Chemical Properties.** The physical and chemical properties of ethylbenzene are well characterized (see Table 4-2) and allow prediction of the transport and transformation of the compound in the environment (Amoore and Hautala 1983; Bohon and Claussen 1951; Chiou et al. 1983; EPA 1982;

## 6. POTENTIAL FOR HUMAN EXPOSURE

Hansch and Leo 1979; Hodson and Williams 1988; Mackay and Shiu 1981; Polak and Lu 1973; Sutton and Calder 1975; Verschueren 1983). No additional studies are needed at the present time.

**Production, Import/Export, Use, Release, and Disposal.** According to the Emergency Planning and Community Right-to-Know Act of 1986, 42 U.S.C. Section 11023, industries are required to submit substance release and off-site transfer information to the EPA. The TRI, which contains this information for 2005, became available in May of 2007. This database is updated yearly and should provide a list of industrial production facilities and emissions.

Ethylbenzene has numerous uses (ACGIH 2002; Ransley 1984; Verschueren 1983), and production of the chemical has steadily increased since 1983 (C&EN 1994a, 1994b, 1995, 2006; Kirschner 1995). Releases occur from a variety of common sources including manufacturing and production (TRI05 2007), fuels, automobile exhaust, and fumes from paints, varnishes, solvents, carpet glue, and hot asphalt (Fishbein 1985; Hampton et al. 1983; Junk and Ford 1980; Katzman and Libby 1975; Kitto et al. 1997; Mukund et al. 1996; NAS 1980; Wallace et al. 1987b). Ethylbenzene also is released from waste waters to the atmosphere in municipal sewer systems (Quigley and Corsi 1995). Therefore, the potential for human exposure to ethylbenzene is considerable. The medium most likely to be contaminated is air, although ethylbenzene has also been detected in trace amounts in water supplies. Some ethylbenzene-containing wastes are designated as hazardous and are subject to EPA handling and recordkeeping requirements. Recommended methods for the disposal of ethylbenzene include burial in a landfill and rotary kiln incineration, liquid injection incineration, and fluidized bed incineration (EPA 1981d). No data need is identified at this time.

**Environmental Fate.** Ethylbenzene is primarily partitioned to and transported in air (Dewulf and van Langenhove 1997; Eisenreich et al. 1981; Mackay 1979; Masten et al. 1994). The partitioning and transport processes in water, soil, and aquatic life are also well characterized (ASTER 1995; Dewulf et al. 1996; Kawamura and Kaplan 1983; Ligocki et al. 1985; Swann et al. 1983). Transformation and degradation processes have also been well characterized in air (Atkinson and Carter 1984; Atkinson et al. 1978; Grovenstein and Mosher 1970; Herron and Huie 1973; Hoshino et al. 1978; O'Brien et al. 1975; Ohta and Ohya 1985; Ravishankara et al. 1978; Yanagihara et al. 1977), water (Acton and Barker 1992; Anid et al. 1993; Bouwer and McCarty 1984; Burback and Perry 1993; Ehrhardt and Petrick 1984; Gschwend et al. 1982; Hutchins 1991; Masten et al. 1994; Wakeham et al. 1983; Wilson et al. 1986), and in soil and sediment (Bestetti and Galli 1984; Chen and Taylor 1995; Hutchins 1991; Hutchins et al.

## 6. POTENTIAL FOR HUMAN EXPOSURE

1991; Jamison et al. 1970; Ramanand et al. 1995; Van der Linden and Thijsse 1965; Yadav and Reddy 1993; Zappi et al. 1996). No data need is identified at this time.

**Bioavailability from Environmental Media.** Ethylbenzene is absorbed following inhalation, oral, and dermal exposures. Information is available on its absorption from air and water, but little data exist regarding dermal bioavailability and absorption from soil and food. Due to its large vapor pressure and Henry's law constant, ethylbenzene is expected to volatilize fairly rapidly from soil surfaces. Based on the moderate affinity of ethylbenzene for soil, especially soils with relatively high organic carbon content, the amount of ethylbenzene in bioavailable form in soil is expected to be low to moderate. Because of the low BCF values calculated for ethylbenzene, food chain bioaccumulation would not be expected to be significant sources of ethylbenzene exposure. No data need is identified at this time.

**Food Chain Bioaccumulation.** Limited data suggests that ethylbenzene does not bioconcentrate in aquatic organisms (Ogata et al. 1984), and is not likely to bioaccumulate in aquatic or terrestrial food chains. However, little information on food residues in commercially important fish and shellfish species is currently available. Additional monitoring data regarding the levels of ethylbenzene would be helpful for several commercially important fish and shellfish species.

**Exposure Levels in Environmental Media.** Reliable monitoring data for the levels of ethylbenzene in contaminated media at hazardous waste sites are needed so that the information obtained on levels of ethylbenzene in the environment can be used in combination with the known body burden of ethylbenzene to assess the potential risk of adverse health effects in populations living in the vicinity of hazardous waste sites.

An extensive amount of atmospheric monitoring data exists (EPA 1988c; Goldberg et al. 1995; Kinney et al. 2002; Kostianen 1995; Mukerjee et al. 1997; Quigley and Corsi 1995; Wallace et al. 1987a, 1987c; Zielinska et al. 1996; Zweidinger et al. 1988). Ethylbenzene has also been detected in surface water and groundwater (Barker 1987; Borden and Yanoschak 1990; Chen and Zoltek 1995; Cole et al. 1984; Cotruvo 1985; Gschwend et al. 1982; Krill and Sonzogni 1986; Quigley and Corsi 1995; Staples et al. 1985; Stubin et al. 1996; Stuermer et al. 1982; Tester and Harker 1981), sediment (Staples et al. 1985), a limited number of foodstuffs (Ferrario et al. 1985; Górna-Binkul et al. 1996; Kinlin et al. 1972; Lovegren et al. 1979; Nicola et al. 1987), and in cigarette smoke (Hodgson et al. 1996; Martin et al. 1997; Wallace 1986; Wallace et al. 1987c). Continued monitoring data at or around hazardous waste sites are needed in order to assess human exposure for populations residing in these areas.

## 6. POTENTIAL FOR HUMAN EXPOSURE

**Exposure Levels in Humans.** Ethylbenzene and its metabolites have been detected in human blood (Angerer and Wulf 1985; Ashley et al. 1994), urine (Bardodej and Bardodevova 1970; Dutkiewicz and Tyras 1967; Engstrom and Bjurstrom 1978; Gromiec and Piotrowski 1984; Kiese and Lenk 1974; Sullivan et al. 1976; Yamasaki 1984), breast milk (Pellizzari et al. 1982), and adipose tissue (Engstrom and Bjurstrom 1978; EPA 1986a). Most of the monitoring data have come from occupational studies of specific worker populations exposed by inhalation. Members of the general population can be exposed to ethylbenzene through inhalation of fumes while pumping gas or riding in gasoline-powered vehicles (Backer et al. 1997; Lawryk and Weisel 1996; Lawryk et al. 1995). Additional information regarding the general population's exposure to ethylbenzene would be useful. Dietary intake is expected to be insignificant as compared to inhalation exposure (Tang et al. 2000). Oral exposures are likely to be low, except for the consumption of contaminated drinking water by populations living in the vicinity of hazardous waste sites, leaking underground storage tanks, or municipal landfills.

**Exposures of Children.** Children are exposed to ethylbenzene by the same routes that affect adults. Biomonitoring data suggest that blood levels of ethylbenzene are lower in children than non--occupationally exposed adults (Sexton et al. 2005). Ethylbenzene has been detected in breast milk samples collected from 8 or 12 women from various cities in the United States; however, the concentrations were not reported (Pellizzari et al. 1982). There do not appear to be any childhood specific means to decrease exposure to ethylbenzene. A data need exists to determine current ethylbenzene residues and their sources in breast milk of members of the general population.

Child health data needs relating to susceptibility are discussed in Section 3.12.2, Identification of Data Needs: Children's Susceptibility.

**Exposure Registries** No exposure registries for ethylbenzene were located. This substance is not currently one of the compounds for which a sub-registry has been established in the National Exposure Registry. The substance will be considered in the future when chemical selection is made for sub-registries to be established. The information that is amassed in the National Exposure Registry facilitates the epidemiological research needed to assess adverse health outcomes that may be related to exposure to this substance.

## 6. POTENTIAL FOR HUMAN EXPOSURE

**6.8.2 Ongoing Studies**

The Federal Research in Progress (FEDRIP 2007) database provides additional information obtainable from a few ongoing studies that may fill in some of the data needs identified in Section 6.8.1. These studies are summarized in Table 6-4.

As part of the Third National Health and Nutrition Evaluation Survey (NHANES III), the Environmental Health Laboratory Sciences Division of the National Center for Environmental Health, Centers for Disease Control and Prevention, will be analyzing human blood samples for ethylbenzene and other volatile organic compounds. These data will give an indication of the frequency of occurrence and background levels of these compounds in the general population.



## 6. POTENTIAL FOR HUMAN EXPOSURE

**Table 6-4. Ongoing Research Regarding the Environmental Fate and Exposure to Ethylbenzene**

Investigator	Affiliation	Description	Sponsor
Thrall KD	Battelle Pacific Northwest Laboratories, Richland, Washington	The overall research objective for this project is to expand prior studies to evaluate the percutaneous absorption of compounds commonly encountered within similar industries (styrene and ethylbenzene) along with focused studies to evaluate the dermal bioavailability of compounds with both lipophilic and hydrophilic properties.	NIOSH
Burke J	EPA	The development of a human exposure model has been initiated to characterize population exposures to air toxics in support of risk assessment activities in the National Air Toxics Program. This research will develop probabilistic inputs for exposure to chemicals such as benzene and ethylbenzene for use in the model.	EPA

EPA = Environmental Protection Agency; NIOSH = National Institute for Occupational Safety and Health

Source: FEDRIP 2007

6. POTENTIAL FOR HUMAN EXPOSURE

This page is intentionally blank.

## 7. ANALYTICAL METHODS

The purpose of this chapter is to describe the analytical methods that are available for detecting, measuring, and/or monitoring ethylbenzene, its metabolites, and other biomarkers of exposure and effect to ethylbenzene. The intent is not to provide an exhaustive list of analytical methods. Rather, the intention is to identify well-established methods that are used as the standard methods of analysis. Many of the analytical methods used for environmental samples are the methods approved by federal agencies and organizations such as EPA and the National Institute for Occupational Safety and Health (NIOSH). Other methods presented in this chapter are those that are approved by groups such as the Association of Official Analytical Chemists (AOAC) and the American Public Health Association (APHA). Additionally, analytical methods are included that modify previously used methods to obtain lower detection limits and/or to improve accuracy and precision.

### 7.1 BIOLOGICAL MATERIALS

Ethylbenzene can be determined in biological fluids, and tissues, and breath using a variety of analytical methods. Representative methods are summarized in Table 7-1. Most analytical methods for biological fluids and tissues use headspace gas chromatographic (GC) analysis. Breath samples are usually collected on adsorbent traps or in sampling bags or canisters, and then analyzed by GC.

The headspace method involves equilibrium of volatile analytes such as ethylbenzene between a liquid or solid sample phase and the gaseous phase. The gaseous phase is then analyzed by GC. There are two main types of headspace methodology: static (equilibrium) headspace and dynamic headspace, which is usually called the "purge-and-trap" method (Seto 1994). The static headspace technique is relatively simple, but may be less sensitive than the purge-and-trap method. The purge-and-trap method, while providing increased sensitivity, requires more complex instrumentation and may result in artifact formation (Seto 1994). Generally, an inert gas such as helium is passed over the biological sample at elevated temperature, and the purged volatile organic compound (VOC) is trapped onto an adsorbent polymeric resin (Tenax). The organic compound is thermally desorbed from the adsorbent followed by identification and quantitation using various detectors; flame ionization detection (FID) and mass spectrometry (MS) are used most often. Other sample preparation methods have been used, but less frequently. Solvent extraction permits concentration, thereby increasing sensitivity, but the extraction solvent can interfere with analysis. Direct aqueous injection is a very rapid method, but sensitivity is low and matrix effects can be a serious problem.

## 7. ANALYTICAL METHODS

**Table 7-1. Analytical Methods for Determining Ethylbenzene in Biological Samples**

Sample matrix	Preparation method	Analytical method	Sample detection limit	Percent recovery	Reference
Whole blood	Whole blood samples were collected by venipuncture, sealed, and refrigerated. Extraction accomplished using a closed system purge and trap sampler	Capillary GC/MS	0.015–0.020 ppb	114–118	Ashley et al. 1992, 1994
Blood	Direct analysis via inertial spray extraction interface	GC/MS	<1 ppb	No data	St-Germain et al. 1995
Blood	Automated head space	Capillary GC/FID	0.002 µg/mL	90–110 (estimated)	Otson and Kumarathasan 1995
Blood	Extraction using dynamic headspace purge and trap system followed by thermal desorption to the GC	cap GC/FID	50 ng/L (calculated)	39	Fustinoni et al. 1996
Urine	Purge and trap	Capillary GC/MS	No data	64–123 for model compounds	Michael et al. 1980
Urine	Extraction using dynamic headspace purge and trap system followed by thermal desorption to the GC	Capillary GC/FID	50 ng/L (calculated)	61	Fustinoni et al. 1996
Mother's milk	Purge and trap	Capillary GC/MS	No data	35–88 for model compounds	Michael et al. 1980
Brain tissue (post mortem)	Modified headspace (full evaporation technique)	Capillary GC-ITD	0.038 nmoles/sample	80–120	Schuberth 1996
Fat tissue	Add saline; freeze; thaw to 0 °C prior to analysis; add CS <sub>2</sub> ; inject into GC	GC/FID; confirmation GC/MS	No data	No data	Wolff et al. 1977
Adipose tissue	Purge and trap	Capillary GC/MS	No data	13–80 for halogenated hydrocarbons	Michael et al. 1980
Breath	Collection via spirometer into passivated canisters	Capillary GC/MS	low µg/m <sup>3</sup> levels	77–82	Thomas et al. 1991
Breath	Collection via spirometer onto charcoal traps; microwave desorption	Capillary GC/MS-SIM	0.2 µg/m <sup>3</sup> (1 L sampled)	No data	Riedel et al. 1996

FID = flame ionization detector; GC = gas chromatography; HPLC = high performance liquid chromatography; ITD = ion trap detector; MS = mass spectrometry; SIM = selected ion monitoring

## 7. ANALYTICAL METHODS

A spirometer is usually used for the collection of breath samples. The device is used to provide clean air for inhalation and a mechanism for pumping exhaled breath into the collection media (Pellizzari et al. 1985). The breath samples are collected into Tedlar bags with subsequent adsorption onto Tenax traps (Pellizzari et al. 1985) or into passivated stainless steel canisters (Thomas et al. 1991). The Tenax traps are analyzed by thermal desorption GC techniques, and canister samples are analyzed by GC as well.

A sensitive and reliable method for identification and quantitation of ethylbenzene in samples of whole blood taken from humans following exposure to VOCs has been developed by Ashley and coworkers at the Centers for Disease Control and Prevention (Ashley et al. 1992, 1994). The method involves purge-and-trap of a 10-mL blood sample with analysis by capillary GC/MS. Anti-foam procedures were used, as well as special efforts to remove background levels of VOCs from reagents and equipment (Ashley et al. 1992). The method is sensitive enough (ppt levels) to determine background levels of VOCs in the population and provides adequate accuracy (114–118% recovery) and precision (16–44% relative standard deviation [RSD]) for monitoring ethylbenzene in the population.

Few methods are available for the determination of ethylbenzene in body fluids and tissues other than blood. A modified dynamic headspace method for urine, mother's milk, and adipose tissue has been reported (Michael et al. 1980). Volatiles swept from the sample are analyzed by capillary GC/FID. Acceptable recovery was reported for model compounds, but detection limits were not reported (Michael et al. 1980). Ethylbenzene in brain tissue may be determined using a headspace, capillary/ion trap detector (ITD) technique (Schuberth 1996). Recovery was good (80–120%) as was precision ( $\approx 20\%$  RSD); the detection limit was reported as 4 ng/sample (0.038 nmoles) (Schuberth 1996).

Sensitive, reliable methods are available for measuring ethylbenzene in breath. Exhaled breath is collected using a spirometer. The exhaled breath is collected into Tedlar bags for later transfer to adsorption tubes (Wallace et al. 1982), into passivated canisters (Thomas et al. 1991), or directly onto adsorbent traps (Riedel et al. 1996). The spirometer system, using adsorption onto Tenax traps and analysis by thermal desorption/capillary GC/MS techniques, was field-tested over the course of a very large exposure study (EPA 1987). The quantitation limit was  $\approx 1 \mu\text{g}/\text{m}^3$ , recovery was 91–100%, and the precision for duplicate samples was  $\leq 30\%$  RSD (EPA 1987). Advances in the methodology include development of a more compact system with collection in 1.8-L canisters (Thomas et al. 1992). Recovery of ethylbenzene is 92–104%, precision for duplicate samples is  $< 3\%$  RSD, and the detection limit was estimated as  $3 \mu\text{g}/\text{m}^3$  for ethylbenzene (Thomas et al. 1992).

## 7. ANALYTICAL METHODS

**7.2 ENVIRONMENTAL SAMPLES**

Methods are available for determining ethylbenzene in a variety of environmental matrices. A summary of representative methods is shown in Table 7-2. Validated methods, approved by agencies and organizations such as EPA, ASTM, APHA, and NIOSH, are available for air, water, and solid waste matrices. Gas chromatography is the most widely used analytical technique for quantifying concentrations of ethylbenzene in environmental matrices. Various detection devices used for GC include FID, MS, and the photoionization detector (PID). Because of the complexity of the sample matrix and the low concentration of VOCs in most environmental media, sample preconcentration is generally required prior to GC analysis. Air samples may be collected and concentrated on adsorbent or in canisters for subsequent analysis. Methods suitable for determining trace amounts of ethylbenzene in aqueous and other environmental media include three basic approaches to the pretreatment of the sample: gas purge-and-trap technique, headspace gas analysis, and extraction with organic solvent.

Gas purge-and-trap is the most widely used method for the isolation and concentration of VOCs in environmental samples (Lesage 1993). The purge-and-trap technique offers advantages over other techniques in that it allows facile isolation and concentration of target compounds, thereby improving overall limits of detection and recovery of sample. Detection limits of <1 µg of ethylbenzene per liter of sample have been achieved (APHA 1995c; EPA 1984c, 1991e, 1992a). A serious drawback of this technique, particularly for quantitative analysis, is interference by impurities found in the stripping gas (EPA 1994c).

A purge-and-trap method with GC/FID analysis (Otson and Williams 1982) or GC/MS (Otson and Chan 1987) has been reported for the analysis and quantitation of ethylbenzene in environmental samples. Detection limits of <0.1 µg/L for GC/FID analysis and 0.1 µg/L were reported. Accuracy was also good, 74–88% (Otson and Chan 1987; Otson and Williams 1982).

Extraction with organic solvents (liquid-liquid extraction) provides a simple, rapid screening method for semi-quantitative determination of ethylbenzene in aqueous samples containing limited number of VOCs, but is less effective for aqueous samples containing large numbers of VOCs. Furthermore, interference from the organic extraction solvent (hexane) makes it more difficult to completely identify all components (Karasek et al. 1987; Otson and Williams 1981).

## 7. ANALYTICAL METHODS

**Table 7-2. Analytical Methods for Determining Ethylbenzene in Environmental Samples**

Sample matrix	Preparation method	Analytical method	Sample detection limit	Percent recovery	Reference
Occupational air	Collection on charcoal adsorbent tube; desorption with CS <sub>2</sub>	GC/FID	0.001–0.01 mg/sample <sup>a</sup>	Bias -7.6%	NIOSH 1994a (NIOSH Method 1501)
Ambient air	Collection on Tenax adsorbent; thermal desorption	Capillary GC/MS	20 ng estimated <sup>a</sup>	No data	EPA 1988a (Method TO-1)
Ambient air	Collection in passivated stainless steel canisters	Capillary GC/MS or PID or FID	No data	No data	EPA 1988b (Method TO-14)
Ambient air	Collection on Tenax adsorbent; thermal desorption	Capillary GC/MS	2 ng <sup>a</sup>	No data	Pellizzari et al. 1993 (IARC Method 6)
Ambient air	Collection in canisters	GC/MS	0.2 ppbv	bias -8.1%	McClenny and Fortune 1995 (CLP Method)
Ambient air	Collection on multisorbent traps; automated preconcentration	Capillary GC/MS	0.036 ppbv	102	Oliver et al. 1996
Ambient air	Collection on multisorbent traps; thermal desorption with modified cryofocussing	Capillary GC/FID	0.25 ppbv	98	Oliver et al. 1996
Indoor air	Collection on Tenax adsorbent; thermal desorption	GC/MS	0.05–0.2 µg/m <sup>3</sup>	No data	Kostianinen 1995
In-vehicle air	Collection on Tenax or multisorbent traps; thermal desorption	Capillary GC/MS-SIM	No data	No data	Lawryk and Weisel 1996
Flue gas	Collection on adsorbent traps using probe; thermal desorption	Capillary GC/FID	0.05 µg/m <sup>3</sup> (estimated)	No data	Jay and Steiglitz 1995
Product emissions	Collection on charcoal traps; desorption with CS <sub>2</sub>	Capillary GC/FID	No data	No data	Wadden et al. 1995
Tobacco smoke	Collection on multisorbent traps; thermal desorption	fused-silica PLOT column GC/MS	No data	No data	Barrefors and Petersson 1993
Snow	SPME using DVB-coated PDMS fiber with a film thickness of 65 µm	GC/MS	0.20 µg/L	No data	Kos and Ariya 2006

## 7. ANALYTICAL METHODS

**Table 7-2. Analytical Methods for Determining Ethylbenzene in Environmental Samples**

Sample matrix	Preparation method	Analytical method	Sample detection limit	Percent recovery	Reference
Drinking water	Purge and trap	GC/PID	0.01–0.04 µg/L	98–101	EPA 1991d (EPA Method 502.2)
Drinking water	Purge and trap	GC/PID; confirmation on second column or GC/MS	0.002 µg/L	93	EPA 1991e (EPA Method 503.1)
Drinking water	Purge and trap	GC/MS	1–2 µg/L	No data	EPA 1991f (EPA Method 524.1)
Drinking water	Purge and trap	Capillary GC/MS	0.06 µg/L	96–99	EPA 1992a (EPA Method 524.2)
Drinking water	Purge and trap	GC/FID or GC/MS	low µg/L	84–114	ASTM 1999b (ASTM Method D 3871)
Drinking water	Direct injection	GC/FID	~1 mg/L	No data	ASTM 1999a (ASTM Method D 2908)
Waste water	Purge and trap	GC/PID; confirmation on second column	0.2 µg/L	98	EPA 1984c (EPA Method 602)
Waste water	Purge and trap	GC/MS	7.2 µg/L	100–103	EPA 1999 (EPA Method 624)
Water	Closed-loop stripping	Capillary GC/MS	50 ng/L (instrumental)	No data	APHA 1995a (Method 6040B)
Waste water	Purge and trap	GC/MS	7.2 µg/L		APHA 1995b (Method 6210B)
Waste water	Purge and trap	GC/PID; confirmation on second column or GC/MS	0.2 µg/L	93	APHA 1995c (Method 6220B)
Waste water	Purge and trap	GC/PID	0.01–0.05 µg/L	93	APHA 1995d (Method 6220C)
Solid waste	Direct injection or purge and trap	Capillary GC/PID	~1 µg/L (soil, sediment); ~0.1 mg/kg (wastes)	101	EPA 1994d (SW846 Method 8021A)
Solid waste	Purge and trap	Capillary GC/PID	~1 µg/L (soil, sediment); ~0.1 mg/kg (wastes)	101	EPA 1995a 9SW846 Method 8021B, proposed)



## 7. ANALYTICAL METHODS

**Table 7-2. Analytical Methods for Determining Ethylbenzene in Environmental Samples**

Sample matrix	Preparation method	Analytical method	Sample detection limit	Percent recovery	Reference
Solid waste	Purge and trap	Capillary GC/MS	~5 µg/kg (soil, sediment)	99	EPA 1994e (SW846 Method 8260A)
Solid waste	Various options including purge and trap, headspace, closed system vacuum distillation	Capillary GC/MS	purge and trap: ~5 µg/kg (soil and sediment); ~0.5 mg/kg (wastes)	90–112 (purge and trap)	EPA 1995b (SW846 Method 8260B, proposed)
Plant foliage	Solvent extraction; filtration	Capillary GC/SM-SIM	50 pg/µL extract	No data	Keymeulen et al. 1991
Fish	Solvent extraction; cleanup on florisil column; solvent microextraction	GC/FID	5 µg/g <sup>b</sup>	98–102	Karasek et al. 1987
Fish and sediment	Homogenization; freezing and vacuum extraction	Capillary GC/MS	25 ppb <sup>b</sup>	Sediments, 97 recovery; fish, 76% average for all analytes	Hiatt 1981, 1983
Eggs	Headspace	Capillary GC/PID; confirmation by GC/MS	0.002 µg/mL	94 (white); 49 (whole); 21 (yolk)	Stein and Narang 1990
Fruits and vegetables	Solvent extraction; filtration	Capillary GC/MS-SIM	No data	No data	Górna-Binkul et al. 1996
Olives and olive oil	Headspace	Capillary GC/MS	Low µg/kg levels	No data	Biedermann et al. 1995
Cooked meat	Azeotropic distillation using Kilens-Nickerson extractor	Capillary GC/MS	6 µg/kg	No data	Gramshaw and Vandenburg 1995
Food containers (polystyrene)	Incubation with DMF; headspace	Capillary GC/FID; confirmation GC/MS	10 ppm	96–102	Sugita et al. 1995

<sup>a</sup>Sample detection limit will depend upon volume sampled. Value is estimated instrumental detection limit.

<sup>b</sup>Method detection limits were not provided; estimates cited are based on lowest concentrations used for method performance evaluation.

CS<sub>2</sub> = carbon disulfide; DMF = dimethylformamide; DVB = divinylbenzene; FID = flame ionization detector; GC = gas chromatography; MeOH = methanol; MS = mass spectrometry; PDMS = polydimethylsiloxane; PID = photoionization detector; PLOT = porous-layer open tubular; SIM = selected ion monitoring; SPME = solid phase microextraction; UV = ultraviolet spectrophotometry

## 7. ANALYTICAL METHODS

Ethylbenzene may be determined in occupational air using collection on multisorbent cartridges, solvent desorption and analysis by GC/FID (NIOSH 1994a). Accuracy is very good (-7.6% bias); detection limits depend upon the amount of air sampled. Ambient air samples may also be collected on adsorbent traps (EPA 1988a; Pellizzari et al. 1993) or in stainless steel canisters (EPA 1988b; McClenny and Fortune 1995). Recovery for Tenax traps is very good, ranging from 91 to 100% (EPA 1987). Little information on accuracy is available for multisorbent traps, but good recovery (102%) has been reported (Oliver et al. 1996). Bias of -8.1% for canister collection has been reported (McClenny and Fortune 1995). Detection limits depend upon the amount of air sampled, but values in the sub-ppb range have been reported (Kostiainen 1995; McClenny and Fortune 1995; Oliver et al. 1996).

Purge-and-trap methodology is used most often for determination of ethylbenzene in water and hazardous wastes (Lesage 1993). The method was developed by Bellar and Lichtenberg (1974) for waste water. An inert gas is bubbled through the sample to strip out volatile components. The analytes in the gas stream are adsorbed onto sorbent traps, then thermally desorbed into the GC column. Very low detection limits for drinking water are reported for the purge-and-trap method with GC/PID (0.002–0.04 µg/L) (EPA 1991e). Accuracy is very good (93–101% recovery) (EPA 1991e). While the method is quite selective, confirmation using a second GC column or GC/MS is recommended (EPA 1991e). A sensitive (0.06 µg/L) and reliable method (96–99% recovery; <10% RSD) for drinking water uses capillary column GC/MS (EPA 1992a). Purge-and-trap methodology with analysis by GC/PID or GC/MS is used for waste waters (APHA 1995b, 1995c, 1995d; EPA 1984c, 1999). The detection limits are lower for GC/PID (0.2 µg/L) (EPA 1984c) than for GC/MS (7.2 µg/L) (EPA 1984b), but confirmation on a second column is recommended (EPA 1984c) when PID is used. Recovery and precision are very good (98–103% recovery; ≤10% RSD) (EPA 1984c, 1999).

Soil, sediment, and solid waste samples are difficult to analyze. Volatilization during sample handling and homogenization can result in ethylbenzene losses. The wet sample is usually dispersed in a solvent, then added to water for purge-and-trap/GC analysis (EPA 1994c). Capillary GC/PID or GC/MS analysis provides detection limits in the low ppb range for soil and sediment and in the sub-ppm range for solid wastes (EPA 1994d, 1994e, 1995a, 1995b).

Few methods are available for the determination of ethylbenzene in fish and biota. A method for the determination of ethylbenzene in fish at low ppm levels using solvent extraction with GC/FID analysis has been reported (Karasek et al. 1987). A procedure to identify and quantify ethylbenzene in fish samples by vacuum distillation with capillary column GC/MS has been reported (Hiatt 1981, 1983).

## 7. ANALYTICAL METHODS

Recovery of 98–102% from spiked fish tissue was reported, but detection limits were not reported (Hiatt 1981). Purge-and-trap/capillary GC/MS has also been used for the determination of ethylbenzene in fish. Performance data for fish tissue samples were not reported (Dreisch and Munson 1983).

Few methods are available for the determination of ethylbenzene in food. Available methods involve solvent extraction (Górna-Binkul et al. 1996), headspace purge (Biedermann et al. 1995), and azeotropic distillation (Gramshaw and Vandenburg 1995) followed by capillary GC/MS or GC/PID analysis. Detection limits are in the low  $\mu\text{g}/\text{kg}$  range (Biedermann et al. 1995; Gramshaw and Vandenburg 1995). Little performance data are available. Recoveries from 21% (egg yolk) to 94% (egg white) were reported for headspace/capillary GC/PID analysis of eggs (Stein and Narang 1990).

Screening methods and field-portable methods may be useful analytical tools. Soil screening for petroleum hydrocarbons, including ethylbenzene, can be conducted using immunoassay procedures (EPA 1995e). Sensitivity is in the ppm range. Solid phase microextraction (SPME) has been tested as a screening method for water (Shirey 1995). The method is used in conjunction with capillary GC techniques. Portable GCs have been used for field monitoring of air (Berkley et al. 1991), water (Driscoll and Atwood 1993), soil (Driscoll and Atwood 1993), and hazardous waste (Overton et al. 1995). There are several studies that compare portable GC methods with laboratory methods (Berkley et al. 1991; Driscoll and Atwood 1993).

### 7.3 ADEQUACY OF THE DATABASE

Section 104(i)(5) of CERCLA, as amended, directs the Administrator of ATSDR (in consultation with the Administrator of EPA and agencies and programs of the Public Health Service) to assess whether adequate information on the health effects of ethylbenzene is available. Where adequate information is not available, ATSDR, in conjunction with NTP, is required to assure the initiation of a program of research designed to determine the health effects (and techniques for developing methods to determine such health effects) of ethylbenzene.

The following categories of possible data needs have been identified by a joint team of scientists from ATSDR, NTP, and EPA. They are defined as substance-specific informational needs that if met would reduce the uncertainties of human health assessment. This definition should not be interpreted to mean that all data needs discussed in this section must be filled. In the future, the identified data needs will be evaluated and prioritized, and a substance-specific research agenda will be proposed.

## 7. ANALYTICAL METHODS

**7.3.1 Identification of Data Needs****Methods for Determining Biomarkers of Exposure and Effect.**

**Exposure.** Exposure to ethylbenzene can be determined by the detection of mandelic acid and phenylglycolic acid in urine or by direct detection of ethylbenzene in human blood. Environmental exposures to ethylbenzene can result in detectable levels in human tissues. Existing methods for the determination of ethylbenzene in blood have the sensitivity necessary (0.008–0.012 ppb) (Ashley et al. 1992) to detect and measure low to trace levels of ethylbenzene in blood that might be present in the general population, as well as concentrations of ethylbenzene that might be associated with specific health effects. Methods for measurement of ethylbenzene in exhaled breath are sensitive enough (low  $\mu\text{g}/\text{m}^3$ ) (Thomas et al. 1991) to provide background levels of ethylbenzene in the general population as well as to measure exposure. Additional performance information would be helpful, as would further development of a portable breath collection system. Information on levels of ethylbenzene in tissues is limited and the existing methods are not as well characterized. Improvements in the sensitivity of the methods for measuring concentrations of ethylbenzene in tissues and additional performance data would be helpful.

Methods for measuring metabolites and biomarkers for ethylbenzene are shown in Table 7-3. Methods exist for measuring ppm levels of ethylbenzene metabolites in urine (Ogata and Taguchi 1987, 1988; Sollenberg et al. 1985). They are sufficiently sensitive for measuring occupational exposure to ethylbenzene. These analytical methods are reliable and precise, but may not be sensitive enough to measure non-occupational exposure. Improvements in the sensitivity of the methods for measuring concentrations of ethylbenzene in tissues, and improvements in the sensitivity for measurement of metabolites in urine would allow better assessment of the correlation between levels in these media and observed health effects.

**Effect.** No specific biomarkers of effect for ethylbenzene were identified.

**Methods for Determining Parent Compounds and Degradation Products in Environmental**

**Media.** Sensitive methods are available for measuring background levels of ethylbenzene in air, water, and wastes, the media of most concern for exposure of the general population and those populations located near hazardous waste sites. Few methods are available for measuring levels of ethylbenzene in fish, plants and biota. Detection limits in the low ppb range have been reported (Dreich and Munson

## 7. ANALYTICAL METHODS

**Table 7-3. Analytical Methods for Determining Biomarkers of Ethylbenzene in Biological Materials**

Sample matrix	Sample preparation	Analytical method	Sample detection limit	Accuracy percent recovery	Reference
Urine (MA)	Dilution; centrifugation	HPLC/UV	MA 5 ng injected	MA 100–102	Ogata and Taguchi 1988
Urine (MA and PGA)	MeOH addition; centrifugation	HPLC	PGA $8.5 \times 10^3$ $\mu\text{g/L}$ MA $10 \times 10^3$ $\mu\text{g/L}$	PGA 101 MA 102.6	Ogata and Taguchi 1987
Urine (MA and PGA)	Filtration; solvent extraction; evaporation and dissolution	HPLC/UV	MA, PGA $1.5 \times 10^3$ $\mu\text{g/L}$	No data	Sollenberg et al. 1985
Urine (MA and PGA)	Filtration; solvent extraction; evaporation and dissolution	ITP	MA $6.1 \times 10^3$ $\mu\text{g/L}$ PGA $3.0 \times 10^3$ $\mu\text{g/L}$	No data	Sollenberg et al. 1985

HPLC = high performance liquid chromatography; ITP = isotachopheresis; MA = mandelic acid; PGA = phenylglyoxylic acid; UV = ultraviolet (detection)

## 7. ANALYTICAL METHODS

1983; Hiatt 1981; Karasek et al. 1987; Keymeulen et al. 1991), but other performance data are generally lacking. Few methods are available for measuring levels of ethylbenzene in food. Little performance data are available for the available methods. Although several good analytical methods are available for detecting ethylbenzene in some environmental media, validated, reliable methods for measuring ethylbenzene in fish and foods are needed. These would be helpful in evaluating the potential for human exposure and health effects that might result from ethylbenzene contamination.

Methods for detecting environmental degradation products of ethylbenzene in environmental media are summarized in Table 7-4. Although methods are available for detecting major environmental degradation products (1-phenylethanol, acetophenone, benzaldehyde, for example) in reaction mixtures, it is not known whether these methods have the sensitivity and specificity for application to environmental media. Sensitive, reliable methods for determining degradation products in air, water, and waste would be helpful.

### 7.3.2 Ongoing Studies

The Environmental Health Laboratory Sciences Division of the National Center for Environmental Health, Centers for Disease Control and Prevention, is developing methods for the analysis of ethylbenzene and other volatile organic compounds in blood. These methods use purge and trap methodology, high-resolution gas chromatography, and magnetic sector mass spectrometry, which give detection limits in the low ppt range.

## 7. ANALYTICAL METHODS

**Table 7-4. Analytical Methods for Determining Environmental Degradation Products of Ethylbenzene**

Sample matrix	Preparation method	Analytical method	Sample detection limit	Accuracy per-cent recovery	Reference
Reaction mixtures	Solvent extraction; concentration	Capillary GC/FID	No data	No data	Ehrhardt and Petrick 1984
Reaction mixtures	Centrifugation; solvent extraction; concentration	GC/FID; confirmation GC/MS	No data	No data	Fukuda et al. 1989

FID = flame ionization detector; GC = gas chromatography; MS = mass spectrometry

7. ANALYTICAL METHODS

This page is intentionally blank.



## 8. REGULATIONS AND ADVISORIES

The international and national regulations and guidelines pertaining to ethylbenzene in air, water, and other media are summarized in Table 8-1.

ATSDR has derived an acute-duration inhalation MRL of 10 ppm for ethylbenzene based on a NOAEL of 300 ppm and a LOAEL of 400 ppm for significant deterioration of auditory thresholds and significant losses of outer hair cells in the organ of Corti in rats exposed 8 hours/day for 5 days (Cappaert et al. 2000). The MRL was derived by dividing the NOAEL<sub>HEC</sub> of 300 ppm by an uncertainty factor of 30 (3 for animal to human extrapolation with dosimetric adjustment and 10 for human variability).

ATSDR has derived an intermediate-duration inhalation MRL of 0.7 ppm for ethylbenzene based on a LOAEL of 200 ppm for significant loss of outer hair cells in the organ of Corti in rats exposed for 6 hours/day, 6 days/week for 13 weeks (Gagnaire et al. 2007). The MRL was derived by dividing the LOAEL<sub>HEC</sub> of 200 ppm by an uncertainty factor of 300 (10 for use of a LOAEL, 3 for animal to human extrapolation with dosimetric adjustment, and 10 for human variability).

ATSDR has derived a chronic-duration inhalation MRL of 0.3 ppm for ethylbenzene based on a LOAEL of 75 ppm for a significant increase in the severity of nephropathy in female rats exposed to ethylbenzene by inhalation for 5 days/week, 6 hours/day, for 104 weeks (NTP 1999). The MRL was derived by dividing the LOAEL<sub>HEC</sub> of 75 ppm by an uncertainty factor of 300 (10 for use of a LOAEL, 3 for animal to human extrapolation with dosimetric adjustment, and 10 for human variability).

ATSDR has derived an intermediate-duration oral MRL of 0.5 mg/kg/day for ethylbenzene based on a BMDL<sub>10</sub> of 48.2 mg/kg/day for hepatotoxicity (centrilobular hepatocyte hypertrophy) in male rats exposed to ethylbenzene by gavage for 13 weeks (Mellert et al. 2007). The MRL was derived by dividing the BMDL<sub>10</sub> of 48.2 mg/kg/day by an uncertainty factor of 100 (10 for animal to human extrapolation with dosimetric adjustment and 10 for human variability).

The EPA oral reference dose (RfD) for ethylbenzene is 0.1 mg/kg/day, based on the LOAEL for liver and kidney toxicity in rats administered 291 mg/kg/day ethylbenzene via gavage 5 days/week for 182 days (Wolf et al. 1956). The RfD was calculated by dividing the NOAEL of 97 mg/kg/day by an uncertainty factor of 1,000 (10 for use of a subchronic study, 10 for interspecies extrapolation, and 10 for intraspecies variability).

## 8. REGULATIONS AND ADVISORIES

The EPA inhalation reference concentration (RfC) for ethylbenzene is 1 mg/m<sup>3</sup> (equivalent to 0.23 ppm), based on developmental toxicity seen in rats and rabbits exposed to 4,340 mg/m<sup>3</sup> (IRIS 2007). The ATSDR intermediate-duration inhalation MRL of 0.3 ppm is comparable to the EPA RfC.

The EPA has classified ethylbenzene as Group D (not classifiable as to human carcinogenicity), due to the lack of animal bioassays and human studies (IRIS 2007). IARC (2006) has classified ethylbenzene as a Group 2B carcinogen (possibly carcinogenic to humans). NTP has not classified ethylbenzene for its carcinogenicity.

## 8. REGULATIONS AND ADVISORIES

**Table 8-1. Regulations and Guidelines Applicable to Ethylbenzene**

Agency	Description	Information	Reference
<u>INTERNATIONAL</u>			
Guidelines:			
IARC	Carcinogenicity classification	Group 2B <sup>a</sup>	IARC 2006
WHO	Air quality guidelines	No data	WHO 2000
	Drinking water quality guidelines	0.3 mg/L <sup>b</sup>	WHO 2004
<u>NATIONAL</u>			
Regulations and Guidelines:			
a. Air			
ACGIH	TLV (8-hour TWA)	100 ppm	ACGIH 2006
	STEL (15-minute TWA)	125 ppm	
EPA	AEGL-1, -2, -3	No data	EPA 2007a
	Hazardous air pollutant	Yes	EPA 2007c 42 USC 7412
NIOSH	REL (10-hour TWA)	100 ppm	NIOSH 2005
	STEL (15-minute TWA)	125 ppm	
	IDLH	800 ppm	
OSHA	PEL (8-hour TWA) for general industry	100 ppm	OSHA 2006c 29 CFR 1910.1000
	PEL (8-hour TWA) for shipyard industry	100 ppm	OSHA 2006a 29 CFR 1915.1000
	PEL (8-hour TWA) for construction industry	100 ppm	OSHA 2006b 29 CFR 1926.55, Appendix A
b. Water			
EPA	Designated as hazardous substances in accordance with Section 311(b)(2)(A) of the Clean Water Act	Yes	EPA 2007b 40 CFR 116.4
	Designated as a toxic pollutant pursuant to Section 307(a)(1) of the Clean Water Act	Yes	EPA 2007g 40 CFR 401.15
	Drinking water standards and health advisories		EPA 2006a
	1-Day health advisory for a 10-kg child	30 mg/L	
	10-Day health advisory for a 10-kg child	3 mg/L	
	DWEL	3 mg/L	
	Lifetime	0.7 mg/L	
	10 <sup>-4</sup> Cancer risk	No data	

## 8. REGULATIONS AND ADVISORIES

**Table 8-1. Regulations and Guidelines Applicable to Ethylbenzene**

Agency	Description	Information	Reference
<b>NATIONAL (cont.)</b>			
EPA	National primary drinking water standards		EPA 2003
	MCLG	0.7 mg/L	
	MCL	0.7 mg/L <sup>c</sup>	
	Public health goal	0.7 mg/L	
	Reportable quantities of hazardous substances designated pursuant to Section 311 of the Clean Water Act	1,000 pounds	EPA 2007d 40 CFR 117.3
	Water quality criteria for human health consumption of:		EPA 2006b
	Water + organism	0.53 mg/L	
	Organism only	2.1 mg/L	
c. Food			
EPA	Inert pesticide ingredients in pesticide products	List 2 <sup>d</sup>	EPA 2004
FDA	Bottled water requirement	0.7 mg/L	FDA 2006a 21 CFR 165.110
	EAFUS	No data	FDA 2007b
d. Other			
ACGIH	Carcinogenicity classification	A3 <sup>e</sup>	ACGIH 2006
	Biological exposure indices (end of shift at end of workweek); sum of mandelic acid and phenyl glyoxylic acid in urine	1.5 g/g creatinine <sup>f</sup>	
EPA	Carcinogenicity classification	Class D <sup>g</sup>	IRIS 2007
	Oral slope factor	No data	
	Inhalation unit risk	No data	
	RfC	1 mg/m <sup>3</sup>	
	RfD	0.1 mg/kg/day	
	Master Testing List	Yes <sup>h</sup>	EPA 2007j
	Superfund, emergency planning, and community right-to-know		
	Designated CERCLA hazardous substance	Yes <sup>i</sup>	EPA 2007e 40 CFR 302.4
	Reportable quantity	1,000 pounds	
	Effective date of toxic chemical release reporting	01/01/87	EPA 2007f 40 CFR 372.65
	TSCA health and safety data reporting requirements	Yes	EPA 2007h 40 CFR 716.120

## 8. REGULATIONS AND ADVISORIES

**Table 8-1. Regulations and Guidelines Applicable to Ethylbenzene**

Agency	Description	Information	Reference
<b>NATIONAL</b> ( <i>cont.</i> )			
NTP	Carcinogenicity classification	No data	NTP 2005

<sup>a</sup>Group 2B: possibly carcinogenic to humans

<sup>b</sup>Concentrations of the substance at or below the health based guideline value may affect the appearance, taste, or odor of the water, leading to consumer complaints.

<sup>c</sup>Potential health effects from exposure above the MCL include liver or kidneys problems; and the common sources of contaminant in drinking water is from the discharge from petroleum refineries.

<sup>d</sup>List 2: potentially toxic other ingredients and high priority for testing inerts

<sup>e</sup>A3: confirmed animal carcinogen with unknown relevance to humans

<sup>f</sup>ACGIH (2006) has submitted notice of intended changes for ethylbenzene in which the BEI will be lowered to 0.7 g/g creatinine.

<sup>g</sup>Class D: not classifiable as to human carcinogenicity

<sup>h</sup>Ethylbenzene was recommended to the Master Testing List (MTL) by the U.S. EPA's Office of Pollution Prevention and Toxics on the basis of the Screening Information Data Sets (SIDS). Styrene was added to the MTL in 1993 and the chemical testing program is currently underway by way of a VTA. The testing needs include health effects, environmental effects, and environmental fate and exposure. The Office of Air and Radiation recommended ethylbenzene to the MTL in 1995 on the basis that ethylbenzene is a hazardous air pollutant. EPA is in the process of determining the testing needs for the following: acute toxicity, neurotoxicity, developmental toxicity, reproductive, and immunotoxicity

<sup>i</sup>Designated CERCLA hazardous substance pursuant to Section 311(b)(2) and Section 307(a) of the Clean Water and Section 112 of the Clean Air Act.

ACGIH = American Conference of Governmental Industrial Hygienists; AEGL = Acute Exposure Guideline Levels; BEI = biological exposure indices; CERCLA = Comprehensive Environmental Response, Compensation, and Liability Act; CFR = Code of Federal Regulations; DWEL = drinking water equivalent level; EAFUS = Everything Added to Food in the United States; EPA = Environmental Protection Agency; FDA = Food and Drug Administration; IARC = International Agency for Research on Cancer; IDLH = immediately dangerous to life or health; IRIS = Integrated Risk Information System; MCL = maximum contaminant level; MCLG = maximum contaminant level goal; NIOSH = National Institute for Occupational Safety and Health; NTP = National Toxicology Program; OSHA = Occupational Safety and Health Administration; PEL = permissible exposure limit; REL = recommended exposure limit; RfC = inhalation reference concentration; RfD = oral reference dose; STEL = short-term exposure limit; TLV = threshold limit values; TSCA = Toxic Substances Control Act; TWA = time-weighted average; USC = United States Code; WHO = World Health Organization

8. REGULATIONS AND ADVISORIES

This page is intentionally blank.

## 9. REFERENCES

Abdul AS, Gibson TL, Rai DN. 1987. Statistical correlations for predicting the partition coefficient for nonpolar organic contaminants between aquifer organic carbon and water. *Haz Waste Haz Mat* 4:211-222.

Abraham M, Ibrahim A. 2006. Air to fat and blood to fat distribution of volatile organic compounds and drugs: Linear free energy analyses. *Eur J Med Chem* 41(12):1430-1438.

Abraham MH, Hassanisadi M, Jalali-Heravi M, et al. 2003. Draize rabbit eye test compatibility with eye irritation thresholds in humans: A quantitative structure-activity relationship analysis. *Toxicol Sci* 76(2):384-391.

\*Abraham MH, Ibrahim A, Acree WE. 2005. Air to blood distribution of volatile organic compounds: A linear free energy analysis. *Chem Res Toxicol* 18(5):904-911.

Abraham MH, Kumarsingh R, Cometto-Muniz JE, et al. 1998a. An algorithm for nasal pungency thresholds in man. *Arch Toxicol* 72:227-232.

Abraham MH, Kumarsingh R, Cometto-Muniz JE, et al. 1998b. Draize eye scores and eye irritation thresholds in man combined into one quantitative structure-activity relationship. *Toxicol In Vitro* 12:403-408.

\*ACGIH. 1992. 1992-1993 Threshold limit values for chemical substances and physical agents and biological exposure indices. Cincinnati, OH: American Conference of Governmental Industrial Hygienists, 21.

ACGIH. 1996. Ethylbenzene. Threshold limit values for chemical substances and physical agents and biological exposure indices. Cincinnati, OH: American Conference of Governmental Industrial Hygienists, 22.

\*ACGIH. 2002. Ethylbenzene. Documentation of the threshold limit values for chemical substances and physical agents and biological exposure indices. 7th ed. Cincinnati, OH: American Conference of Governmental Industrial Hygienists.

\*ACGIH. 2006. Ethylbenzene. Threshold limit values for chemical substances and physical agents and biological exposure indices. Cincinnati, OH: American Conference of Governmental Industrial Hygienists, 29, 104.

\*Acton DW, Barker JF. 1992. In situ biodegradation potential of aromatic hydrocarbons in anaerobic groundwaters. *J Contam Hydrol* 9:325-352.

\*Adinolfi M. 1985. The development of the human blood-CSF-brain barrier. *Dev Med Child Neurol* 27(4):532-537.

---

\* Cited in text

+ Cited in supplemental document

## 9. REFERENCES

\*Adlercreutz H. 1995. Phytoestrogens: Epidemiology and a possible role in cancer protection. *Environ Health Perspect Suppl* 103(7):103-112.

Admans G, Takahashi T, Ban S, et al. 2001. Artificial neural network for predicting the toxicity of organic molecules. *Bull Chem Soc Jpn* 74:2451-2461.

AFCEE. 1999a. Recommendation for no further investigation at study area 6 (SA 6). San Antonio, TX: U.S. Air Force Center for Environmental Excellence. ADA381656.

AFCEE. 1999b. Treatability study in support of intrinsic remediation for fire protection training area 3. San Antonio, TX: U.S. Air Force Center for Environmental Excellence. ADA382789.

AFRL. 2001a. Comparison of time-averaged concentrations measured at fixed locations and painters' breathing zones during aircraft spray painting in conditions of straight-through and recirculating ventilation. U.S. Air Force Research Laboratory. AFRLMLTYTP20010033. ADA392941.

AFRL. 2001b. Total petroleum hydrocarbon criteria working group (TPHCWG) field demonstration report: Elmendorf Air Force Base, Alaska. Wright-Patterson AFB, OH: U.S. Air Force Research Laboratory. AFRLHEWPTR20010118. ADA424194.

AFRL. 2002. Total petroleum hydrocarbon criteria working group (TPHCWG) field demonstration report: Air Force Number 6 Fuel Farm, Dobbins AFB, GA. Wright-Patterson AFB, OH: U.S. Air Force Research Laboratory. AFRLHEWPTR20020158. ADA425422.

AFRL. 2003. Total petroleum hydrocarbon criteria working group (TPHCWG) field demonstration report: IRP site 4, POL area, Springfield ANG Base, Springfield, OH: Wright Patterson AFB, OH: U.S. Air Force Research Laboratory. AFRLHEWPTR20030099. ADA425111.

\*Agency for Toxic Substances and Disease Registry. 1989. Decision guide for identifying substance-specific data needs related to toxicological profiles; Notice. Agency for Toxic Substances and Disease Registry, Division of Toxicology. *Fed Regist* 54(174):37618-37634.

\*Agency for Toxic Substances and Disease Registry. 1990. Biomarkers of organ damage or dysfunction for the renal, hepatobiliary and immune systems. Subcommittee on Biomarkers of Organ Damage and Dysfunction. Atlanta, GA: Agency for Toxic Substances and Disease Registry.

\*Agency for Toxic Substances and Disease Registry. 1992. Toxicological profile for styrene. Agency for Toxic Substances and Disease Registry. <http://www.atsdr.cdc.gov/toxprofiles/tp53.pdf>. August 02, 2007.

\*Agency for Toxic Substances and Disease Registry. 1995. Toxicological profile for gasoline. Agency for Toxic Substances and Disease Registry. <http://www.atsdr.cdc.gov/toxprofiles/tp72.html>. August 14, 2007.

Agency for Toxic Substances and Disease Registry. 2005. Notice of the revised priority list of hazardous substances that will be the subject of toxicological profiles. *Fed Regist* 70:72840-72842.

Alarie Y. 1981. Bioassay for evaluating the potency of airborne sensory irritants and predicting acceptable levels of exposure in man. *Food Cosmet Toxicol* 19:623-626.



## 9. REFERENCES

- Alarie Y, Nielson GD, Abraham MH. 1998a. A theoretical approach to the Ferguson principle and its use with non-reactive and reactive airborne chemicals. *Pharmacol Toxicol* 83(6):270-279.
- Alarie Y, Schaper M, Nielsen GD, et al. 1998b. Structure-activity relationships of volatile organic chemicals as sensory irritants. *Arch Toxicol* 72:125-140.
- Alarie Y, Wakisaka I, Oka S. 1973. Sensory irritation by sulfur dioxide and chlorobenzylidene malononitrile. *Environ Physiol Biochem* 3:53-64.
- Al-Gailany KAS, Houston JB, Bridges JW. 1977. The role of substrate lipophilicity in determining type 1 microsomal P450 binding characteristics. *Biochem Pharmacol* 27:783-788.
- Almgren M, Grieser F, Powell JR, et al. 1979. A correlation between the solubility of aromatic hydrocarbons in water and micellar solution, with their normal boiling points. *J Chem Eng Data* 24:285-287.
- \*Altman PL, Dittmer DS. 1974. *Biological handbooks: Biology data book*. Vol. III. 2nd ed. Bethesda, MD: Federation of American Societies for Experimental Biology, 1987-2008, 2041.
- Altshuller AP, Bellar TA. 1963. Gas chromatographic analysis of hydrocarbons in the Los Angeles atmosphere. *J Air Pollut Control Assoc* 13:81-87.
- Altshuller AP, Lonneman WA, Sutterfield FD, et al. 1971. Hydrocarbon composition of the atmosphere of the Los Angeles basin - 1967. *Environ Sci Technol* 5:1009-1016.
- American Chemistry Council. 2003a. A pilot inhalation study for a reproductive toxicity study of ethylbenzene in rats. Submitted to the U.S. Environmental Protection Agency under TSCA Section 8(e). 8EHQ-1202-15228 B. 89030000085.
- American Chemistry Council. 2003b. Pilot inhalation toxicity study for a 2-generation reproductive study in rats. Submitted to the U.S. Environmental Protection Agency under TSCA Section 8(e). 8EHQ-1003-15228 C. 89040000022.
- American Chemistry Council. 2003c. Pilot inhalation study for a reproductive toxicity study of ethylbenzene in rats. Submitted to the U.S. Environmental Protection Agency under TSCA Section FYI. FYI-0903-01462 A. 84030000029.
- \*Amoore JE, Hautala E. 1983. Odor as an aid to chemical safety: Odor thresholds compared with threshold limit values and volatilities for 214 industrial chemicals in air and water dilution. *J Appl Toxicol* 3:272-290.
- \*Andersen ME, Krishnan K. 1994. Relating *in vitro* to *in vivo* exposures with physiologically based tissue dosimetry and tissue response models. In: Salem H, ed. *Animal test alternatives: Refinement, reduction, replacement*. New York: Marcel Dekker, Inc., 9-25.
- \*Andersen ME, MacNaughton MG, Clewell HJ, et al. 1987. Adjusting exposure limits for long and short exposure periods using a physiological pharmacokinetic model. *Am Ind Hyg Assoc J* 48(4):335-343.
- Andersen P. 1953. Inhibitory reflexes elicited from the trigeminal and olfactory nerves in rabbits. *Acta Physiol Scand* 30:137-148.

## 9. REFERENCES

- +\*Andersson K, Fuxe K, Nilsen OG, et al. 1981. Production of discrete changes in dopamine and noradrenaline levels and turnover in various parts of the rat brain following exposure to xylene, *ortho*-, *meta*-, and *para*-xylene, and ethylbenzene. *Toxicol Appl Pharmacol* 60:535-548.
- \*Aneja VP. 1993. Organic compounds in cloud water and their deposition at a remote continental site. *J Air Waste Manage Assoc* 43:1239-1244.
- \*Angerer J, Lehnert G. 1979. Occupational chronic exposure to organic solvents. *Int Arch Occup Environ Health* 43:145-150.
- \*Angerer J, Wulf H. 1985. Occupational chronic exposure to organic solvents. XI. Alkylbenzene exposure of varnish workers: Effects on hematopoietic system. *Int Arch Occup Environ Health* 56:307-321.
- \*Anid PJ, Alvarez PJJ, Vogel TM. 1993. Biodegradations of monoaromatic hydrocarbons in aquifer columns amended with hydrogen peroxide and nitrate. *Wat Res* 27(4):685-691.
- +\*Antoine SR, DeLeon IR, O'Dell-Smith RM. 1986. Environmentally significant volatile organic pollutants in human blood. *Bull Environ Contam Toxicol* 36:364-371.
- \*APHA. 1995a. Method 6040 B. Closed-loop stripping, gas chromatography/mass spectrometric analysis. In: Eaton AD, Clesceri LS, Greenberg AE, eds. *Standard methods for the examination of water and wastewater*. Washington, DC: American Public Health Association. American Water Works Association. Water Environmental Federation, 6-7 to 6-16.
- \*APHA. 1995b. Method 6210 B. Purge and trap packed-column gas chromatographic/mass spectrometric method I. In: Eaton AD, Clesceri LS, Greenberg AE, eds. *Standard methods for the examination of water and wastewater*. Washington, DC: American Public Health Association. American Water Works Association. Water Environmental Federation, 6-17 to 6-25.
- \*APHA. 1995c. Method 6220 B. Purge and trap gas chromatographic method I. In: Eaton AD, Clesceri LS, Greenberg AE, eds. *Standard methods for the examination of water and wastewater*. Washington, DC: American Public Health Association. American Water Works Association. Water Environmental Federation, 6-39 to 6-41.
- \*APHA. 1995d. Method 6220 C. Purge and trap gas chromatographic method II. In: Eaton AD, Clesceri LS, Greenberg AE, eds. *Standard methods for the examination of water and wastewater*. Washington, DC: American Public Health Association. American Water Works Association. Water Environmental Federation, 6-42 to 6-46.
- Aquatic Life Advisory Committee of the Ohio River Valley Water Sanitation Committee. 1960. Aquatic life water quality criteria: Third progress report. *J Water Pollut Control Fed* 32:65-82.
- \*Ashley DL, Prah JD. 1997. Time dependence of blood concentrations during and after exposure to a mixture of volatile organic compounds. *Arch Environ Health* 52(1):26-33.
- +\*Ashley DL, Bonin MA, Cardinali FL. 1992. Determining volatile organic compounds in human blood from a large sample production by using purge and trap gas chromatography-mass spectrometry. *Anal Chem* 64(9):1021-1029.

## 9. REFERENCES

- \*Ashley DL, Bonin MA, Cardinali FL, et al. 1994. Blood concentration of volatile organic compounds in a nonoccupationally exposed U.S. population and in groups with suspected exposure. *Clin Chem* 40(7):1401-1409.
- +\*Ashley DL, Bonin MA, Hamar B, et al. 1995. Removing the smoking confounder from blood volatile organic compounds measurements. *Environ Res* 7(1):39-45.
- \*Assmuth T, Kalevi K. 1992. Concentrations and toxicological significance of trace organic compounds in municipal solid waste landfill gas. *Chemosphere* 24(9):1207-1216.
- \*ASTER. 1995. ASTER (Assessment Tools for the Evaluation of Risk) ecotoxicity profile. Duluth, MN: U.S. Environmental Protection Agency, Environmental Research Laboratory.
- \*ASTM. 1999a. D 2908-91. Standard practice for measuring volatile organic matter in water by aqueous-injection gas chromatography. In: Allen RF, Baldini NC, Donofrio et al., eds. 1999 Annual book of ASTM standards. Vol. 11.02. Section 11: Water and environmental technology, 168-173.
- \*ASTM. 1999b. D 3871-84. Standard test method for purgeable organic compounds in water using headspace sampling. In: Allen RF, Baldini NC, Donofrio PE, et al., eds. 1999 Annual book of ASTM standards. Vol. 11.02. Section 11: Water and environmental technology, 348-358.
- \*Atkinson R, Carter WPL. 1984. Kinetics and mechanisms of the gas-phase reactions of ozone with organic compounds under atmospheric conditions. *Chem Rev* 84:437-470.
- \*Atkinson R, Aschmann SM, Winer AM. 1987. Kinetics of the reactions of NO<sub>3</sub> radicals with a series of aromatic compounds. *Environ Sci Technol* 21:1123-1126.
- \*Atkinson R, Darnall KR, Pitts JN. 1978. Rate constraints for reaction of OH radicals and ozone with cresols at 300±1 K. *J Phys Chem* 82:2759-2761.
- \*Backer LC, Egeland GM, Ashley DL, et al. 1997. Exposure to regular gasoline and ethanol oxyfuel during refueling in Alaska. *Environ Health Perspect* 105(8):850-855.
- +Backes WL, Sequeira DJ, Cawley GF, et al. 1993. Relationship between hydrocarbon structure and induction of P450: Effects on protein levels and enzyme activities. *Xenobiotica* 23(12):1353-1366.
- +\*Bakke OM, Scheline RR. 1970. Hydroxylation of aromatic hydrocarbons in the rat. *Toxicol Appl Pharmacol* 16:691-700.
- Banerjee S. 1985. Calculation of water solubility of organic compounds with UNIFAC-derived parameters. *Environ Sci Technol* 19:369-370.
- Banerjee S, Howard PH. 1988. Improved estimation of solubility and partitioning through correction of UNIFAC-derived activity coefficients. *Environ Sci Technol* 22:839-841.
- Bardodej Z, Bardodejova E. 1961. [Value and application of exposure tests. X. Exposure test for ethylbenzene.] *Ceskoslovenska Hygiena* 6:537-545. (Czechoslovakian)
- +\*Bardodej Z, Bardodejova E. 1970. Biotransformation of ethylbenzene, styrene, and alpha-methylstyrene in man. *Am Ind Hyg Assoc J* 31:206-209.

## 9. REFERENCES

- +\*Bardodej Z, Cirek A. 1988. Long-term study on workers occupationally exposed to ethylbenzene. *J Hyg Epidemiol Microbiol Immunol* 32:1-5.
- \*Barker JF. 1987. Volatile aromatic and chlorinated organic contaminants in groundwater at six Ontario landfills. *Water Pollut Res J Can* 22:33-48.
- Barker JF, Tessmann JS, Plotz PE, et al. 1986. The organic geochemistry of a sanitary landfill plume. *J Contam Hydrol* 1:171-189.
- \*Barnes DG, Dourson M. 1988. Reference dose (RfD): Description and use in health risk assessments. U.S. Environmental Protection Agency. *Regul Toxicol Pharmacol* 8:471-486.
- \*Barrefors G, Petersson G. 1993. Assessment of ambient volatile hydrocarbons from tobacco smoke and from vehicle emissions. *J Chromatogr* 643(1/2):71-76.
- Basak SC, Gute BD, Mills D, et al. 2003. Quantitative molecular similarity methods in the property/toxicity estimation of chemicals: A comparison of arbitrary versus tailored similarity spaces. *J Mol Struct (Theochem)* 622(1-2):127-145.
- \*Baun A, Jensen SD, Bjerg PL, et al. 2000. Toxicity of organic chemical pollution in groundwater downgradient of a landfill (Grindsted, Denmark). *Environ Sci Technol* 34:1647-1652.
- Bayer CW, Black MS. 1987. Capillary chromatographic analysis of volatile organic compounds in the indoor environment. *J Chromatogr Sci* 25:60-64.
- Beall JR, Ulsamer AG. 1981. Toxicity of volatile organic compounds present indoors. *Bull NY Acad Med* 57:978-996.
- \*Beavers JD, Himmelstein JS, Hammond SK, et al. 1996. Exposure in a household using gasoline-contaminated water: A pilot study. *J Occup Environ Med* 38(1):35-38.
- Bedding ND, McIntyre AE, Perry R, et al. 1982. Organic contaminants in the aquatic environment: I. Sources and occurrence. *Sci Total Environ* 25:143-167.
- Beliveau M, Krishnan K. 2000a. Concentration dependency of rat blood: Air partition coefficients of some volatile organic chemicals. *J Toxicol Environ Health A* 60:377-389.
- Beliveau M, Krishnan K. 2000b. Estimation of rat blood: Air partition coefficients of volatile organic chemicals using reconstituted mixtures of blood components. *Toxicol Lett* 116:183-188.
- Beliveau M, Lipscomb J, Tardif R, et al. 2005. Quantitative structure-property relationships for interspecies extrapolation of the inhalation pharmacokinetics of organic chemicals. *Chem Res Toxicol* 18(3):475-485.
- Beliveau M, Tardif R, Krishnan K. 2003. Quantitative structure-property relationships for physiologically based pharmacokinetic modeling of volatile organic chemicals in rats. *Toxicol Appl Pharmacol* 189(3):221-232.
- \*Bellar TA, Lichtenberg JJ. 1974. Determining volatile organics at microgram-per-liter levels by gas chromatography. *J Am Water Works Assoc* 66:739-744.

## 9. REFERENCES

- Bergamaschi E, Brustolin A, DePalma G, et al. 1999. Biomarkers of dose and susceptibility in cyclists exposed to monoaromatic hydrocarbons. *Toxicol Lett* 108(2-3):241-247.
- \*Berger GS, ed. 1994. Epidemiology of endometriosis. In: *Endometriosis: Advanced management and surgical techniques*. New York, NY: Springer-Verlag, 3-7.
- Bergeron RM, Desai K, Serron SC, et al. 1999. Changes in the expression of cytochrome P450s 2B1, 2B2, 2E1 and 2C11 in response to daily aromatic hydrocarbon treatment. *Toxicol Appl Pharmacol* 157:1-8.
- Bergeron RM, Serron SC, Rinehart JJ, et al. 1998. Pituitary component of the aromatic hydrocarbon-mediated expression of CYP2B and CYP2C11. *Xenobiotica* 28(3):303-312.
- \*Berkley RE, Varns JL, Pleil J. 1991. Comparison of portable gas chromatographs and passivated canisters for field sampling airborne toxic organic vapors in the United States and the USSR. *Environ Sci Technol* 25(8):1439-1444.
- Berglund RL, Whipple GM. 1987. Predictive modeling of organic emissions. *Chem Eng Prog* 83:46-54.
- +Bernard AM, De Russis R, Normand J-C, et al. 1989. Evaluation of the subacute nephrotoxicity of cyclohexane and other industrial solvents in the female Sprague-Dawley rat. *Toxicol Lett* 45(2/3):271-280.
- Bertsch W, Anderson E, Holzer G. 1975. Trace analysis of organic volatiles in water by gas chromatography-mass spectrometry with glass capillary columns. *J Chromatogr* 112:701-718.
- Bertsch W, Chang RC, Zlatkis A. 1974. The determination of organic volatiles in air pollution studies: Characterization of profiles. *J Chromatogr Sci* 12:175-182.
- Beskid O, Dusek Z, Solansky I, et al. 2006. The effects of exposure to different clastogens on the pattern of chromosomal aberrations detected by FISH whole chromosome painting in occupationally exposed individuals. *Mutat Res* 594(1-2):20-29.
- \*Bestetti G, Galli E. 1984. Plasmid-coded degradation of ethylbenzene and 1-phenylethanol in *Pseudomonas fluorescens*. *FEMS Microbiology Letters* 21:165-168.
- +Bevan MAJ, Proctor CJ, Baker-Rogers J. 1991. Exposure to carbon monoxide, respirable suspended particulates, and volatile organic compounds while commuting by bicycle. *Environ Sci Technol* 25(4):788-791.
- \*Biedermann M, Grob K, Morchio G. 1995. On the origin of benzene, toluene, ethylbenzene and xylene in extra virgin olive oil. *Z Lebensm Unters Forsch* 200:266-272.
- \*Blank IH, McAuliffe DJ. 1985. Penetration of benzene through human skin. *J Invest Dermatol* 84:522-526.
- \*Blank IH, Scheuplein RJ. 1969. Transport into and within the skin. *Brit J Dermatol* 81(Supp 4):4-10.
- Blinova VG, Kharchevnikova NV. 2000. Toxicity of substituted benzenes predicted using the JSM method of automated hypothesis generation and quantum-chemical calculations. *Pharm Chem J* 34(4):208-214.

## 9. REFERENCES

- Bocek K. 1976. Relationships among activity coefficients, partition coefficients and solubilities. *Experientia Suppl* 23:231-240.
- \*Bohon RL, Claussen WF. 1951. The solubility of aromatic hydrocarbons in water. *J Am Chem Soc* 73:1571-1578.
- Bond DL, Thodos G. 1960. Vapor pressures of alkyl aromatic hydrocarbons. *J Chem Eng Data* 5:289-292.
- \*Borden RC, Yanoschak TM. 1990. Ground and surface water quality impacts of North Carolina sanitary landfills. *Water Resour Bull* 26(2):269-277.
- \*Borden RC, Black DC, McBleif KV. 2002. MTBE and aromatic hydrocarbons in North Carolina stormwater runoff. *Environ Pollut* 118:141-152.
- Bos R, Goudena EJG, Guicherit R, et al. 1978. Atmospheric precursors and oxidants concentrations in the Netherlands. In: Guicherit R, ed. *Photochemical smog formation in the Netherlands*. Delft, The Netherlands: TNO Research Institute for Environmental Hygiene, 20-59.
- Bos R, Guicherit R, Hoogveen A. 1977. Distribution of some hydrocarbons in ambient air near Delft and the influence on the formation of secondary air pollutants. *Sci Total Environ* 7:269-281.
- Botton S, Parsons JR. 2006. Degradation of BTEX compounds under iron-reducing conditions in contaminated aquifer microcosms. *Environ Toxicol Chem* 25(10):2630-2638.
- \*Bouwer EJ, McCarty PL. 1983. Transformations of halogenated organic compounds under denitrification conditions. *Appl Environ Microbiol* 45:1295-1299.
- \*Bouwer EJ, McCarty PL. 1984. Modeling of trace organics biotransformation in the subsurface. *Ground Water* 22:433-440.
- \*Boyd SA, Xiangcan J, Lee J-F. 1990. Sorption of nonionic organic compounds by corn residues from a no-tillage field. *J Environ Qual* 19:734-738.
- Brass HJ. 1982. Procedures for analyzing organic contaminants in drinking water. *Am Water Works Assoc J* 74:107-112.
- Brooke DN, Dobbs AJ, Williams N. 1986. Octanol:water partition coefficients(P): Measurement, estimation, and interpretation, particularly for chemicals with P>105. *Ecotox Environ Safety* 11:251-260.
- \*Brown HS, Hattis D. 1989. The role of skin absorption as a route of exposure for volatile organic compounds (VOCs) in household tap water: A simulated kinetic approach. *J Am Coll Toxicol* 8(5):839-851.
- Brown RL, Wasik SP. 1974. A method of measuring the solubilities of hydrocarbons in aqueous solutions. *J Res Natl Bur Stand Sec A* 78:453-460.
- \*Budavari S, O'Neil MJ. 1989. Ethylbenzene. In: *The Merck index. An encyclopedia of chemicals, drugs, and biologicals*. 11th ed. Rahway, NJ: Merck & Co., Inc., 595.

## 9. REFERENCES

- \*Burback BL, Perry JJ. 1993. Biodegradation and biotransformation of groundwater pollutant mixtures by *Mycobacterium vaccae*. *Applied and Environmental Microbiology* 59(4):1025-1029.
- Burkhard LP, Kuehl DW. 1986. N-octanol/water partition coefficients by reverse phase liquid chromatography/mass spectrometry for eight tetrachlorinated planar molecules. *Chemosphere* 15:163-167.
- \*Burri J, Crockett R, Hany R, et al. 2004. Gasoline composition determined by <sup>1</sup>H NMR spectroscopy. *Fuel* 83(2):187-193.
- \*Burris DR, MacIntyre WG. 1984. Water solubility behavior of hydrocarbon mixtures implications for petroleum dissolution. In: Vandermeulen JH, Hruday SE, eds. *Oil in freshwater: Chemistry, biology, countermeasure technology*. New York, NY: Pergamon Press, 85-93.
- Buswell JA, Jurtschuk P. 1969. Microbial oxidation of hydrocarbons measured by oxygraphy (using a Clark oxygen electrode). *Arch Mikrobiol* 64:215-222.
- \*C&EN. 1994a. Production by the U.S. chemical industry: Growth continues in chemical production. *Chem Eng News* 72(27):30-36.
- \*C&EN. 1994b. Top 50 chemicals production rose modestly last year. *Chem Eng News* 72(15):12-15.
- \*C&EN. 1995. Production soared in most chemical sectors. *Chem Eng News* 73(26):38-42.
- \*C&EN. 2006. Production: Growth is the norm. Output of chemicals increased across most products and in most countries. *Chem Eng News*. July 10, 2006.
- Calabrese EJ. 1978. Pollutants and high-risk groups. The biological basis of increased human susceptibility to environmental and occupational pollutants. New York, NY: John Wiley and Sons, 186-193.
- \*Campbell JL, Fisher JW. 2007. A PBPK modeling assessment of the competitive metabolic interactions of JP-8 vapor with two constituents, m-xylene and ethylbenzene. *Inhal Toxicol* 19(3):265-273.
- Campbell JR, Luthy RG. 1985. Prediction of aromatic solute partition coefficients using the UNIFAC group contribution model. *Environ Sci Tech* 19:980-985.
- Canady WT, Robinson DA, Colby HD. 1974. A partition model for hepatic cytochrome P-450-hydrocarbon complex formation. *Biochem Pharmacol* 23:3075-3078.
- +\*Cappaert NLM, Klis SFL, Baretta AB, et al. 2000. Ethyl benzene-induced ototoxicity in rats: A dose-dependent mid-frequency hearing loss. *J Assoc Res Otolaryngol* 1(4):292-299.
- +\*Cappaert NLM, Klis SFL, Muijser H, et al. 1999. The ototoxic effects of ethyl benzene in rats. *Hear Res* 137:91-102.
- +\*Cappaert NLM, Klis SFL, Muijser H, et al. 2001. Simultaneous exposure to ethyl benzene and noise: Synergistic effects on outer hair cells. *Hear Res* 162(1-2):67-79.

## 9. REFERENCES

- +\*Cappaert NLM, Klis SFL, Muijser H, et al. 2002. Differential susceptibility of rats and guinea pigs to the ototoxic effects of ethyl benzene. *Neurotoxicol Teratol* 24(4):503-510.
- Cardoza TR, Rosa DP, Feiden IR, et al. 2006. Corrigendum to [Genotoxicity and toxicity assessment in urban hydrographic basins. *Mutation Research* 603:83-96]. *Mutat Res* 605(1-2):103.
- Chakraborty R, Coates JD. 2004. Anaerobic degradation of monoaromatic hydrocarbons. *Appl Microbiol Biotechnol* 64(4):437-446.
- Chambers DM, McElprang DO, Waterhouse MG, et al. 2006. An improved approach for accurate quantitation of benzene, toluene, ethylbenzene, xylene, and styrene in blood. *Anal Chem* 78:5375-5383.
- +Chan C, Lin S, Her G. 1994. Office worker's exposure to volatile organic compounds while commuting and working in Taipei City. *Atmos Environ* 28(14):2351-2359.
- Chan PC, Hasemani JK, Mahleri J, et al. 1998. Tumor induction in F344/N rats and B6C3F1 mice following inhalation exposure to ethylbenzene. *Toxicol Lett* 99(1):23-32.
- Chao J, Lin CT, Chung TH. 1983. Vapor pressure of coal chemicals. *J Phys Chem Ref Data* 12:1033-1063.
- \*Charest-Tardif G, Tardif R, Krishnan K. 2006. Inhalation pharmacokinetics of ethylbenzene in B6C3F1 mice. *Toxicol Appl Pharmacol* 210(1-2):63-69.
- \*Chen C, Taylor RT. 1995. Thermophilic biodegradation of BTEX by two *Thermus* species. *Biotechnol Bioeng* 48:614-624.
- \*Chen CS, Zoltek J. 1995. Organic priority pollutants in wetland-treated leachates at a landfill in central Florida. *Chemosphere* 31(6):3455-3464.
- +\*Chin BH, McKelvey JA, Calisti LJ, et al. 1980a. A comparison of *in vivo* and *in vitro* (tissue explant) techniques: Metabolic profile of ethylbenzene in the rat and the dog. *Bull Environ Contam Toxicol* 25:241-245.
- +\*Chin BJ, McKelvey JA, Tyler TR, et al. 1980b. Absorption, distribution, and excretion of ethylbenzene, ethylcyclohexane, and methylethylbenzene isomers in rats. *Bull Environ Contam Toxicol* 24:477-483.
- Chin YP, Weber WJ, Voice TC. 1986. Determination of partition coefficients and aqueous solubilities by reverse phase chromatography. II. Evaluation of partitioning and solubility models. *Water Res* 20:1443-1450.
- Chiou CT. 1985. Partition coefficients of organic compounds in lipid-water systems and correlations with fish bioconcentration factors. *Environ Sci Technol* 19:57-62.
- \*Chiou CT, Porter PE, Schmedding DW. 1983. Partition equilibria of nonionic organic compounds between soil organic matter and water. *Environ Sci Technol* 17:227-231.
- Chou CC, Riviere JE, Monteiro-Riviere NA. 2003. The cytotoxicity of jet fuel aromatic hydrocarbons and dose-related interleukin-8 release from human epidermal keratinocytes. *Arch Toxicol* 77:384-391.



## 9. REFERENCES

- Clark AI, McIntyre AE, Lester JN, et al. 1982. Evaluation of a Tenax GC sampling procedure for collection and analysis of vehicle-related aromatic and halogenated hydrocarbons in ambient air. *J Chromatogr* 252:147-157.
- Clark AI, McIntyre AE, Lester JN, et al. 1984a. Ambient air measurements of aromatic and halogenated hydrocarbons at urban, rural and motorway locations. *Sci Total Environ* 39:265-279.
- Clark AI, McIntyre AE, Perry R, et al. 1984b. Monitoring and assessment of ambient atmospheric concentrations of aromatic and halogenated hydrocarbons at urban, rural, and motorway locations. *Environ Pollut Series B* 7:141-158.
- Claus D, Walker N. 1964. The decomposition of toluene by soil bacteria. *J Gen Microbiol* 36:107-122.
- \*Clayton GD, Clayton FE, eds. 1981. *Patty's industrial hygiene and toxicology*. Vol. 2B. 3rd ed. New York, NY: John Wiley & Sons, Inc., 3303-3307.
- \*Clewell HJ, Andersen M. 1985. Risk assessment extrapolations and physiological modeling. *Toxicol Ind Health* 1(4):111-131.
- +\*Climie IJG, Hutson DH, Stoydin G. 1983. The metabolism of ethylbenzene hydroperoxide in the rat. *Xenobiotica* 13:611-618.
- \*CMR. 2004. Ethylbenzene. *Chemical Market Reporter*. July 14, 2007.
- \*Cole RH, Frederick RE, Healy RP, et al. 1984. Preliminary findings of the priority pollutant monitoring project of the nationwide urban runoff program. *J Water Pollut Control Fed* 56:898-908.
- Colenutt BA, Thorburn S. 1980. Gas chromatographic analysis of trace hydrocarbon pollutants in water samples. *Int J Environ Stud* 15:25-32.
- +\*Cometto-Muñiz JE, Cain WS. 1995. Relative sensitivity of the ocular trigeminal, nasal trigeminal and olfactory systems to airborne chemicals. *Chemical Senses* 20(2):191-198.
- +\*Conkle JP, Camp BJ, Welch BE. 1975. Trace composition of human respiratory gas. *Arch Environ Health* 30:290-295.
- \*Cotruvo JA. 1985. Organic micropollutants in drinking water: An overview. *Sci Total Environ* 47:7-26.
- Cox DP, Goldsmith CD. 1979. Microbial conversion of ethylbenzene to 1-phenethanol and acetophenone by *Nocardia tartaricans* ATCC 31190. *Appl Environ Microbiol* 38:514-520.
- +\*Cragg ST, Clarke EA, Daly IW, et al. 1989. Subchronic inhalation toxicity of ethylbenzene in mice, rats, and rabbits. *Fundam Appl Toxicol* 13(3):399-408.
- +\*Cramer PH, Boggess KE, Hosenfeld JM, et al. 1988. Determination of organic chemicals in human whole blood: Preliminary method development for volatile organics. *Bull Environ Contam Toxicol* 40:612-618.

## 9. REFERENCES

- Croute F, Poinot J, Gaubin Y, et al. 2002. Volatile organic compounds cytotoxicity and expression of HSP72, HSP90 and GRP78 stress proteins in cultured human cells. *Biochim Biophys Acta* 1591:147-155.
- Csanady GA, Filser JG. 2001. The relevance of physical activity for the kinetics of inhaled gaseous substances. *Arch Toxicol* 74(11):663-672.
- Cucco JA. 1987. A method of determining the efficiency of air sampling traps to collect and release volatile organic compounds. *Anal Lett* 20:223-234.
- Czerczak S, Kupczewska M. 2002. Assignment of skin notation for maximum allowable concentration (MAC) list in Poland. *Appl Occup Environ Hyg* 17(3):187-199.
- \*Daisey JM, Hodgson AT, Fisk WJ, et al. 1994. Volatile organic compounds in twelve California office buildings: Classes, concentrations and sources. *Atmos Environ* 28(22):3557-3562.
- Darnall KR, Lloyd AC, Winer AM, et al. 1976. Reactivity scale for atmospheric hydrocarbons based on reaction with hydroxyl radicals. *Environ Sci Technol* 10:692-696.
- Da Silva MLB, Alvarez PJJ. 2004. Enhanced anaerobic biodegradation of benzene-toluene-ethylbenzene-xylene-ethanol mixtures in bioaugmented aquifer columns. *Appl Environ Microbiol* 70(8):4720-4726.
- \*Dean BJ, Brooks TM, Hodson-Walker G, et al. 1985. Genetic toxicology testing of 41 industrial chemicals. *Mutat Res* 153:57-77.
- De Bortoli M, Knoepfel H, Pecchio E, et al. 1986. Concentrations of selected organic pollutants in indoor and outdoor air in northern Italy. *Environ Int* 12:343-350.
- +\*De Ceaurriz JC, Micillino JC, Bonnet P, et al. 1981. Sensory irritation caused by various industrial airborne chemicals. *Toxicol Lett (Amst)* 9:137-144.
- De Celis R, Feria-Velasco A, Gonzalez-Unzaga M, et al. 2000. Semen quality of workers occupationally exposed to hydrocarbons. *Fertil Steril* 73(2):221-228.
- \*Degirmenci E, Ono Y, Kawara O, et al. 2000. Genotoxicity analysis and hazardousness prioritization of a group of chemicals. *Water Sci Technol* 42(7-8):125-131.
- \*de Medinilla J, Espirgares M. 1988. Contamination by organic solvents in auto paint shops. *Am Occup Hyg* 31(4):509-513.
- \*Dennison JE, Andersen ME, Clewell HJ, et al. 2004. Development of a physiologically based pharmacokinetic model for volatile fractions of gasoline using chemical lumping analysis. *Environ Sci Technol* 38(21):5674-5681.
- \*Dennison JE, Andersen ME, Yang RSH. 2003. Characterization of the pharmacokinetics of gasoline using PBPK modeling with a complex mixtures chemical lumping approach. *Inhal Toxicol* 15:961-986.
- \*Dennison JE, Bigelow PL, Mumtaz MM, et al. 2005. Evaluation of potential toxicity from co-exposure to three CNS depressants (toluene, ethylbenzene, and xylene) under resting and working conditions using PBPK modeling. *J Occup Environ Hyg* 2(3):127-135.

## 9. REFERENCES

- Dewulf J, Van Langenhove H. 1997. Chlorinated C<sub>1</sub>- and C<sub>2</sub>-hydrocarbons and monocyclic aromatic hydrocarbons in marine waters: An overview on fate processes, sampling, analysis and measurements. *Water Research* 31(8):1825-1838.
- \*Dewulf J, Dewettinck T, De Visscher A, et al. 1996. Sorption of chlorinated C<sub>1</sub>- and C<sub>2</sub>-hydrocarbons and monocyclic aromatic hydrocarbons on sea sediment. *Water Research* 30 (12):3130-3138.
- de Wolf W, Lieder PH, Walker JD. 2004. Application of QSARs: Correlation of acute toxicity in the rat following oral or inhalation exposure. *QSAR Comb Sci* 23(7):521-525.
- \*Dilling WL, Bredeweg CJ, Tefertiller NB. 1976. Organic photochemistry. XIII. Simulated atmospheric photodecomposition rates of methylene chloride, 1,1,1-trichloroethane, trichloroethylene, tetrachloroethylene, and other compounds. *Environ Sci Technol* 10:351-356.
- DOT. 1990a. Hazardous materials table, special provisions, hazardous materials communications, emergency response information, and training requirements. U.S. Department of Transportation. Code of Federal Regulations. 49 CFR 172.101.
- DOT. 1990b. List of hazardous substances and reportable quantities. U.S. Department of Transportation. Code of Federal Regulations. CFR 172.101, App A.
- Dowty BJ, Laseter JL, Storer J. 1976. The transplacental migration and accumulation in blood of volatile organic constituents. *Pediatr Res* 10:696-701.
- \*Dreisch FA, Munson TO. 1983. Purge-and-trap analysis using fused silica capillary column GC/MS. *J Chromatogr Sci* 21:111-118.
- \*Driscoll N, Atwood ES. 1993. Application of gas chromatography with photoionization and electron-capture detectors for field screening of semi volatiles in soil and water. *J Chromatogr* 642:435-443.
- Drozd J, Novak J, Rijks JA. 1978. Quantitative and qualitative head-space gas analysis of parts per billion amounts of hydrocarbons in water: A study of model systems by capillary-column gas chromatography with splitless sample injection. *J Chromatogr* 158:471-482.
- Dueerksen-Hughes PJ, Yang J, Ozcan O. 1999. p53 induction as a genotoxic test for twenty-five chemicals undergoing *in vivo* carcinogenicity testing. *Environ Health Perspect* 107(10):805-812.
- +\*Dutkiewicz T, Tyras H. 1967. A study of the skin absorption of ethylbenzene in man. *Brit J Ind Med* 24:330-332.
- \*Dutkiewicz T, Tyras H. 1968. Skin absorption of toluene, styrene, and xylene by man. *Brit J Ind Med* 24:243.
- ECETOC. 1986. Joint assessment of commodity chemicals. No. 7: Ethylbenzene. Brussels, Belgium: European Chemical Industry Ecology and Toxicology Center.
- Edelson SB, Cantor DS. 1998. Autism: Xenobiotic influence. *Toxicol Ind Health* 14(6):799-811.

## 9. REFERENCES

- \*Ehret-Henry J, Ducruet V, Luciani A, et al. 1994. Styrene and ethylbenzene migration from polystyrene into dairy products by dynamic purge-and-trap gas chromatography. *J Food Sci* 59(5):990-1001.
- \*Ehrhardt M, Petrick G. 1984. On the sensitized photo-oxidation of alkylbenzenes in seawater. *Mar Chem* 15:47-58.
- \*Eiceman GA, McConnon JT, Zaman M, et al. 1986. Hydrocarbons and aromatic hydrocarbons in groundwater surrounding an earthen waste disposal pit for produced water in the Duncan oil field of New Mexico. *Int J Environ Anal Chem* 24:143-162.
- \*Eisenreich SJ, Looney BB, Thornton JD. 1981. Airborne organic contaminants in the Great Lakes ecosystem. *Environ Sci Technol* 15(1):30-38.
- Elcombe CR, Bridges JW, Gray TJ, et al. 1975. Studies on the interaction of safrole with rat hepatic microsomes. *Biochem Pharmacol* 24:1427-1433.
- Elke K, Jermann E, Begerow J, et al. 1998. Determination of benzene, toluene, ethylbenzene and xylenes in indoor air at environmental levels using diffusive samplers in combination with headspace solid-phase microextraction and high-resolution gas chromatography-flame ionization detection. *J Chromatogr A* 826:191-200.
- \*Ellenson WD, Mukerjee S, Stevens RK, et al. 1997. An environmental scoping study in the lower Rio Grande Valley of Texas: II. Assessment of transboundary pollution transport and other activities by air quality monitoring. *Environ Int* 23(5):643-655.
- \*El Masri AM, Smith JN, Williams RT. 1958. The metabolism of alkylbenzenes: Phenylacetylene and phenylethylene (styrene). *Biochem J* 68(2):199-204.
- +\*El Masry AM, Smith JN, Williams RT. 1956. The metabolism of alkylbenzenes: *n*-Propylbenzene and *n*-butylbenzene with further observations on ethylbenzene. *Biochem J* 64:50-56.
- +\*Elovaara E, Engstrom K, Nickels J, et al. 1985. Biochemical and morphological effects of long-term inhalation exposure of rats to ethylbenzene. *Xenobiotica* 15:299-308.
- +\*Elovaara E, Engstrom K, Vainio H, et al. 1982. Unaltered metabolism of *m*-xylene in the presence of ethylbenzene. In: Hietanen E, Laitinen M, Hanninen O, eds. *Cytochrome P-450, biochemistry, biophysics and environmental implications*. Amsterdam, The Netherlands: Elsevier Biomedical Press, 765-768.
- +\*Elovaara E, Engstrom K, Vainio H. 1984. Metabolism and disposition of simultaneously inhaled *m*-xylene and ethylbenzene in the rat. *Toxicol Appl Pharmacol* 75:466-478.
- Engelhardt G, Schwind K-R, Mussler B. 2004. The testing of chemicals in the Syrian hamster embryo (SHE) cell transformation assay for assessment of carcinogenic potential. *Toxicol In Vitro* 18(2):213-218.
- \*Engelke M, Bergmann U, Diehl HA. 1993. Fluidity of the microsomal membrane and cytochrome P450 reduction kinetics of pig liver microsomes as a consequence of organic solvent impact. *Xenobiotica* 23(1):71-78.

## 9. REFERENCES

- +\*Engstrom J, Bjurstrom R. 1978. Exposure to xylene and ethylbenzene. II. Concentration in subcutaneous adipose tissue. *Scand J Work Environ Health* 4:195-203.
- +\*Engstrom K, Elovaara E, Aitio A. 1985. Metabolism of ethylbenzene in the rat during long-term intermittent inhalation exposure. *Xenobiotica* 15:281-286.
- +\*Engstrom K, Riihimaki V, Laine A. 1984. Urinary disposition of ethylbenzene and *m*-xylene in man following separate and combined exposure. *Int Arch Occup Environ Health* 54:355-363.
- +Engstrom KM. 1984. Metabolism of inhaled ethylbenzene in rats. *Scand J Work Environ Health* 10:83-87.
- Enzminger JD, Ahlert RC. 1987. Environmental fate of polynuclear aromatic hydrocarbons in coal tar. *Environ Technol Lett* 8:269-278.
- EPA. 1973. Guidelines establishing test procedures for analysis of pollutants. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 136, App A.
- EPA. 1978. Designation of hazardous substances. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 116.4.
- EPA. 1979a. Non-urban hydrocarbon concentrations in ambient air north of Houston, Texas. Research Triangle Park, NC: U.S. Environmental Protection Agency. EPA500379010, 38.
- EPA. 1979b. Toxic pollutants. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 401.15.
- \*EPA. 1981. Engineering handbook for hazardous waste incineration. Cincinnati, OH: U.S. Environmental Protection Agency, Office of Solid Waste. PB81248163.
- \*EPA. 1982. Aquatic fate process data for organic priority pollutants. Washington, DC: U.S. Environmental Protection Agency, Office of Water Regulations and Standards, Monitoring and Data Support Division. EPA440481014.
- EPA. 1984a. Application for permit to discharge wastewater: Existing manufacturing, commercial, mining, and silvicultural operations. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 125.
- \*EPA. 1984b. Health effects assessment for ethylbenzene. Cincinnati, OH: U.S. Environmental Protection Agency, Environmental Criteria and Assessment Office. EPA540186008.
- \*EPA. 1984c. Method 602: Purgeable aromatics. Guidelines establishing test procedures for the analysis of pollutants under the Clean Water Act; final rule and interim final rule and proposed rule. U.S. Environmental Protection Agency. *Fed Regist* 49(209):40-48.
- EPA. 1984d. Method 624. Guidelines establishing test procedures for the analysis of pollutants under the Clean Water Act; final rule and interim final rule and proposed rule. U.S. Environmental Protection Agency. 40 CFR Part 136.

## 9. REFERENCES

- +\*EPA. 1984e. Analyses of exhaled breath of 355 urban residents for volatile organic compounds. Indoor Air. Vol. 4. Chemical characterization and personal exposure. Proceedings of the 3<sup>rd</sup> International Conference on Indoor Air Quality and Climate held in Stockholm on August 20-24, 1984. U.S. Environmental Protection Agency. PB85104214, 15-20.
- EPA. 1985a. Maximum contaminant level goals. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 141.50.
- EPA. 1985b. Drinking water criteria document for ethylbenzene. Cincinnati, OH: U.S. Environmental Protection Agency, Environmental Criteria and Assessment Office. PB86117835.
- EPA. 1985c. Determination of reportable quantities. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 117.3.
- EPA. 1985d. Synthetic organic compound sampling survey of public water supplies. Washington, DC: U.S. Environmental Protection Agency. PB85214427AS, 38.
- +\*EPA. 1986a. Broad scan analysis of the FY82 national human adipose tissue survey specimens. Vol. I. Executive summary. Washington, DC: U.S. Environmental Protection Agency, Office of Toxic Substances. EPA566586035.
- EPA. 1986b. General pretreatment regulations for existing and new sources of pollution. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 403, Appendix B.
- EPA. 1986c. Reference values for risk assessment (Final draft). Cincinnati, OH: U.S. Environmental Protection Agency, Office of Solid Waste. ECAOCIN477.
- EPA. 1986d. Test methods for evaluating solid waste SW-846. U.S. Environmental Protection Agency.
- \*EPA. 1987. Project summary. The total exposure assessment methodology (TEAM) study: Summary and analysis. U.S. Environmental Protection Agency, Office of Research and Development. EPA600687002.
- \*EPA. 1988a. Method T01-1. Method for the determination of volatile organic compounds in ambient air using tenax adsorption and gas chromatography mass spectrometry (GC/MS). Compendium of Methods for the Determination of Toxic Organic Compounds in Ambient Air. U.S. Environmental Protection Agency. EPA600489017.
- \*EPA. 1988b. Method T014-1. Determination of volatile organic compounds (VOCs) in ambient air using SUMMA passivated canister sampling and gas chromatographic analysis. Compendium of Methods for the determination of toxic organic compounds in ambient air. U.S. Environmental Protection Agency. EPA600489017.
- \*EPA. 1988c. National ambient volatile organic compounds (VOCs) data base update. Research Triangle Park, NC: U.S. Environmental Protection Agency, Atmospheric Sciences Research Laboratory. EPA600388010A.
- EPA. 1988d. Recommendations for and documentation of biological values for use in risk assessment. U.S. Environmental Protection Agency. EPA600687008.

## 9. REFERENCES

- EPA. 1989a. Interim methods for development of inhalation reference doses. Washington, DC: U.S. Environmental Protection Agency, Office of Health and Environmental Assessment. EPA600888066F.
- EPA. 1989b. National primary and secondary drinking water regulations. U.S. Environmental Protection Agency. Fed Regist 54:22062-22160.
- \*EPA. 1990a. Interim methods for development of inhalation reference concentrations. Washington, DC: U.S. Environmental Protection Agency, Office of Health and Environmental Assessment, Office of Research and Development, Environmental Criteria and Assessment Office. EPA600890066A. PB90238890.
- EPA. 1990b. Standards of performance for volatile organic compounds (VOC) emissions from synthetic organic chemical manufacturing industry (SOCMI) distillation operation. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 60.667.
- EPA. 1991a. National primary drinking water regulations. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 141.61.
- EPA. 1991b. Constituents for detection monitoring. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 258, App 1.
- EPA. 1991c. List of hazardous inorganic and organic constituents. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 258, App II.
- \*EPA. 1991d. Method 502.2. Volatile organic compounds in water by purge and trap capillary column gas chromatography with photoionization and electrolytic conductivity detectors in series. Methods for the determination of organic compounds in drinking water. U.S. Environmental Protection Agency. EPA600488039.
- \*EPA. 1991e. Method 503.1. Volatile aromatic and unsaturated organic compounds in water by purge and trap gas chromatography. Methods for the determination of organic compounds in drinking water. U.S. Environmental Protection Agency. EPA600488039.
- \*EPA. 1991f. Method 524.1. Measurement of purgeable organic compounds in water by packed column gas chromatography/mass spectrometry. Revision 3.0. In: Methods for the determination of organic compounds in drinking water. Cincinnati, OH: U.S. Environmental Protection Agency, 253-282. EPA600488039. PB91231480.
- \*EPA. 1991g. Alpha<sub>2u</sub>-Globulin: Association with chemically induced renal toxicity and neoplasia in the male rat. Washington, DC: U.S. Environmental Protection Agency. EPA625391019F.
- \*EPA. 1992a. Method 524.2. Measurement of purgeable organic compounds in water by capillary column gas chromatography mass spectrometry. Methods for the determination of organic compounds in drinking water. Supplement II. U.S. Environmental Protection Agency. EPA600R92129.
- EPA. 1992b. National air toxics information clearinghouse: NATICH data base report on state, local and EPA air toxics activities. Research Triangle Park, NC: U.S. Environmental Protection Agency, Office of Air Quality Planning and Standards, Emissions Standards Division. EPA453R92008.
- \*EPA. 1992c. Hazardous wastes from non-specific sources. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 261.31.

## 9. REFERENCES

EPA. 1992d. Applicability of treatment standards. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 268.40.

EPA. 1992e. Waste specific prohibitions-solvent wastes. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 268.30.

EPA. 1993a. Electroplating point source category. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 413.02.

EPA. 1993b. Pretreatment standards for existing sources (PSES). U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 414.25.

EPA. 1993c. Pretreatment standards for existing sources (PSES). U.S. Environmental Protection Agency. 40 CFR 414.35.

EPA. 1993d. Pretreatment standards for existing sources (PSES). U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 414.45.

EPA. 1993e. Pretreatment standards for existing sources (PSES). U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 414.55.

EPA. 1993f. Toxic pollutant effluent limitations and standards for direct discharge point sources that do not use end-of-pipe biological treatment. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 414.101.

EPA. 1993g. Toxic pollutant effluent limitations and standards for direct discharge point sources that use end-of-pipe biological treatment. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 414.91.

EPA. 1993h. General pretreatment regulations for existing and new sources of pollution. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 403, App G.

EPA. 1993j. Pretreatment standards for new sources (PSNS). U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 423.17.

EPA. 1993k. Steam electric power generating point source category. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 423, App A.

EPA. 1994a. National emissions standards for organic hazardous air pollutants from synthetic organic chemical manufacturing industry. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 63.106.

\*EPA. 1994c. Measurement of reformulated gasoline fuel parameters. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 80.46.

\*EPA. 1994d. Method 8021A. Halogenated volatiles by gas chromatography using photoionization and electrolytic conductivity detectors in series: Capillary column technique. SW-846. Final update II. 3rd ed. U.S. Environmental Protection Agency.



## 9. REFERENCES

- \*EPA. 1994e. Method 8260A. Volatile organic compounds by gas chromatography mass spectrometry (GC/MS): Capillary column technique. Method Status Table SW-846, 3rd ed., Updates I, II, IIA and IIB. U.S. Environmental Protection Agency.
- EPA. 1994f. Chemical lists and reporting periods. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 712.30.
- EPA. 1994g. Standards of performance for the equipment leaks of VOC in the synthetic organic chemicals manufacturing industry. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 60.489.
- EPA. 1994h. NPDES permit application testing requirements. U.S. Environmental Protection Agency. 40 CFR 122, App D.
- EPA. 1994i. Applicability; description of the metal finishing point source category. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 433.10.
- EPA. 1994j. Designation, reportable quantities, and notification. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 302.4.
- EPA. 1994k. Specific toxic chemical listings. Chemicals and chemical categories to which this part applies. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 372.65.
- EPA. 1994l. Standards of performance for volatile organic compounds emissions from synthetic organic chemical manufacturing industry (SOCMI) reactor processes. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 60.707.
- EPA. 1994m. Health and safety data reporting. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 716.120.
- EPA. 1994n. Tests methods for pesticide pollutants. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 455.50.
- \*EPA. 1994o. Methods for derivation of inhalation reference concentrations and application of inhalation dosimetry. Washington, DC: U.S. Environmental Protection Agency, Office of Research and Development. EPA600/8-90/066F.
- \*EPA. 1995a. Method 8021B. Halogenated volatiles by gas chromatography using photoionization and electrolytic conductivity detectors in series: Capillary column technique. SW-846. Final update IIB. 3rd ed. U.S. Environmental Protection Agency.
- \*EPA. 1995b. Method 8260B. Volatile organic compounds by gas chromatography mass spectrometry (GC/MS): Capillary column technique. SW-846. Final update IIB. 3rd ed. U.S. Environmental Protection Agency.
- \*EPA. 1995c. Drinking water regulations and health advisories. Washington, DC: U.S. Environmental Protection Agency, Office of Water.
- \*EPA. 1995d. Toxic chemical release inventory. Reporting form R and instructions. Section 313 of the Emergency Planning and Community Right-to-Know Act. Washington, DC: U.S. Environmental Protection Agency, Office of Pollution Prevention and Toxics.

## 9. REFERENCES

- \*EPA. 1995e. Method 4030: Soil screening for petroleum hydrocarbons by immunoassay. In: Test methods for evaluating solid waste, physical/chemical methods. Final update IIB. 3rd ed. U.S. Environmental Protection Agency. SW-846. <http://www.epa.gov/epaoswer/hazwaste/test/pdfs/4030.pdf>. August 15, 2007.
- EPA. 1997a. Land disposal restrictions: Correction of tables; treatment standards for hazardous wastes and universal treatment standards. U.S. Environmental Protection Agency. Fed Regist 62:7502-7600.
- \*EPA. 1997b. Special report on environmental endocrine disruption: An effects assessment and analysis. Washington, DC: U.S. Environmental Protection Agency, Risk Assessment Forum. EPA630R96012.
- \*EPA. 1999. Method 624: Purgeables. In: Methods and guidance for the analysis of water: Version 2. U.S. Environmental Protection Agency. PB99500209. [http://infotrek.er.usgs.gov/docs/nemi/method\\_pdf/5249.pdf](http://infotrek.er.usgs.gov/docs/nemi/method_pdf/5249.pdf). August 13, 2007.
- \*EPA. 2000. Benchmark dose technical guidance document. Washington, DC: U.S. Environmental Protection Agency. EPA630R00001.
- \*EPA. 2003. National primary drinking water regulations. Washington, DC: U.S. Environmental Protection Agency, Office of Ground Water and Drinking Water. EPA816F03016. <http://www.epa.gov/safewater/mcl.html>. March 07, 2006.
- \*EPA. 2004. Inert pesticide ingredients in pesticide products. Washington, DC: U.S. Environmental Protection Agency. <http://www.epa.gov/opprd001/inerts/lists.html>. April 11, 2007.
- \*EPA. 2005. Toxic chemical release inventory reporting forms and instructions: Revised 2004 version. Section 313 of the Emergency Planning and Community Right-to-Know Act (Title III of the Superfund Amendments and Reauthorization Act of 1986). U.S. Environmental Protection Agency. Office of Environmental Information. EPA260B05001.
- \*EPA. 2006a. Drinking water standards and health advisories. Washington, DC: Office of Water, U.S. Environmental Protection Agency. EPA822R04005. <http://epa.gov/waterscience/criteria/drinking/>. April 11, 2007.
- \*EPA. 2006b. National recommended water quality criteria. Washington, DC: U.S. Environmental Protection Agency, Office of Water, Office of Science and Technology. <http://www.epa.gov/waterscience/criteria/wqcriteria.html>. March 07, 2006.
- \*EPA. 2007a. Acute exposure guideline levels (AEGLs) Washington, DC: Office of Pollution Prevention and Toxics, U.S. Environmental Protection Agency. <http://www.epa.gov/oppt/aegl/pubs/compiled.pdf>. April 11, 2007.
- \*EPA. 2007b. Designated as hazardous substances in accordance with Section 311(b)(2)(A) of the Clean Water Act. Code of Federal Regulations. 40 CFR 116.4. Washington, DC: U.S. Environmental Protection Agency. <http://www.epa.gov/epacfr40/chapt-I.info/chi-toc.htm>. April 11, 2007.
- \*EPA. 2007c. Hazardous air pollutants. Clean Air Act. United States Code. 42 USC 7412. Washington, DC: U.S. Environmental Protection Agency. <http://www.epa.gov/ttn/atw/orig189.html>. April 11, 2007.

## 9. REFERENCES

- \*EPA. 2007d. Reportable quantities of hazardous substances designated pursuant to Section 311 of the Clean Water Act. Code of Federal Regulations. 40 CFR 117.3. Washington, DC: U.S. Environmental Protection Agency. <http://www.epa.gov/epacfr40/chapt-I.info/chi-toc.htm>. April 11, 2007.
- \*EPA. 2007e. Superfund, emergency planning, and community right-to-know programs. Designation, reportable quantities, and notifications. Code of Federal Regulations. 40 CFR 302.4. Washington, DC: U.S. Environmental Protection Agency. <http://www.epa.gov/epacfr40/chapt-I.info/chi-toc.htm>. April 11, 2007.
- \*EPA. 2007f. Superfund, emergency planning, and community right-to-know programs. Toxic chemical release reporting. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 372.65. <http://www.epa.gov/epacfr40/chapt-I.info/chi-toc.htm>. April 11, 2007.
- \*EPA. 2007g. Toxic pollutants designated pursuant to Section 307(a)(1) of the Clean Water Act. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 401.15. <http://www.epa.gov/epacfr40/chapt-I.info/chi-toc.htm>. April 11, 2007.
- \*EPA. 2007h. Toxic Substances Control Act. Health and Safety Data Reporting. Substances and listed mixtures to which this subpart applies. U.S. Environmental Protection Agency. Code of Federal Regulations. 40 CFR 716.120. <http://www.epa.gov/epacfr40/chapt-I.info/chi-toc.htm>. April 11, 2007.
- \*EPA. 2007i. Ethylbenzene. Modernized STORET system: Regular results by project (stormodb): Characteristic search by CAS number. U.S. Environmental Protection Agency. <http://www.epa.gov/storet/dbtop.html>. April 02, 2007.
- \*EPA. 2007j. Master testing list. Washington, DC: U.S. Environmental Protection Agency, Office of Pollution Prevention and Toxics. <http://www.epa.gov/opptintr/chemtest/pubs/mtl.htm>. May 10, 2007.
- +\*Ethylbenzene Producers Association. 1986a. A four day inhalation study of ethylbenzene in the rat, mouse, and rabbit. Ethylbenzene Producers Association. Submitted to the U.S. Environmental Protection Agency under TSCA Section 8D. OTS0513170.
- Ethylbenzene Producers Association. 1986b. A four week inhalation study of ethylbenzene in the rat, mouse, and rabbit. Ethylbenzene Producers Association. Submitted to the U.S. Environmental Protection Agency under TSCA Section 8d. OTS0513173.
- +Etkina EI, Etkina IA. 1995. Chemical mixtures exposure and children's health. *Chemosphere* 31(1):2463-2474.
- +\*Faber WD, Roberts LSG, Stump DG, et al. 2006. Two generation reproduction study of ethylbenzene by inhalation in Crl-CD rats. *Birth Defects Res B Dev Reprod Toxicol* 77(1):10-21.
- +\*Faber WD, Roberts LSG, Stump DG, et al. 2007. Inhalation developmental neurotoxicity study of ethylbenzene in Crl-CD rats. *Birth Defects Res B Dev Reprod Toxicol* 80:34-48.
- Fang Z, Sonner J, Laster MJ, et al. 1996. Anesthetic and convulsant properties of aromatic compounds and cycloalkanes: Implications for mechanisms of narcosis. *Anesth Analg* 83(5):1097-1104.

## 9. REFERENCES

- \*FDA. 2006a. Beverages. Bottled water. U.S. Food and Drug Administration. Code of Federal Regulations. 21 CFR 165.110. <http://www.accessdata.fda.gov/scripts/cdrh/cfdocs/cfcr/CFRSearch.cfm>. April 11, 2007.
- \*FDA. 2006b. Total diet study. Market baskets 1991-1993 through 2003-2004. U.S. Food and Drug Administration, 1-126.
- \*FDA. 2007. Everything added to food in the United States (EAFUS) Washington, DC: U.S. Food and Drug Administration. <http://vm.cfsan.fda.gov/~dms/eafus.html>. April 11, 2007.
- \*FEDRIP. 2007. Ethylbenzene. Federal Research in Progress database. Springfield, VA: National Technical Information Service.
- \*Fellin P, Otson R. 1994. Assessment of the influence of climatic factors on concentration levels of volatile organic compounds (VOCs) in Canadian homes. *Atmos Environ* 28(22):3581-3586.
- \*Ferrario JB, Lawler GC, DeLeon IR, et al. 1985. Volatile organic pollutants in biota and sediments of Lake Pontchartrain. *Bull Environ Contam Toxicol* 34:246-255.
- \*Filipovic D, Paulsen MD, Loida PJ, et al. 1992. Ethylbenzene hydroxylation by cytochrome P450cam. *Biochem Biophys Res Commun* 189(1):488-495.
- \*Fishbein L. 1985. An overview of environmental and toxicological aspects of aromatic hydrocarbons. IV. Ethylbenzene. *Sci Total Environ* 44:269-287.
- \*Florin I, Rutberg L, Curvall M, et al. 1980. Screening of tobacco smoke constituents for mutagenicity using the Ames test. *Toxicology* 18:219-232.
- \*Fomon SJ. 1966. Body composition of the infant: Part 1: The male reference infant. In: Faulkner F, ed. *Human development*. Philadelphia, PA: WB Saunders, 239-246.
- \*Fomon SJ, Haschke F, Ziegler EE, et al. 1982. Body composition of reference children from birth to age 10 years. *Am J Clin Nutr* 35:1169-1175.
- Forziati AF, Norris WR, Rossini FD. 1949. Vapor pressures and boiling points of sixty API-NBS hydrocarbons. *J Res Natl Bureau Standards* 43:555-563.
- +Fouchecourt MO, Riviere JL. 1996. Activities of liver and lung cytochrome p450-dependent monooxygenases and antioxidant enzymes in laboratory and wild Norway rats exposed to reference and contaminated soils. *Toxicology* 30(4):513-522.
- Fox MA, Tran NL, Groopman JD. 2004. Toxicological resources for cumulative risk: An example with hazardous air pollutants. *Regul Toxicol Pharmacol* 40(3):305-311.
- +\*Frantik E, Hornychova M, Horvath M. 1994. Relative acute neurotoxicity of solvents: Isoeffective air concentrations of 48 compounds evaluated in rats and mice. *Environ Res* 66(2):173-185.
- Fujita T, Iwasa J, Hansch C. 1964. A new substituent constant,  $\pi$ , derived from partition coefficients. *J Amer Chem Soc* 86:5175-5180.

## 9. REFERENCES

- \*Fukuda M, Nishi T, Igarashi M, et al. 1989. Degradation of ethylbenzene by *Pseudomonas putida* harboring OCT plasmid. *Agric Biol Chem* 53(12):3293-3299.
- Furnas DW, Hine CH. 1958. Neurotoxicity of some selected hydrocarbons. *Arch Ind Health* 18:9-15.
- Fusillo TV, Hochreiter JJ J, Lord DG. 1985. Distribution of volatile organic compounds in a New Jersey coastal plain aquifer system. *Groundwater* 23:354-360.
- +\*Fustinoni S, Buratti M, Giampiccolo R. 1995. Biological and environmental monitoring of exposure to airborne benzene and other aromatic hydrocarbons in Milan traffic wardens. *Toxicol Lett* 77:387-392.
- \*Fustinoni S, Buratti M, Giampiccolo R, et al. 1996. Biological monitoring of airborne aromatic hydrocarbon exposure: A gas chromatographic procedure for the determination of benzene, toluene, ethylbenzene and xylenes in blood and urine. *Med Lav* 87(1):63-75.
- Fustinoni S, Giampiccolo R, Pulvirenti S, et al. 1999. Headspace solid-phase microextraction for the determination of benzene, toluene, ethylbenzene and xylenes in urine. *J Chromatogr B Biomed Sci Appl* 723:105-115.
- +\*Gagnaire F, Langlais C. 2005. Relative ototoxicity of 21 aromatic solvents. *Arch Toxicol* 79(6):346-354.
- +\*Gagnaire F, Langlais C, Grossmann S, et al. 2007. Ototoxicity in rats exposed to ethylbenzene and to two technical xylene vapours for 13 weeks. *Arch Toxicol* 81(2):127-143.
- Gamberale F, Annwall G, Hultengren M. 1978. Exposure to xylene and ethylbenzene. III. Effects on central nervous function. *Scand J Work Environ Health* 4:204-211.
- \*Gargas ML, Burgess RJ, Voisard DE, et al. 1989. Partition coefficients of low-molecular-weight volatile chemicals in various liquids and tissues. *Toxicol Appl Pharmacol* 98:87-99.
- Gerarde HW. 1959. Toxicological studies on hydrocarbons. III. The biochemorphology of the phenylalkanes and phenylalkenes. *AMA Arch Ind Health* 19:403-418.
- +Gerarde HW, Linden NJ. 1956. Toxicological studies on hydrocarbons. II. A comparative study of the effect of benzene and certain mono-n-alkylbenzenes on hemopoiesis and bone marrow metabolism in rats. *AMA Arch Ind Health* 13:468-474.
- +Gerarde HW, Linden NJ. 1963. Toxicological studies on hydrocarbons: IX. The aspiration hazard and toxicity of hydrocarbons and hydrocarbon mixtures. *Arch Environ Health* 6:329-341.
- +Gershbein LL. 1975. Liver regeneration as influenced by the structure of aromatic and heterocyclic compounds. *Res Commun Chem Pathol Pharmacol* 11:445-466.
- Gibson DT. 1977. Biodegradation of aromatic petroleum hydrocarbons. In: Wolfe DA, ed. Fate and effects of petroleum hydrocarbons in marine organisms and ecosystems. New York, NY: Pergamon Press, 36-46.
- Gibson DP, Brauning R, Shaffi HS, et al. 1997. Induction of micronuclei in Syrian hamster embryo cells: Comparison to results in the SHE cell transformation assay for national toxicology program test chemicals. *Mutat Res* 392(1-2):61-70.

## 9. REFERENCES

- \*Gibson DT, Geschwendt B, Yeh WK, et al. 1973. Initial reactions in the oxidation of ethylbenzene by *Pseudomonas putida*. *Biochemistry* 12:1520-1528.
- Gibson DT, Koch JR, Kallio RE. 1968. Oxidative degradation of aromatic hydrocarbons by microorganisms. I. Enzymatic formation of catechol from benzene. *Biochemistry* 7:2653-2662.
- Giger W, Schaffner C. 1981. Groundwater pollution by volatile chemicals. *Stud Environ Sci* 17:517-522.
- \*Gillette JR, Mitchell JR, Brodie BB. 1974. Biochemical mechanisms of drug toxicity. *Ann Rev Pharmacol* 14:271-288.
- \*Giwerzman A, Carlsen E, Keiding N, et al. 1993. Evidence for increasing incidence of abnormalities of the human testis: A review. *Environ Health Perspect Suppl* 101(2):65-71.
- \*Goldberg MS, Al-Homsi N, Goulet L, et al. 1995. Incidence of cancer among persons living near municipal solid waste landfill site in Montreal, Quebec. *Arch Environ Health* 50(6):416-424.
- Goldfrank LR. 1994. Hydrocarbons. In: Goldfrank LR, Flomenbaum NE, Lewin NA, et al., eds. *Goldfrank's toxicologic emergencies*. 5th ed. Norwalk, CT: Appleton & Lange, 1231-1244.
- \*Górna-Binkul A, Keymeulen R, Van Langenhove H, et al. 1996. Determination of monocyclic aromatic hydrocarbons in fruit and vegetables by gas chromatography-mass spectrometry. *J Chromatogr A* 734(2):297-302.
- \*Gossel TA, Bricker JD. 1994. Principles of clinical toxicology. 3rd ed. New York, NY: Raven Press, 124-126.
- Gossett RW, Brown DA, Young DR. 1983. Predicting the bioaccumulation of organic compounds in marine organism using octanol/water partition coefficients. *Mar Pollut Bull* 14:387-392.
- \*Gramshaw JW, Vandenburg HJ. 1995. Compositional analysis of samples of thermoset polyester and migration of ethylbenzene and styrene from thermoset polyester into pork during cooking. *Food Addit Contam* 12(2):223-234.
- \*Greiner JW, Kramer RE, Robinson DA, et al. 1976. Interaction of aromatic hydrocarbons and drugs with adrenal microsomal cytochrome P-450 in the guinea pig. *Biochem Pharmacol* 25(8):951-955.
- Grigor'eva KV, Klyuzko AS. 1971. Studies of the metabolite of styrene and ethylbenzene in urine. *Hyg Sanit* 36:136-137.
- Grob K, Grob G. 1971. Gas-liquid chromatographic-mass spectrometric investigation of C<sub>6</sub>-C<sub>20</sub> organic compounds in an urban atmosphere. An application of ultra trace analysis on capillary columns. *J Chromatogr* 62:1-13.
- +\*Gromiec JP, Piotrowski JK. 1984. Urinary mandelic-acid as an exposure test for ethylbenzene. *Int Arch Occup Environ Health* 55(1):61-72.
- \*Grosjean D, Fung K. 1984. Hydrocarbons and carbonyls in Los Angeles air. *J Air Pollut Control Assoc* 34:537-543.

## 9. REFERENCES

- \*Grovenstein E, Mosher AJ. 1970. Reaction of atomic oxygen with aromatic hydrocarbons [Letter]. *J Am Chem Soc* 92:3810-3812.
- \*Gschwend PM, Zafirlou OC, Mantoura RFC, et al. 1982. Volatile organic compounds at a coastal site. 1. Seasonal variations. *Environ Sci Technol* 16:31-38.
- +Gut IY, Terelius E, Frantik I, et al. 1993. Exposure to various benzene derivatives differently induces cytochromes P450 2B1 and P450 2E1 in rat liver. *Arch Toxicol* 67(4):237-243.
- \*Guy RH, Maibach HI. 1984. Correction factors for determining body exposure from forearm percutaneous absorption data. *J Appl Toxicol* 4(1):26-28.
- \*Guzelian PS, Henry CJ, Olin SS. 1992. Similarities and differences between children and adults: Implications for risk assessment. Washington, DC: International Life Sciences Institute Press.
- \*Haddad S, Béliveau M, Tardif R, et al. 2001. A PBPK modeling-based approach to account for interactions in the health risk assessment of chemical mixtures. *Toxicol Sci* 63:125-131.
- +\*Hajimiragha H, Ewers U, Brockhaus A, et al. 1989. Levels of benzene and other volatile aromatic compounds in the blood of non-smokers and smokers. *Int Arch Occup Environ Health* 61(8):513-518.
- \*Hallbourg RR, Delfino JJ, Miller WL. 1992. Organic priority pollutants in groundwater and surface water at three landfills in north central Florida. *Water Air Soil Pollut* 65:307-322.
- \*Hampton CV, Pierson WR, Schuetzle D, et al. 1983. Hydrocarbon gases emitted from vehicles on the road. 2. Determination of emission rates from diesel and spark-ignition vehicles. *Environ Sci Technol* 17:699-708.
- Hannah SA, Austern BM, Eralp AE, et al. 1986. Comparative removal of toxic pollutants by six wastewater treatment processes. *J Water Pollut Control Fed* 58:27-34.
- \*Hansch C, Leo A. 1979. Substituent constants for correlation analysis in chemistry and biology. New York, NY: John Wiley & Sons, 232.
- Hansch C, Leo A, Nikaitani D. 1972. On the additive-constitutive character of partition coefficients. *J Org Chem* 37:3090-3092.
- Hansch C, Quinlan JE, Lawrence GL. 1968. The linear-free energy relationship between partition coefficients and the aqueous solubility of organic liquids. *J Org Chem* 33:347-350.
- +Hansen LF, Nielsen GD. 1994. Sensory irritation effects of n-propanol and ethylbenzene after pretreatment with capsaicin or indomethacin. *Pharmacol Toxicol* 75(3-4):154-161.
- \*Hard GC. 2002. Significance of the renal effects of ethylbenzene in rodents for assessing human carcinogenic risk. *Toxicol Sci* 69:30-41.
- Hardin BD, Bond GP, Sikov MR, et al. 1981. Testing of selected workplace chemicals for teratogenic potential. *Scand J Work Environ Health* 7 (Suppl 4):66-75.

## 9. REFERENCES

- Harkonen H, Lindstrom K, Seppalainen AM, et al. 1978. Exposure-response relationship between styrene exposure and central nervous functions. *Scand J Work Environ Health* 4:53-59.
- \*Harkov R, Kebbekus B, Bozzelli JW, et al. 1983. Measurement of selected volatile organic compounds at three locations in New Jersey during the summer season. *J Air Pollut Control Assoc* 33:1177-1183.
- Harkov R, Kebbekus B, Bozzelli JW, et al. 1984. Comparison of selected volatile organic compounds during the summer and winter at urban sites in New Jersey. *Sci Total Environ* 38:259-274.
- Harkov R, Kebbekus B, Bozzelli JW. 1987. Volatile organic compounds at urban sites in New Jersey. In: Lioy PJ, Daisey JM, eds. *Toxic air pollutants*. Chelsea, MI: Lewis Publishers Inc, 69-90.
- Haumann K, Kiesswetter E, van Thriel C, et al. 2003. Breathing and heart rate during experimental solvent exposure of young adults with self-reported multiple chemical sensitivity (sMCS) *Neurotoxicology* 24(2):179-186.
- Hawthorne SB, Miller DJ. 2003. Evidence for very tight sequestration of BTEX compounds in manufactured gas plant soils based on selective supercritical fluid extraction and soil/water partitioning. *Environ Sci Technol* 37(16):3587-3594.
- \*HazDat. 2007. Ethylbenzene. HazDat Database: ATSDR's Hazardous Substance Release and Health Effects Database. Atlanta, GA: Agency for Toxic Substances and Disease Registry. <http://www.atsdr.cdc.gov/hazdat.html>. April 02, 2007.
- Heald PC, Schladow SG, Reuter JE, et al. 2005. Modeling MTBE and BTEX in lakes and reservoirs used for recreational boating. *Environ Sci Technol* 39:1111-1118.
- \*Heikes DL, Jensen SR, Fleming-Jones ME. 1995. Purge and trap extraction with GC-MS determination of volatile organic compounds in table-ready foods. *J Agric Food Chem* 43:2869-2875.
- Heiselman DE, Cannon LA. 1990. Benzene and the aromatic hydrocarbons. In: Haddad LM, Winchester JF eds. *Clinical management of poisoning and drug overdose*. 2nd ed., 1222-1232.
- Henry B, Grant SG, Klopman G, et al. 1998. Induction of forward mutations at the thymidine kinase locus of mouse lymphoma cells: Evidence for electrophilic and non-electrophilic mechanisms. *Mutat Res* 397:313-335.
- \*Herron JT, Huie RE. 1973. Rate constants for the reactions of atomic oxygen ( $O^3P$ ) with organic compounds in the gas phase. *J Phys Chem Ref Data* 2(3):467-518.
- Hester NE, Meyer RA. 1979. A sensitive technique for measurement of benzene and alkylbenzenes in air. *Environ Sci Technol* 13:107-109.
- \*Hiatt MH. 1981. Analysis of fish and sediment for volatile priority pollutants. *Anal Chem* 53:1541-1543.
- \*Hiatt MH. 1983. Determination of volatile organic compounds in fish samples by vacuum distillation and fused silica capillary gas chromatography-mass spectrometry. *Anal Chem* 55:506-516.
- Hinwood AL, Rodriguez C, Runnion T, et al. 2007. Risk factors for increased BTEX exposure to four Australian cities. *Chemosphere* 66(3):533-541.



## 9. REFERENCES

- \*Hodgson AT, Daisey JM, Grot RA. 1991. Sources and source strengths of volatile organic compounds in a new office building. *J Air Waste Manage Assoc* 41(11):1461-1468.
- \*Hodgson AT, Daisey JM, Mahanama KRR, et al. 1996. Use of volatile tracers to determine the contribution of environmental tobacco smoke to concentrations of volatile organic compounds in smoking environment. *Environ Int* 22(3):295-307.
- \*Hodgson AT, Garbesi K, Sextro RG, et al. 1992. Soil-gas contamination and entry volatile organic compounds into a house near a landfill. *J Air Waste Manage Assoc* 42(3):277-283.
- \*Hodson J, Williams NA. 1988. The estimation of the adsorption coefficient ( $K_{oc}$ ) for soils by high performance liquid chromatography. *Chemosphere* 17:67-77.
- \*Hoel DG, Davis DL, Miller AB, et al. 1992. Trends in cancer mortality in 15 industrialized countries, 1969-1986. *J Natl Cancer Inst* 84(5):313-320.
- Holmberg B, Malmfors T. 1974. The cytotoxicity of some organic solvents. *Environ Res* 7:183-192.
- Holmberg B, Jakobson I, Malmfors T. 1974. The effect of organic solvents on erythrocytes during hypotonic hemolysis. *Environ Res* 7:193-205.
- +\*Holz O, Scherer G, Brodtmeier S, et al. 1995. Determination of low level exposure to volatile aromatic hydrocarbons and genotoxic effects in workers at a styrene plant. *Environ Med* 52(6):420-428.
- +Hong HL, Yang RSH, Boorman GA. 1991. Residual damage to hematopoietic system in mice exposed to a mixture of groundwater contaminants. *Toxicol Lett* 57(1):101-112.
- \*Hoshino M, Akimoto H, Okuda M. 1978. Photochemical oxidation of benzene, toluene, and ethylbenzene initiated by hydroxyl radicals in the gas phase. *Bull Chem Soc Jpn* 51:718-724.
- \*HSDB. 2007. Ethylbenzene. Hazardous Substances Data Bank. National Library of Medicine. <http://toxnet.nlm.nih.gov>. April 02, 2007.
- Hung I-F, Lee S-A, Chen R-K. 1998. Simultaneous determination of benzene, toluene, ethylbenzene, and xylenes in urine by thermal desorption-gas chromatography. *J Chromatogr B* 706(2):352-357.
- \*Hutchins SR. 1991. Optimizing BTEX biodegradation under denitrifying conditions. *Environ Toxicol Chem* 10:1437-1448.
- \*Hutchins SR, Sewell GW, Kovacs DA, et al. 1991. Biodegradation of aromatic hydrocarbons by aquifer microorganisms under denitrifying conditions. *Environ Sci Technol* 25:68-76.
- Huyskens PL, Tack JJ. 1975. Specific interactions of phenols with water. *J Phys Chem* 79:1654-1658.
- IARC. 2000. Ethylbenzene. IARC monographs on the evaluation of carcinogenic risks to humans. Vol. 77. Some industrial chemicals. Lyon, France: World Health Organization International Agency for Research on Cancer.

## 9. REFERENCES

- \*IARC. 2006. Agents reviewed by the IARC Monographs. Volumes 1–96. Lyon, France: International Agency for Research on Cancer. <http://monographs.iarc.fr/ENG/Classification/index.php>. April 11, 2007.
- Imamura K, Fuji T. 1979. [Rapid determination of toluene, ethylbenzene, and xylene isomers at ppb level in ambient air by mass fragmentography]. *Bunseki Kagaku* 28:549-554. (Japanese)
- +Imaoka S, Funae Y. 1991. Induction of cytochrome P450 isozymes in rat liver by methyl n-alkyl ketones and n-alkylbenzenes. Effects of hydrophobicity of inducers on inducibility of cytochrome *Biochem Pharmacol* 45(42):143-150.
- Ioffe BV, Isidorov VA, Zenkevich IG. 1979. Certain regularities in the composition of volatile organic pollutants in the urban atmosphere. *Environ Sci Technol* 13:864-868.
- \*IRIS. 2007. Ethylbenzene. Integrated Risk Information System. Washington, DC: U.S. Environmental Protection Agency. <http://www.epa.gov/iris/subst/index.html>. April 11, 2007.
- +\*Ivanov SV. 1962. [Toxicology of ethylbenzene.] *Tr Voronezh Gos Med Inst* 47:80-82. (Russian).
- Ivanov SV. 1964. [Materials on toxicity and hygienic rating ethylbenzol content in the atmosphere of industrial premises]. *Gig Tr Prof Zabol* 8:9-14. (Russian)
- Jahn MK, Handerlein SB, Meckenstock RU. 2005. Anaerobic degradation of benzene, toluene, ethylbenzene, and o-xylene in sediment-free iron-reducing enrichment cultures. *Appl Environ Microbiol* 71(6):3355-3358.
- \*Jamison VW, Raymond RL, Hudson JO. 1970. Hydrocarbon cooxidation by *Nocardia corallina* strain V-49. *Develop Ind Microbiol* 12:99-105.
- Jang JY, Droz PO, Kim S. 2001. Biological monitoring of workers exposed to ethylbenzene and co-exposed to xylene. *Int Arch Occup Environ Health* 74:31-37.
- \*Jay K, Steiglitz L. 1995. Identification and quantification of volatile organic components in emissions of waste incineration plants. *Chemosphere* 30(7):1249-1260.
- Jo WK, Yu CH. 2001. Public bus and taxicab drivers' exposure to aromatic work-time volatile organic compounds. *Environ Res* 86(1):66-72.
- \*Johanson CE. 1980. Permeability and vascularity of the developing brain: Cerebellum vs. cerebral cortex. *Brain Res* 190:3-16.
- +Johanson G, Filser JG. 1992. Experimental data from closed chamber gas uptake studies in rodents suggest lower uptake rate of chemical than calculated from literature values on alveolar ventilation. *Arch Toxicol* 66(4):291-295.
- Johnstone RAW, Quan PM, Carruthers W. 1962. Composition of cigarette smoke: Some low-boiling components. *Nature* 195:1267-1269.
- \*Jonsson A, Persson KA, Grigoriadis V. 1985. Measurements of some low molecular-weight oxygenated, aromatic, and chlorinated hydrocarbons in ambient air and in vehicle emissions. *Environ Int* 11:383-392.

## 9. REFERENCES

- \*Junk GA, Ford CS. 1980. A review of organic emissions from selected combustion processes. *Chemosphere* 9:187-230.
- Juttner F. 1986. Analysis of organic compounds (VOC) in the forest air of southern Black Forest. *Chemosphere* 15:985-992.
- \*Kango RY, Quinn JG. 1989. Adsorption studies of xylenes and ethylbenzene on soil and humic acid by a purge and trap gas chromatographic method. *Chemosphere* 19(8/9):1269-1276.
- Kappeler T, Wuhrmann K. 1978. Microbial degradation of the water soluble fraction of gas oil. I. *Water Res* 12:327-333.
- \*Karasek FW, Charbonneau GM, Reuel GJ, et al. 1987. Determination of organic compounds leached from municipal incinerator fly ash by water at different pH levels. *Anal Chem* 59:1027-1031.
- \*Katzman H, Libby WF. 1975. Hydrocarbon emissions from jet engines operated at simulated high altitude supersonic flight conditions. *Atmos Environ* 9:839-842.
- \*Kaubisch N, Daly JW, Jerina DM. 1972. Arene oxides as intermediate in the oxidative metabolism of aromatic compounds. Isomerization of methyl-substituted arene oxides. *Biochemistry* 11:3080-3088.
- +\*Kawai T, Mizunuma K, Yasugi T, et al. 1991. Urinary methylhippuric acid isomer levels after occupational exposure to a xylene mixture. *Int Arch Occup Environ Health* 63(1):69-75.
- +\*Kawai T, Yasugi T, Mizunuma K, et al. 1992. Comparative evaluation of urinalysis and blood analysis as means of detecting exposure to organic solvents at low concentrations. *Int Arch Occup Environ Health* 64(4):223-234.
- \*Kawamura K, Kaplan IR. 1983. Organic compounds in the rainwater of Los Angeles. *Environ Sci Tech* 17:497-501.
- \*Keefe SH, Barber LB, Runkel RL, et al. 2004. Fate of volatile organic compounds in constructed wastewater treatment wetlands. *Environ Sci Technol* 38(7):2209-2216.
- \*Keith LH, Garrison AW, Allen FR, et al. 1976. Identification of organic compounds in drinking water from thirteen U.S. cities. In: Identification and analysis of organic pollutants in water. Ann Arbor, MI: Ann Arbor Science Publishers, Inc., 329-373.
- \*Kelly TJ, Mukund R, Spicer CW, et al. 1994. Concentrations and transformations of hazardous air pollutants. *Environ Sci Technol* 28(8):378A-387A.
- \*Keymeulen R, Van Langenhove H, Schamp N. 1991. Determination of monocyclic aromatic hydrocarbons in plant cuticles by gas chromatography-mass spectrometry. *J Chromatogr* 541:83-88.
- +\*Kiese M, Lenk W. 1974. Hydroxyacetophenones: Urinary metabolites of ethylbenzene and acetophenone. *Xenobiotica* 4:337-343.
- Kim YM, Harrad S, Harrison RM. 2002. Levels and sources of personal inhalation exposure to volatile organic compounds. *Environ Sci Technol* 36:5405-5410.

## 9. REFERENCES

- \*Kinlin TE, Muraldihara R, Pittet AO, et al. 1972. Volatile components of roasted filberts. *J Agric Food Chem* 20:1021.
- \*Kinney PL, Chillrud SN, Ramstrom S, et al. 2002. Exposures to multiple air toxics in New York City. *Environ Health Perspect* 110(Suppl 4):539-546.
- \*Kirschner EM. 1995. Production of top 50 chemicals increased substantially in 1994. *Chem Eng News* 73(15):16-22.
- \*Kitto AM, Pirbazari M, Badriyha BN, Ravindran V, Tyner R, Synolakis CE. 1997. Emissions of volatile and semi-volatile organic compounds and particulate matter from hot asphalts. *Environ Technol* 18(2):121-138.
- \*Knox RC, Canter LW. 1996. Prioritization of ground water contaminants and sources. *Water Air Soil Pollut* 88:205-226.
- \*Komori M, Nishio K, Kitada M et al. 1990. Fetus-specific expression of a form of cytochrome P-450 in human livers. *Biochemistry* 29:4430-4433.
- Kool HJ, Van Kreijl CF, Zoeteman BCJ. 1982. Toxicology assessment of organic compounds in drinking water. *Crit Rev Env Control* 12:307-357.
- Kopfler FC, Melton GG, Mullaney JL, et al. 1977. Human exposure to water pollutants. *Adv Environ Sci Technol* 8:419-433.
- Koren HS, Devlin RB. 1992. Human upper respiratory tract responses to inhaled pollutants with emphasis on nasal lavage. *Ann New York Acad Sci* 641:215-224.
- \*Kos G, Ariya PA. 2006. Determination of a wide range of volatile and semivolatile organic compounds in snow by use of solid-phase micro-extraction (SPME). *Anal Bioanal Chem* 385:57-66.
- \*Kostiainen R. 1995. Volatile organic compounds in the indoor air of normal and sick houses. *Atmos Environ* 29(6):693-702.
- \*Krill RM, Sonzogni WC. 1986. Chemical monitoring of Wisconsin's groundwater. *J Am Water Works Assoc* 78:70-75.
- \*Krishnan K, Andersen ME. 1994. Physiologically-based pharmacokinetic modeling in toxicology. In: Wallace Hayes, ed. *Principles and Methods of Toxicology*. 3rd ed. New York, NY: Raven Press, Ltd., 149-188.
- \*Krishnan K, Andersen ME, Clewell HJ, et al. 1994. Physiologically based pharmacokinetic modeling of chemical mixtures. In: Yang RSH, ed. *Toxicology of chemical mixtures: Case studies, mechanisms, and novel approaches*. San Diego, CA: Academic Press, 399-437.
- Krost KJ, Pellizzari ED, Walburn SG, et al. 1982. Collection and analysis of hazardous organic emissions. *Anal Chem* 54:810-817.
- Krotoszynski BK, Bruneau GM, O'Neill HJ. 1979. Measurement of chemical inhalation exposure in urban population in the presence of endogenous effluents. *J Anal Toxicol* 3:225-234.

## 9. REFERENCES

- \*Kubo T, Urano K, Utsumi H. 2002. Mutagenicity characteristics of 255 environmental chemicals. *J Health Sci* 48(6):545-554.
- Kumagai S, Matsunaga I. 1992. Fluctuations of occupational exposure indices to mixtures. *Ann Occup Hyg* 36(2):131-143.
- Kumagai S, Matsunaga I. 1995. Models describing variation of short-term exposure levels of two chemicals. *Annals Occup Hyg* 39(1):7-20.
- \*Kwok ESC, Atkinson R. 1994. Estimation of hydroxyl radical reaction rate constants for gas-phase organic compounds using a structure-reactivity relationship: An update. Riverside CA: University of California. CMAARC8.00R.
- Lambotte-Vandepaer M, Duverger-Van Bogaert M, De Meester C, et al. 1979. Styrene induced modifications of some rat liver enzymes involved in the activation and inactivation of xenobiotics. *Biochem Pharmacol* 28:1653-1660.
- Langworth S, Anundi H, Friis L, et al. 2001. Acute health effects common during graffiti removal. *Int Arch Occup Environ Health* 74(3):213-218.
- LaRegina J, Bozzelli JW, Harkov R, et al. 1986. Volatile organic compounds at hazardous waste sites and a sanitary landfill. *Environ Prog* 5:18-27.
- \*Lawryk NJ, Weisel CP. 1996. Concentration of volatile organic compounds in the passenger compartments of automobiles. *Environ Sci Technol* 30:810-816.
- \*Lawryk NJ, Liroy PJ, Weisel CP. 1995. Exposure to volatile organic compounds in the passenger compartment of automobiles during periods of normal and malfunctioning operation. *J Expo Anal Environ Epidemiol* 5(4):511-531.
- \*Leeder JS, Kearns GL. 1997. Pharmacogenetics in pediatrics: Implications for practice. *Pediatr Clin North Am* 44(1):55-77.
- Lehmann E, Gmehling J, Weidlich U. 1986. Survey on organic solvents in various products and methods for estimating workplace exposures. *Prog Clin Biol Res* 220:31-41.
- Lehmann I, Rehwagen M, Dietz U, et al. 2001. Enhanced *in vivo* IgE production and T cell polarization toward the type 2 phenotype in association with indoor exposure to VOC: Results of the LARS study. *Int J Hyg Environ Health* 204(4):211-221.
- \*Leikin JB, Poloucek FP. 2002. Ethylbenzene. In: *Poisoning and toxicology handbook*. Hudson, OH: Lexi-Comp, Inc., 554.
- Lemire S, Ashley D, Olaya P, et al. 2004. Environmental exposure of commuters in Mexico City to volatile organic compounds as assessed by blood concentrations, 1998. *Salud Publica Mex* Jan-Feb(1):32-38.
- \*Lesage S. 1993. Methods for the analysis of hazardous wastes. *J Chromatogr* 642:65-74.
- \*Leung HW. 1993. Physiologically-based pharmacokinetic modelling. In: Ballantine B, Marro T, Turner T, eds. *General and Applied Toxicology*. Vol. 1. New York, NY: Stockton Press, 153-164.

## 9. REFERENCES

- \*Lide DR, ed. 1994. CRC handbook of chemistry and physics. 75th ed. Boca Raton, FL: CRC Press, Inc., 3-47, 6-62, 15-46, 16-26.
- \*Ligocki MP, Leuenberger C, Pankow JF. 1985. Trace organic compounds in rain-II. Gas scavenging of neutral organic compounds. *Atmos Environ* 19:1609-1617.
- \*Lillo RS, Morris JW, Caldwell JM, et al. 1990. Atmosphere contamination following repainting of a human hyperbaric chamber complex. *Undersea Biomed Res* 17(5):437-449.
- Liu, J, Li N, Jiang G, et al. 2005. Disposable ionic liquid coating for headspace solid-phase microextraction of benzene, toluene, ethylbenzene, and xylenes in paints followed by gas chromatography-flame ionization detection. *J Chromatogr A* 1066:27-32.
- \*Livingston AL. 1978. Forage plant estrogens. *J Toxicol Environ Health* 4(2-3):301-324.
- Lloyd AC, Darnall KR, Winer AM, et al. 1976. Relative rate constants for reaction of the hydroxyl radical with a series. *J Phys Chem* 80:789-794.
- +Lofgren L, Persson K, Stromvall A-M. 1991. Exposure of commuters to volatile aromatic hydrocarbons from petrol exhaust. *Sci Total Environ* 108(3):225-233.
- Logemann W, Giraldi P, Gagliardo E, et al. 1964. [Presence of mandelic acid and hippuric acid in the urine of individuals given (oral) ethylbenzene]. *Hoppe-Seylers Z Physiol Chem* 337:48-49. (German)
- Lonneman WA, Bellar TA, Altshuller AP. 1968. Aromatic hydrocarbons in the atmosphere of the Los Angeles basin. *Environ Sci Technol* 2:1017-1020.
- \*Lovegren NV, Fisher GS, Legendre MG, et al. 1979. Volatile constituents of dried legumes. *J Agric Food Chem* 27:851-853.
- Lowry LK. 1986. Biological exposure index as a complement to the TLV. *J Occup Med* 28:578-582.
- \*Lyman WJ, Reehl WF, Rosenblatt DH. 1982. Handbook of chemical property estimation methods. New York, NY: McGraw-Hill Book Company, 15-25.
- \*Mackay D. 1979. Finding fugacity feasible. *Environ Sci Technol* 13(10):1218-1223.
- \*Mackay D, Shiu WY. 1981. A critical review of Henry's law constants for chemicals of environmental interest. *J Phys Chem Ref Data* 19:1175-1199.
- Mackay D, Bobra A, Chan DW, et al. 1982. Vapor pressure correlations for low-volatility environmental chemicals. *Environ Sci Technol* 16:645-649.
- Mackay D, Bobra A, Shiu WY, et al. 1980. Relationships between aqueous solubility and octanol-water partition coefficients. *Chemosphere* 9:701-711.
- \*Mackay D, Shiu WY, Sutherland RP. 1979. Determination of air-water Henry's law constants for hydrophobic pollutants. *Environ Sci Technol* 13:333-337.

## 9. REFERENCES

- Malaney GW, McKinney RE. 1966. Oxidative abilities of benzene-acclimated activated sludge. *Water Sewage Works* 113:302-309.
- Maltoni C, Ciliberti A, Pinto C, et al. 1997. Results of long-term experimental carcinogenicity studies of the effects of gasoline, correlated fuels, and major gasoline aromatics on rats. *Ann N Y Acad Sci* 837:15-52.
- +\*Maltoni C, Conti B, Cotti G, et al. 1985. Experimental studies on benzene carcinogenicity at the Bologna Institute of Oncology: Current results and ongoing research. *Am J Ind Med* 7:415-446.
- Malyarova LK, Nesterova NE. 1972. Determination of aromatic compounds (benzene and its homologues) in the air. *Gig Tr Prof Zabol* 16:58-59.
- Marks TA, Ledoux TA, Moore JA. 1982. Teratogenicity of a commercial xylene mixture in the mouse. *J Toxicol Environ Health* 9:97-105.
- \*Martin P, Heavner DL, Nelson PR, et al. 1997. Environmental tobacco smoke (ets): A market cigarette study. *Environ Int* 23(1):75-90.
- Martinez MA, Ballesteros S. 2005. Investigation of fatalities due to acute gasoline poisoning. *J Anal Toxicol* 29(7):643-651.
- Martins EM, Arbilla G, Bauerfeldt GF, et al. 2007. Atmospheric levels of aldehydes and BTEX and their relationship with vehicular fleet changes in Rio de Janeiro urban area. *Chemosphere* 67:2096-2103.
- \*Masten LW, Boeri RL, Walker JD. 1994. Strategies employed to determine the acute aquatic toxicity of Ethylbenzene, a highly volatile, poorly water-soluble chemical. *Ecotoxicol Environ Safety* 27:335-348.
- +\*Matsumoto T, Koga M, Sata T, et al. 1992. The changes of gasoline compounds in blood in a case of gasoline intoxication. *J Toxicol Clin Toxicol* 30(4):653-662.
- Mayer S, Cook R, Mattler M. 1983. Evaluation of potential employee exposures while molding ignition resistant polystyrene. *J Cell Plast* 19:227-236.
- \*Maylin GA, Cooper MJ, Anders MW. 1973. Effect of phenobarbital treatment on the stereochemistry of the *in vitro* metabolism of ethylbenzene. *J Med Chem* 16:606-610.
- \*Mayr U, Butsch A, Schneider S. 1992. Validation of two *in vitro* test systems for estrogenic activities with zearalenone, phytoestrogens and cereal extracts. *Toxicology* 74(2-3):135-149.
- McAuliffe C. 1963. Solubility in water of C1-C9 hydrocarbons. *Nature* 200:1092-1093.
- McAuliffe C. 1966. Solubility in water of paraffin, cycloparaffin, olefin, acetylene, cycloolefin and aromatic hydrocarbons. *J Phys Chem* 70:1267-1275.
- \*McClenny WA, Fortune CR. 1995. Superfund contract laboratory program method evaluation--ambient air volatile organic compounds from canisters. *J Environ Sci Health A* 30(4):901-919.
- \*McDougal JN, Pollard DL, Weisman W, et al. 2000. Assessment of skin absorption and penetration of JP-8 jet fuel and its components. *Toxicol Sci* 55:247-255.

## 9. REFERENCES

- McElroy NR, Thompson ED, Jurs PC. 2003. Classification of diverse organic compounds that induce chromosomal aberrations in Chinese hamster cells. *J Chem Inf Comput Sci* 43(6):2111-2119.
- \*McGregor DB, Brown A, Cattanaach P, et al. 1988. Responses of the L5178Y tk+/tk- mouse lymphoma cell forward mutation assay: III. 72 Coded chemicals. *Environ Mol Mutag* 12:85-154.
- +\*McMahon RE, Sullivan HR. 1966. Microsomal hydroxylation of ethylbenzene. Stereospecificity and the effect. *Life Sci* 5:921-926.
- \*McMahon RE, Sullivan HR, Craig JC, et al. 1969. The microsomal oxygenation of ethylbenzene: Isotopic, stereochemical, and induction studies. *Arch Biochem Biophys* 132:575-577.
- +\*Mellert W, Deckhardt K, Kaufmann W, et al. 2007. Ethylbenzene: 4- and 13-week rat oral toxicity. *Arch Toxicol* 81:361-370.
- \*Meylan WM, Howard PH, Boethling RS, et al. 1999. Improved method for estimating bioconcentration/bioaccumulation factor from octanol/water partition coefficient. *Environ Toxicol Chem* 18(4):664-672.
- \*Michael LC, Erickson MD, Parks SP. 1980. Volatile environmental pollutants in biological matrices with a headspace purge technique. *Anal Chem* 52:1836-1841.
- +Mickiewicz W, Rzeczycki W. 1988. Effect of styrene and other alkyl benzene derivatives on oxidation of FAD- and NAD-linked substrates in rat liver mitochondria. *Biochem Pharmacol* 37(23):4439-4444.
- \*Midorikawa K, Uchida T, Okamoto Y, et al. 2004. Metabolic activation of carcinogenic ethylbenzene leads to oxidative DNA damage. *Chem Biol Interact* 150:271-281.
- Mill T. 1982. Hydrolysis and oxidation processes in the environment. *Environ Toxicol Chem* 1:135-141.
- Miller RL, Etre LS, Johansen NG. 1983a. Quantitative analysis of hydrocarbons by structural group type in gasolines and distillates. II. Liquid chromatography. *J Chromatogr* 259:393-412.
- Miller RL, Etre LS, Johansen NG. 1983b. Quantitative analysis of hydrocarbons by structural group type in gasolines and distillates. III. Combined use of liquid and gas chromatography. *J Chromatogr* 264:19-32.
- Ministry of Environment. 1999. Ambient water quality guidelines for ethylbenzene. British Columbia: Ministry of Environment. MIC10004289.  
<http://www.env.bc.ca/wat/wq/BCguidelines/ethylbenzene.html>. April 04, 2007.
- Minoia C, Meroni G, Aprea C, et al. 1996. Environmental and urinary reference values as markers of exposure to hydrocarbons in urban areas. *Sci Total Environ* 192(2):163-82.
- Miyake K, Kitaura F, Mizuno N, et al. 1987. Determination of partition coefficient and acid dissociation constant by high-performance liquid chromatography on porous polymer gel as a stationary phase. *Chem Pharmacol* 35:377-388.



## 9. REFERENCES

- \*Mohtashampur E, Norpoth K, Woelke U, et al. 1985. Effects of ethylbenzene, toluene, and xylene on the induction of micronuclei in bone marrow polychromatic erythrocytes of mice. *Arch Toxicol* 58:106-109.
- +\*Molnar J, Paksy KA, Naray M. 1986. Changes in the rat's motor behaviour during 4-hour inhalation exposure to preanesthetic concentrations of benzene and its derivatives. *Acta Physiol Hung* 67:349-354.
- +\*Morgan DL, Cooper SW, Carlock DL, et al. 1991. Dermal absorption of neat and aqueous volatile organic chemicals in the Fischer 344 rat. *Environ Res* 55(1):51-63.
- \*Morselli PL, Franco-Morselli R, Bossi L. 1980. Clinical pharmacokinetics in newborns and infants: Age related differences and therapeutic implications. *Clin Pharmacokinet* 5:485-527.
- +\*Moscato G, Biscaldi G, Cottica D, et al. 1987. Occupational asthma due to styrene: Two case reports. *J Occup Med* 29:957-960.
- \*Muhammad F, Monteiro-Riviere NA, Baynes RE, et al. 2005. Effect of *in vivo* jet fuel exposure on subsequent *in vitro* dermal absorption of individual aromatic and aliphatic hydrocarbon fuel constituents. *J Toxicol Environ Health* 68:719-737.
- \*Mukerjee S, Ellenson WD, Lewis RG, et al. 1997. An environmental scoping study in the Lower Rio Grande Valley of Texas: III. Residential microenvironmental monitoring for air, house dust, and soil. *Environ Int* 23(5):657-673.
- \*Mukund R, Kelly TJ, Spicer CW. 1996. Source attribution of ambient air toxic and other VOCs in Columbus, Ohio. *Atmos Environ* 30(20):3457-3470.
- Murray DAJ, Lockhart WL. 1981. Microextraction and gas chromatographic analysis of selected petroleum hydrocarbons in water and fish tissue. *J Chromatogr* 212:305-311.
- Mutti A, Franchini I. 1987. Toxicity of metabolites to dopaminergic systems and the behavioural effects. *Br J Ind Med* 44:721-723.
- +\*Mutti A, Falzoi H, Romanelli A, et al. 1988. Brain dopamine as a target for solvent toxicity: Effects of some monocyclic aromatic hydrocarbons. *Toxicology* 49:77-82.
- \*Nakajima T, Sato A. 1979. Enhanced activity of liver drug-metabolizing enzymes for aromatic and chlorinated hydrocarbons following food deprivation. *Toxicol Appl Pharmacol* 50:549-556.
- Namkung E, Rittmann BE. 1987. Estimating volatile organic compound emissions from publicly owned treatment works. *J Water Pollut Control Fed* 59:670-678.
- \*NAS. 1980. The alkyl benzenes. Washington, DC: National Academy of Sciences, I-16, IV-1 to IV-88.
- \*NAS/NRC. 1989. Report of the oversight committee. Biologic markers in reproductive toxicology. Washington, DC: National Academy of Sciences, National Research Council, National Academy Press, 15-35.
- \*Naskali L, Engelke M, Tahti H, et al. 1993. The effects of selected organic solvents on rat synaptosomal membrane fluidity and integral enzyme activities. *Neurosci Res Commun* 13(1):27-35.

## 9. REFERENCES

- \*Naskali L, Oksanen H, Tahti H. 1994. Astrocytes as targets for CNS effects of organic solvents *in vitro*. *Neurotoxicology* 15(3):609-612.
- \*Nestmann ER, Lee EG. 1983. Mutagenicity of constituents of pulp and papermill effluent in growing cells of *Saccharomyces cerevisiae*. *Mutat Res* 119:273-280.
- \*Nestmann ER, Lee EG, Matula TI, et al. 1980. Mutagenicity of constituents identified in pulp and paper mill effluents using the Salmonella/mammalian-microsome assay. *Mutat Res* 79:203-212.
- \*NFPA. 1994. Ethylbenzene. Fire protection guide to hazardous materials. 11th ed. Quincy, MA: National Fire Protection Association, 49-65, 325-348.
- Nicholson WJ, Tarr D. 1984. Occupational hazards in production and processing of styrene polymers - epidemiologic findings. *Industrial Hazards of Plastics and Synthetic Elastomers*. New York, NY: Alan R. Liss, Inc., 263-277.
- \*Nicola RM, Branchflower R, Pierce D. 1987. Chemical contaminants in bottomfish. *J Environ Health* 49:342-347.
- +\*Nielsen GD, Alarie Y. 1982. Sensory irritation, pulmonary irritation, and respiratory stimulation by airborne benzene and alkylbenzenes: Prediction of safe industrial exposure levels and correlation with their thermodynamic properties. *Toxicol Appl Pharmacol* 65:459-477.
- Niemi GJ, Veith GD, Regal RR, et al. 1987. Structural features associated with degradable and persistent chemicals. *Environ Toxicol Chem* 6:515-527.
- NIOSH. 1974. Health hazard evaluation/toxicity determination. ARCO Polymer Incorporated, Monaca, Pennsylvania. Cincinnati, OH: National Institute for Occupational Safety and Health. PB232729.
- +\*NIOSH. 1981. Teratologic assessment of ethylbenzene and 2-ethoxyethanol. Cincinnati, OH: National Institute for Occupational Safety and Health. PB83208074.
- NIOSH. 1984. NIOSH manual of analytical methods. Washington, DC: U.S. Department of Health, Education, and Welfare, Public Health Service, Center for Disease Control, National Institute for Occupational Safety and Health.
- \*NIOSH. 1990. Ethylbenzene. Estimated numbers of employees potentially exposed to specific agents by 2-digit Standard Industrial Classification (SIC). National Occupational Exposure Survey conducted from 1981-1983. Centers for Disease Control. National Institute for Occupational Safety and Health. <http://www.cdc.gov/noes/>. August 22, 2007.
- \*NIOSH. 1994a. Method 1501. NIOSH manual of analytical methods. Washington, DC: U.S. Department of Health, Education, and Welfare, Public Health Service, Center for Disease Control, National Institute for Occupational Safety and Health.
- NIOSH. 1994b. Ethylbenzene. NIOSH pocket guide to chemical hazards. U.S. Department of Health, Education, and Welfare, Public Health Service, Center for Disease Control, National Institute for Occupational Safety and Health, 132-133.

## 9. REFERENCES

- \*NIOSH. 1995. Report to Congress on workers' home contamination study conducted under the worker's family Protection Act (29 U.S.C. 671a). DHHS (NIOSH) Publication No. 95-123. PB96192000HEF.
- NIOSH. 1997. NIOSH pocket guide to chemical hazards. U.S. Department of Health and Human Services. Public Health Service. Centers for Disease Control and Prevention. National Institute for Occupational Safety and Health.
- NIOSH. 1999. Health Hazard Evaluation Report. Cincinnati, OH: National Institute for Occupational Safety and Health. HETA9701062770. PB2000107833.
- \*NIOSH. 2005. Ethylbenzene. NIOSH pocket guide to chemical hazards. Atlanta, GA: National Institute for Occupational Safety and Health, Centers for Disease Control and Prevention. <http://www.cdc.gov/niosh/npg/> April 11, 2007.
- NIOSH. 2006. NIOSH Health Hazard Evaluation Report - ACH Foam Technologies, Fond du Lac, Wisconsin. Washington: National Institute for Occupational Safety and Health. HETA No. 2005-0243-3016. PB 2006 115 469.
- \*NIOSH/OSHA. 1978. Occupational health guidelines for ethyl benzene. Washington, DC: National Institute for Occupational Safety and Health. Occupational Safety and Health Administration.
- \*Nishihara T, Nishikawa J, Kanayama T, et al. 2000. Estrogenic activities of 517 chemicals by yeast two-hybrid assay. *J Health Sci* 46(4):282-298.
- \*Norppa H, Vainio H. 1983a. Induction of sister-chromatid exchanges by styrene analogues in cultured human lymphocytes. *Mutat Res* 116:379-387.
- Norppa H, Vainio H. 1983b. Genetic toxicity of styrene and some of its derivatives. *Scand J Work Environ Health* 9:108-114.
- \*NRC. 1993. Pesticides in the diets of infants and children. National Research Council, Washington DC: National Academy Press. PB93216091.
- \*NTP. 1986. Toxicology and carcinogenesis studies of xylenes (mixed) (60% m-xylene, 14% p-xylene, 9%-xylene, and 17% ethylbenzene) in F334/N rats and B6C3F1 mice (gavage studies). Research Triangle Park, NC: National Toxicology Program. NTP TR 327.
- NTP. 1988a. National toxicology program: Review of current DHHS, DOE, and EPA research related to toxicology. Fiscal year 1988. Research Triangle Park, NC: U.S. Department of Health and Human Services, Public Health Service.
- NTP. 1988b. National toxicology program annual plan for fiscal year 1988. Research Triangle Park, NC: U.S. Department of Health and Human Services, Public Health Service, National Toxicology Program.
- +\*NTP. 1992. Toxicity studies of ethylbenzene in F344/N rats and B6C3F1 mice (inhalation studies). Research Triangle Park, NC: National Toxicology Program. NTP Tox 10. <http://inmagic.syrres.com/esc-images/NTIS/NTP/TOX010.pdf>. August 02, 2007.

## 9. REFERENCES

- +\*NTP. 1999. NTP technical report on the toxicology and carcinogenesis studies of ethylbenzene in F344/N rats and B6C3F1 mice (inhalation studies). Research Triangle Park, NC: National Toxicology Program, U.S. Department of Health and Human Services. NTP TR 466.
- \*NTP. 2005. Report on carcinogens. 11 ed. Research Triangle Park, NC: U.S. Department of Health and Human Services, Public Health Service National Toxicology Program. <http://ntp-server.niehs.nih.gov/ntp/roc/toc11.html>. March 08, 2006.
- \*Nunes P, Benville PE. 1979. Uptake and depuration of petroleum hydrocarbons in the Manila clam, *Tapes semidecussata* reeve. *Bull Environ Contam Toxicol* 21:719-726.
- Nutmagul W, Cronn DR, Hill HH. 1983. Photoionization-flame-ionization detection of atmospheric hydrocarbons after capillary gas chromatography. *Anal Chem* 55:2160-2164.
- Nyska A, Haseman JK, Hailey JR, et al. 1999. The association between severe nephropathy and pheochromocytoma in the male F344 rat-The National Toxicology Program experience. *Toxicol Pathol* 27(4):456-462.
- O'Brien RJ, Holmes JR, Bockian AH. 1975. Formation of photochemical aerosol from hydrocarbons chemical reactivity and products. *Environ Sci Technol* 9:568-576.
- \*Ogata M, Taguchi T. 1987. Quantitation of urinary metabolites of toluene, xylene, styrene, ethylbenzene, benzene and phenol by automated high-performance liquid chromatography. *Int Arch Occup Environ Health* 59:263-272.
- +\*Ogata M, Taguchi T. 1988. Simultaneous determination of urinary creatinine and metabolites of toluene, xylene, styrene, ethylbenzene and phenol by automated high performance liquid chromatography. *Environ Health* 61(1/2):131-140.
- \*Ogata M, Fujisawa K, Ogino Y, et al. 1984. Partition coefficients as a measure of bioconcentration potential of crude oil compounds in fish and shellfish. *Bull Environ Contam Toxicol* 33:561-567.
- \*Ohta T, Ohyama T. 1985. A set of rate constants for the reactions of OH radicals with aromatic hydrocarbons. *Bull Chem Soc Jpn* 58:3029-3030.
- \*Oliver KD, Adams JR, Daughtrey EH, et al. 1996. Technique for monitoring toxic VOCs in air: Sorbent preconcentration, closed-cycle cooler cryofocusing and GC/MS analysis. *Environ Sci Technol* 30:1939-1945.
- Opdyke DLJ. 1975. Monographs on fragrance raw materials. *Food Cosmet Toxicol* 13:803-804.
- Osborn AG, Scott DW. 1980. Vapor pressures of 17 miscellaneous organic compounds. *J Chem Thermodynamic* 12:429-438.
- OSHA. 1974. Air contaminants. Occupational Safety and Health Administration. Code of Federal Regulations. 29 CFR 1910.1000.
- \*OSHA. 2006a. Air contaminants. Occupational safety and health standards for shipyard employment. Occupational Safety and Health Administration. Code of Federal Regulations. 29 CFR 1915.1000 <http://www.osha.gov/comp-links.html>. April 11, 2007.

## 9. REFERENCES

- \*OSHA. 2006b. Gases, vapors, fumes, dusts, and mists. Safety and health regulations for construction. Occupational Safety and Health Administration. Code of Federal Regulations. 29 CFR 1926.55, Appendix A. <http://www.osha.gov/comp-links.html>. April 11, 2007.
- \*OSHA. 2006c. Limits for air contaminants. Occupational safety and health standards. Occupational Safety and Health Administration. Code of Federal Regulations. 29 CFR 1910.1000. <http://www.osha.gov/comp-links.html>. April 11, 2007.
- \*OTA. 1990. Neurotoxicity: Identifying and controlling poisons of the nervous system. Washington, DC: Office of Technology Assessment. OTABA438.
- Otson R. 1987. Sample handling and analysis for 51 volatile organics by an adapted purge and trap GC-MS technique. *Int J Environ Anal Chem* 30:275-287.
- \*Otson R, Chan C. 1987. Sample handling and analysis for 51 volatile organics by an adapted purge and trap GC-MS technique. *Int J Environ Anal Chem* 30:275-287.
- \*Otson R, Kumarathasan P. 1995. An automated head space analysis method for xylenes and ethylbenzene in blood and water. *Chemosphere* 30(6):1109-1123.
- \*Otson R, Williams DT. 1981. Evaluation of a liquid-liquid extraction technique for water pollutants. *J Chromatogr* 212:187-198.
- \*Otson R, Williams DT. 1982. Headspace chromatographic determination of water pollutants. *Anal Chem* 54:942-946.
- \*Otson R, Fellin P, Tran Q. 1994. VOCs in representative Canadian residences. *Atmos Environ* 28(22):3563-3569.
- \*Overton EB, Stewart M, Carney R. 1995. Instrumental consideration for reliable fieldable VOC analyses. *J Hazard Mater* 43:77-89.
- \*Owen GM, Brozek J. 1966. Influence of age, sex, and nutrition on body composition during childhood and adolescence. In: Falkner F, ed. *Human development*. Philadelphia, PA: Saunders, 222-238.
- Paolini M, Potenza G, Biagi GL, et al. 2001. Re: Ethylbenzene induces microsomal oxygen free radical generation: Antibody-directed characterization of the responsible cytochrome P450 enzymes. *Toxicol Appl Pharmacol* 173(3):188-189.
- Patterson JW, Kodukala PS. 1981. Biodegradation of hazardous organic pollutants. *Chem Eng Prog* 77:48-55.
- Pelekis M, Krishnan K. 2004. Magnitude and mechanistic determinants of the interspecies toxicokinetic uncertainty factor for organic chemicals. *Regul Toxicol Pharmacol* 40(3):264-271.
- +\*Pellizzari ED, Hartwell TD, Harris BSH, et al. 1982. Purgeable organic compounds in mother's milk. *Bull Environ Contam Toxicol* 28:322-328.
- \*Pellizzari ED, Sheldon L, Keever J, et al. 1993. Determination of airborne organic compounds using tenax GC and gas chromatography mass spectrometry. *Environmental carcinogens selected methods of*

## 9. REFERENCES

analysis. Vol 7. IARC Publication No. 68. Lyon, France: International Agency for the Research on Cancer, 196-210.

\*Pellizzari ED, Zweidinger RA, Sheldon LS. 1985. Method 23: Breath sampling. Environmental carcinogens selected methods of analysis. Vol 7. IARC Publication No. 68. Lyon, France: International Agency for the Research of Cancer, 399-411.

Perbellini L, Pasini F, Romani S, et al. 2002. Analysis of benzene, toluene, ethylbenzene and *m*-xylene in biological samples from the general population. J Chromatogr B Analyt Technol Biomed Life Sci 778:199-210.

Pereira WE, Rostad CE, Taylor H E, et al. 1982. Characterization of organic contaminants in environmental samples associated with Mount St. Helens 1980 volcanic eruption. Environ Sci Technol 16:387-396.

Pettersson B, Curvall M, Enzell CR. 1980. Effects of tobacco smoke compounds on the noradrenaline induced oxidative metabolism in isolated brownfat cells. Toxicology 18:1-15.

Phelps CD, Young LY. 1999. Anaerobic biodegradation of BTEX and gasoline in various aquatic sediments. Biodegradation 10(1):15-25.

\*Pierce CH, Dills RL, Silvey GW, et al. 1996. Partition coefficients between human blood or adipose tissue and air for aromatic solvents. Scand J Work Environ Health 22:112-118.

Pilotti A, Ancker K, Arrhenius E, et al. 1975. Effects of tobacco and tobacco smoke constituents on cell multiplication *in vitro*. Toxicology 5:49-62.

Pleil JD, Oliver KD, McClenny WA. 1988. Ambient air analysis using nonspecific flame ionization and electron capture detection compared to specific detection by mass spec. J Air Pollut Control Assoc 38:1006-1010.

\*Plumb RH. 1991. The occurrence of Appendix IX organic constituents in disposal site ground water. Ground Water Monit Rev 11(2):157-164.

Pohl HR, Roney N, Wilbur S, et al. 2003. Six interaction profiles for simple mixtures. Chemosphere 53(2):183-197.

\*Polak J, Lu BCY. 1973. Mutual solubilities of hydrocarbons and water at 0 and 25 C. Can J Chem 51:4018-4023.

Possanzini M, Ciccio P, Brancaloni E, et al. 1982. Gas chromatographic detection of hydrocarbons in the atmosphere using specific GC detectors and mass spectrometry in selected ion monitoring mode. Comm Eur Communities. Phys Chem Behav Atmos Pollut 7624:76-81.

\*Potter TL. 1993. Analysis of petroleum contaminated soil and water: An overview. In: Calabrese EJ, Kostecki PT, eds. Principles and practices for petroleum contaminated soils. Boca Raton, FL: Lewis Publishers, 1-14.

\*Proctor NH, Hughes JP. 1978. Ethylbenzene. In: Chemical hazards of the workplace. Philadelphia, PA: J.B. Lippincott Company, 251-252.

## 9. REFERENCES

- \*Ptacek CJ, Cherry JA, Gillham RW. 1984. Mobility of dissolved petroleum derived hydrocarbon in sand aquifers. In: Vandermeulen JH, Hrudey SE, eds. Oil in freshwater: Chemistry, biology, countermeasure technology. New York, NY: Pergamon Press, 195-212.
- +\*Pyykko K, Paavilainen S, Metsa-Ketela T, et al. 1987. The increasing and decreasing effects of aromatic hydrocarbon solvents on pulmonary and hepatic cytochrome P-450 in the rat. *Pharmacol Toxicol* 60:288-293.
- \*Quigley CJ, Corsi RL. 1995. Emissions of VOCs from a municipal sewer. *J Air Waste Manage Assoc* 45:395-403.
- Radzikowska-Kintzi H, Jakubowski M. 1981. Internal standardization in the head space analysis of organic solvents in blood. *Int Arch Occup Environ Health* 49:115-123.
- \*Ramanand K, Balba MT, Duffy J. 1995. Biodegradation of select organic pollutants in soil columns under denitrifying conditions. *Haz Waste Haz Mater* 12(1):27-36.
- \*Ransley DL. 1984. Xylenes and ethylbenzene. In: Grayson M, ed. *Kirk-Othmer encyclopedia of chemical technology*. Vol. 24. New York, NY: John Wiley & Sons, 709-744.
- \*Rao PSC, Hornsley AG, Kilcrease DF, et al. 1985. Sorption and transport of hydrophobic organic chemicals in aqueous and mixed solvent systems: Model development and preliminary evaluation. *J Environ Qual* 14:376-382
- \*Rappaport SM, Selvin S, Waters MA. 1987. Exposure to hydrocarbon components of gasoline in the petroleum industry. *Appl Ind Hyg* 2:148-154.
- \*Ravishankara AR, Wagner S, Fischer S, et al. 1978. A kinetics study of the reactions of hydroxyl with several aromatic and olefinic compounds. *Int J Chem Kinet* 10:783-804.
- \*Raykar PV, Fung MC, Anderson BD. 1988. The role of protein and lipid domains in the uptake of solutes by human stratum corneum. *Pharmacol Res* 5(3):140-150.
- Reisch MS. 1994. Top 50 chemicals production rose modestly last year. *Chem Eng News* 72(15):12-15.
- Reutman SR, LeMasters GK, Knecht EA, et al. 2002. Evidence of reproductive endocrine effects in women with occupational fuel and solvent exposures. *Environ Health Perspect* 110(8):805-811.
- \*Rhue RD, Rao PSC, Smith RE. 1988. Vapor-phase adsorption of alkyl benzenes and water on soils and clays. *Chemosphere* 17:727-741.
- Ribbons DW, Eaton RW. 1982. Chemical transformations of aromatic hydrocarbons that support the growth. In: Chakrabarty AM, ed. *Biodegradation and detoxification of environmental pollutants*. CRC Press, Inc., 59-84.
- \*Riedel K, Ruppert T, Conze C, et al. 1996. Determination of benzene and alkylated benzenes in ambient and exhaled air by microwave desorption coupled with gas chromatography-mass spectrometry. *J Chromatogr A* 719(2):383-389.

## 9. REFERENCES

- +Roberfroid M, Poncelet F, Lambotte-Vandepaer M, et al. 1978. Acute biotoxic effect of styrene on rat liver. Correlation with enzyme-mediated mutagenicity of benzpyrene and acrylonitrile. *Scand J Work Environ Health* 4:163-168.
- \*Roberts MS, Triggs EJ, Anderson RA. 1975. Permeability of solutes through biological membranes measured by a desorption technique. *Nature* 257:225-227.
- +\*Romanelli A, Falzoi M, Mutti A, et al. 1986. Effects of some monocyclic aromatic solvents and their metabolites on brain dopamine in rabbits. *J Appl Toxicol* 6(6):431-435.
- \*Romer KG, Federsel RJ, Freundt KJ. 1986. Rise of inhaled toluene, ethyl benzene, m-xylene, or mesitylene in rat blood after treatment with ethanol. *Bull Environ Contam Toxicol* 37:874-876.
- \*Rosen AA, Skeel RT, Ettinger MB. 1963. Relationship of river water odor to specific organic contaminants. *J Water Pollut Cont Fed* 35:777-782.
- \*Rosenfeld JK, Plumb RH. 1991. Ground water contamination at wood treatment facilities. *Ground Water Monit Rev* 11:133-140.
- Rosenkranz HS, Karol MH. 1999. Chemical carcinogenicity: Can it be predicted from knowledge of mutagenicity and allergic contact dermatitis? *Mutat Res* 431(1):81-91.
- \*Rowell LB. 1986. Human circulation, regulation during physical stress. New York, NY: Oxford University Press, Inc., 96-98
- Roy WR, Griffin RA. 1985. Mobility of organic solvents in water-saturated soil materials. *Environ Geol Water Sci* 7:241-247.
- \*RTECS. 2007. Ethylbenzene. Registry of Toxic Effects on Chemical Substances. National Institute of Occupational Safety and Health. MDL Information Systems, Inc. May 8, 2007.
- Rumchev K, Spickett J, Bulsara M, et al. 2004. Association of domestic exposure to volatile organic compounds with asthma in young children. *Thorax* 59(9):746-751.
- Sabljić A. 1984. Prediction of the nature and strength of soil sorption of organic pollutants by molecular topology. *J Agric Food Chem* 32:243-246.
- Sabljić A. 1987. On the prediction of soil sorption coefficients of organic pollutants from molecular structure: Application of molecular topology model. *Environ Sci Technol* 21:358-366.
- \*Sack TM, Steele DH, Hammerstrom K, et al. 1992. A survey of household products for volatile organic compounds. *Atmos Environ* 26A(6):1063-1070.
- +\*Saillefait AM, Gallissot F, Morel G, et al. 2003. Developmental toxicities of ethylbenzene, *ortho*-, *meta*-, *para*-xylene and technical xylenes in rats following inhalation exposure. *Food Chem Toxicol* 41:415-429.
- +\*Saillefait AM, Gallissot F, Sabate JP, et al. 2006. Developmental toxicity of combined ethylbenzene and methylethylketone administered by inhalation to rats. *Food Chem Toxicol* 44(8):1287-1298.



## 9. REFERENCES

- +\*Saillefait AM, Gallissot F, Sabate JP, et al. 2007. Developmental toxic effects of ethylbenzene to toluene alone and in combination with butyl acetate in rats after inhalation exposure. *J Appl Toxicol* 27(1):32-42.
- \*Sams C, Loizou GD, Crocker J, et al. 2004. Metabolism of ethylbenzene by human liver microsomes and recombinant human cytochrome P450s (CYP). *Toxicol Lett* 147(3):253-260.
- Sanemasa I, Araki M, Deguchi T, et al. 1981. Solubilities of benzene and the alkylbenzenes in water - method for obtaining aqueous solutions saturated with vapors in equilibrium with organic liquids. *Chem Lett* 2:225.
- Sanemasa I, Araki M, Deguchi T, et al. 1982. Solubility measurements of benzene and the alkylbenzenes in water by making use of solute vapor. *Bull Chem Soc Jpn* 55:1054-1062.
- Sato A, Nakajima T. 1979. Partition coefficients of some aromatic hydrocarbons and ketones in water, blood, and oil. *Br J Ind Med* 36:231-234.
- \*Sauer PA, Tyler EJ. 1995. Heavy metal and volatile organic chemical removal and treatment in on-site wastewater infiltration systems. I. Catch basins and septic tanks. *Water Air Soil Pollut* 89:221-232.
- Sauer TC. 1981. Volatile organic compounds in open ocean and coastal surface waters. *Org Geochem* 3:91-101.
- \*Sauer TC, Sackett WM, Jeffrey LM. 1978. Volatile liquid hydrocarbons in the surface coastal waters of the Gulf of Mexico. *Mar Chem* 7:1-16.
- \*Sax NI, Lewis RJ. 1989. Dangerous properties of industrial materials. Vol. II. 7th ed. New York, NY: Van Nostrand Reinhold, 1601.
- Sax SN, Bennett DH, Chillrud SN, et al. 2006. A cancer risk assessment of inner-city teenagers living in New York City and Los Angeles. *Environ Health Perspect* 114:1558-1566.
- \*Scheuplein RJ. 1976. Permeability of the skin: A review of some major concepts. *J Invest Dermatol* 67:672-676.
- Scheuplein RJ, Blank IH, Brauner GJ, et al. 1969. Percutaneous absorption of steroids. *J Invest Dermatol* 52(1):63-70.
- Schirmer RE, Pahl TR, Phelps DW. 1984. Application of internal standards in routine vapor measurements by gas chromatography. *Am Ind Hyg Assoc J* 45:95-98.
- \*Schuberth J. 1996. A full evaporation headspace technique with capillary GC and ITD: A means for quantitating volatile organic compounds in biological samples. *J Chromatogr Sci* 34(7):314-319.
- Schwarz FP, Miller J. 1980. Determination of the aqueous solubilities of organic liquids at 10.0, 20.0 and 30.0 C by elution chromatography. *Anal Chem* 52:2162-2164.
- \*Seely JC, Haseman JK, Nyska A, et al. 2002. Effect of chronic progressive nephropathy on the incidence of renal tubule cell neoplasms in control male F344 rats. *Toxicol Pathol* 30(6):681-686.

## 9. REFERENCES

- Selvakumar A, Hsieh HN. 1987. Absorption of organic compounds by microbial biomass. *Int J Environ Stud* 30:313-319.
- +Sequeira DJ, Eyer CS, Cawley GF, et al. 1992. Ethylbenzene-mediated induction of cytochrome P450 isozymes in male and female rats. *Biochem Pharmacol* 44(6):1171-1182.
- Serra JR, Thompson ED, Jurs PC. 2003. Development of binary classification of structural chromosome aberrations for a diverse set of organic compounds from molecular structure. *Chem Res Toxicol* 16(2):153-163.
- Serron SC, Dwivedi N, Backes WL. 2000. Ethylbenzene induces microsomal oxygen free radical generation: Antibody-directed characterization of the responsible cytochrome P450 enzymes. *Toxicol Appl Pharmacol* 164(3):305-311.
- Serron SC, Zhang S, Bergeron RM, et al. 2001. Effect of hypophysectomy and growth hormone replacement on the modulation of P450 expression after treatment with the aromatic hydrocarbon ethylbenzene. *Toxicol Appl Pharmacol* 172(3):163-171.
- \*Setchell BP, Waites GMH. 1975. The blood-testis barrier. In: Creep RO, Astwood EB, Geiger SR, eds. *Handbook of physiology: Endocrinology V*. Washington, DC: American Physiological Society, 143-172.
- \*Seto Y. 1994. Determination of volatile substances in biological samples by headspace gas chromatography. *J Chromatogr A* 674:25-62.
- \*Sexton K, Adgate JL, Church TR, et al. 2005. Children's exposure to volatile organic compounds as determined by longitudinal measurements in blood. *Environ Health Perspect* 113(3):342-349.
- Sgaragli G, Della Corte L, Rizzotti-Conti M, et al. 1977. Effects of monocyclic compounds on biomembranes. *Biomed Pharmacol* 26:2145-2149.
- +\*Shatkin JA, Brown HS. 1991. Pharmacokinetics of the dermal route of exposure to volatile organic chemicals in water: A computer simulation model. *Environ Res* 56(1):90-108.
- Shen TT. 1982. Estimation of organic compound emissions from waste lagoons. *J Air Pollut Control Assoc* 32:79-82.
- Shen Y. 1998. *In vitro* cytotoxicity of BTEX metabolites in Hela cells. *Arch Environ Contam Toxicol* 34:229-234.
- Shields HC, Weschler CJ. 1987. Analysis of ambient concentrations of organic vapors with a passive sampler. *J Air Pollut Control Fed* 37:1039-1045.
- Shinohara R, Kido A, Eto S, et al. 1981. Identification and determination of trace organic substances in tap water by computerized gas chromatography-mass spectrometry and mass fragmentography. *Water Res* 15:535-542.
- \*Shirey RE. 1995. Rapid analysis of environmental samples using solid-phase microextraction (SPME) and narrow bore capillary columns. *J High Resol Chromatogr* 18(8):495-499.

## 9. REFERENCES

- Shoji R, Sakoda A, Sakai Y, et al. 2000. A new assay for evaluating hepatotoxicity and cytotoxicity using LDL-uptake activity of liver cells. *J Health Sci* 46(6):493-502.
- \*Sikkema J, De Bont J AM, Poolman B. 1995. Mechanisms of membrane toxicity of hydrocarbons. *Microbiol Rev* 59(2):201-222.
- Simpson S, Lemasters G, Kesner J, et al. 2000. Internal dose of benzene, ethyl-benzene, toluene & xylenes & fuel components and effects on reproductive hormones in women. *Am J Epidemiol* 151:11.
- \*Singh HB, Salas LJ, Cantrell BK, et al. 1985. Distribution of aromatic hydrocarbons in the ambient air. *Atmos Environ* 19:1911-1919.
- \*Singh HG, Salas LJ, Smith AJ, et al. 1981. Measurements of some potentially hazardous organic chemicals in urban environments. *Atmos Environ* 15:601-612.
- Skender L, Brcic I, Karacic V. 2004. Urine analysis for the evaluation of environmental exposures to aromatic hydrocarbons. *Arch Environ Health* 59(5):237-244.
- \*Sliwiska-Kowalska M, Zamyslowska-Szmytke E, Szymczak W, et al. 2001. Hearing loss among workers exposed to moderate concentrations of solvents. *Scand J Work Environ Health* 27(5):335-342.
- +\*Smith JN, Smithies RH, Williams RT. 1954a. The metabolism of alkylbenzenes. Stereochemical aspects of the biological hydroxylation of ethylbenzene to methylphenylcarbinol. *Biochem J* 56:320-324.
- +\*Smith JN, Smithies RH, Williams RT. 1954b. The metabolism of alkylbenzenes. (a) Glucuronic acid excretion following the administration of alkylbenzenes. (b) Elimination of toluene in the expired air of rabbits. *Biochem J* 56:317-320.
- +\*Smyth H, Carpenter CP, Weil CS, et al. 1962. Range finding toxicity data: List VI. *Am Ind Hyg Assoc J* 23:95-107.
- \*Snider EH, Manning FS. 1982. A survey of pollutant emission levels in wastewaters and residuals from the petroleum refining industry. *Environ Int* 7:237-258.
- +\*Sollenberg J, Smallwood AW, Lowry LK. 1985. Determination of mandelic and phenylglyoxylic acids in rat urine by high- performance liquid chromatography and by isotachopheresis. *J Chromatogr* 343:175-178.
- Spiller HA. 2001. Chronic occupational exposure to aromatic hydrocarbon gases associated with dysmenorrhea, dysfunctional uterine bleeding and CNS effects. *J Toxicol Clin Toxicol* 39(5):525.
- \*Sram RJ, Beskid O, Binkova B, et al. 2004. Cytogenic analysis using fluorescence *in situ* hybridization (FISH) to evaluate occupational exposure to carcinogens. *Toxicol Lett* 149:335-344.
- SRI. 1988. Ethylbenzene. *Directory of chemical producers: United States of America..* Menlo Park, CA: SRI International, 608-609.
- SRI. 1990. Ethylbenzene. *Directory of chemical producers: United States of America.* Menlo Park, CA: SRI International, 610.

## 9. REFERENCES

- SRI. 1992. Ethylbenzene. Directory of chemical producers: United States of America. Menlo Park, CA: SRI International, 609-610.
- SRI. 1994. Ethylbenzene. Directory of chemical producers: United States of America. Menlo Park, CA: SRI International, 591.
- SRI. 1995. Ethylbenzene. Directory of chemical producers: United States of America. Menlo Park, CA: SRI International, 586.
- SRI. 1996. Ethylbenzene. Directory of chemical producers: United States of America. Menlo Park, CA: SRI International, 580.
- \*SRI. 2006. Ethylbenzene. Directory of chemical producers: United States of America. Menlo Park, CA: SRI International, 593.
- \*Staples CA, Werner AF, Hoogheem TJ. 1985. Assessment of priority pollutant concentrations in the United States using STORET database. *Environ Toxicol Chem* 4:131-142.
- Stein V, Narang S. 1990. A simplified method for the determination of volatiles in eggs using headspace analysis with a photoionization detector. *Arch Environ Contam Toxicol* 19:593-596.
- \*St-Germain F, Mamer O, Brunet J, et al. 1995. Volatile organic compound analysis by an inertial spray extraction interface coupled to an ion trap mass spectrometer. *Anal Chem* 67:4536-4541.
- \*Stein VB, Narang RS. 1990. A simplified method for the determination of volatiles in eggs using headspace analysis with a photoionization detector. *Arch Environ Contam Toxicol* 19:593-596.
- \*Stokman SK. 1987. Estimations of concentrations of soluble petroleum hydrocarbons migrating into ground water from contaminated soil sources. Proceedings of the NWWA/API conference on petroleum hydrocarbons and organic chemicals in groundwater: Prevention, detection and restoration, Houston, Texas, November 1987. Dublin, OH: National Water Well Association, 541-558.
- \*Stott WT, Johnson KA, Bahnemann R, et al. 2003. Evaluation of potential modes of action of inhaled ethylbenzene in rats and mice. *Toxicol Sci* 71:53-66.
- \*Stubin AI, Brosnan TM, Porter KD, et al. 1996. Organic priority pollutants in New York City municipal wastewaters: 1989-1993. *Water Environ Res* 68(6):1037-1044.
- \*Stuermer DH, Ng DJ, Morris CJ. 1982. Organic contaminants in groundwater near an underground coal gasification site in northeastern Wyoming. *Environ Sci Technol* 16:582-587.
- \*Sugita T, Ishiwata H, Kawamura Y, et al. 1995. Headspace gas chromatographic analysis of residual volatile substances in polystyrene food containers. *J Food Hyg Soc Jpn* 36(2):263-268. (Japanese).
- +\*Sullivan HR, Miller WM, McMahon RE. 1976. Reaction pathways of *in vivo* stereoselective conversion of ethylbenzene to (-)-mandelic acid. *Xenobiotica* 6:49-54.
- +\*Susten AS, Niemeier RW, Simon SD. 1990. *In vivo* percutaneous absorption studies of volatile organic solvents in hairless mice. II. Toluene, ethylbenzene and aniline. *J Appl Toxicol* 10(3):217-225.

## 9. REFERENCES

- \*Sutton C, Calder JA. 1975. Solubility of alkylbenzenes in distilled and seawater 25.0°C. *J Chem Eng Data* 20:320-322.
- \*Swann RL, Laskowski DA, McCall PJ, et al. 1983. A rapid method for the estimation of the environmental parameters octanol/water partition coefficient, soil sorption constant, water to air ratio, and water solubility. *Residue Rev* 85:17-28.
- Swedrowska H, Jarnuszkiewicz I, Slebioda K. 1986. Application of gas chromatography in conjunction with enrichment of samples on active carbon to determine low concentrations of organic compounds in air. Part I. Aromatic hydrocarbons. *Bull Inst Marit Trop Med Gdynia* 37:103-112.
- Takeuchi A, Kawai T, Zhang ZW, et al. 2002. Toluene, xylenes and xylene isomers in urine as biological indicators of low-level exposure to each solvent; a comparative study. *Int Arch Occup Environ Health* 75:387-393.
- Takeuchi Y, Ono Y, Hisanaga N, et al. 1982. Environmental and health surveys on car repair workers exposed to organic solvents. *Jpn J Ind Health* 24:305-313.
- \*Tang W, Hemm I, Eisenbrand G. 2000. Estimation of human exposure to styrene and ethylbenzene. *Toxicology* 144:39-50.
- +Tanii H, Huang J, Hashimoto K. 1995. Structure-acute toxicity relationship of aromatic hydrocarbons in mice. *Toxicol Lett* 76(1):27-31.
- +\*Tardif R, Charest-Tardif G, Brodeur J. 1996. Comparison of the influence of binary mixtures versus a ternary mixture of inhaled aromatic hydrocarbons on their blood kinetics in the rat. *Arch Toxicol* 70(7):405-13.
- \*Tardif R, Charest-Tarif G, Brodeur J, et al. 1997. Physiologically based pharmacokinetic modeling of a ternary mixture of alkyl benzenes in rats and humans. *Toxicol Appl Pharmacol* 144:120-134.
- \*Tardif R, Laparé S, Plaa GL, et al. 1991. Effect of simultaneous exposure to toluene and xylene on their respective biological exposure indices in humans. *Int Arch Occup Environ Health* 63:279-284.
- Tatrai E, Balogh T, Baca G, et al. 1982. [Embryotoxic effect of ethylbenzene]. *Egeszsegstudomány* 26:297-303. (Hungarian)
- +\*Tegeris JS, Balster RL. 1994. A comparison of the acute behavioral effects of alkylbenzenes using a functional observational battery in mice. *Fundam Appl Toxicol* 22(2):240-250.
- \*Tester DJ, Harker RJ. 1981. Groundwater pollution investigations in the Great Ouse Basin. *Water Pollut Control* 80:614-631.
- Thelestram M, Curvall M, Enzell CR. 1980. Effect of tobacco smoke compounds on the plasma membrane of cultured human lung fibroblasts. *Toxicology* 15:203-217.
- \*Thienes C, Haley TJ. 1972. *Clinical toxicology*. 5th ed. Philadelphia, PA: Lea and Febiger, 126-127.
- \*Thomas K, Colborn T. 1992. Organochlorine endocrine disruptors in human tissue. In: Colborn T, Clement C, eds. *Chemically induced alterations in sexual and functional development: The wildlife/human connection*. Princeton, NJ: Princeton Scientific Publishing, 65-394.

## 9. REFERENCES

- +\*Thomas KW, Pellizzari ED, Cooper SD. 1991. A canister-based method for collection and GC/MS analysis of volatile organic compounds in human breath. *J Anal Toxicol* 15(2):54-59.
- \*Thomas KW, Pellizzari ED, Raymer JH, et al. 1992. Kinetics of low-level volatile organic compounds in breath - I. Experimental design and data quality. *J Exp Anal Environ Epidemiol* 2(2):45-66.
- +\*Toftgard R, Nilsen OG. 1982. Effects of xylene and xylene isomers on cytochrome P-450 and *in vitro* enzymatic activities in rat liver kidney and lung. *Toxicology* 23:197-212.
- \*TRI05. 2007. TRI explorer: Providing access to EPA's toxics release inventory data. Washington, DC: Office of Information Analysis and Access. Office of Environmental Information. U.S. Environmental Protection Agency. Toxics Release Inventory. <http://www.epa.gov/triexplorer/>. March 08, 2007.
- \*Tsuruta H. 1982. Percutaneous absorption of organic solvents: III. On the penetration rates of hydrophobic solvents through excised rat skin. *Ind Health* 20:335-346.
- +\*Ungvary G. 1986. Solvent effects on reproduction: Experimental toxicity. *Prog Clin Biol Res* 220:169-177.
- +\*Ungváry G, Tátrai E. 1985. On the embryotoxic effects of benzene and its alkyl derivatives in mice, rats and rabbits. *Arch Toxicol Suppl* 8:425-430.
- Uno I, Wakamatsu S, Wadden RA, et al. 1985. Evaluation of hydrogen reactivity in urban air. *Atmos Environ* 19:1283-1293.
- U.S. Air Force. 2000. Historical air emissions estimate, Kelly Air Force Base, TX. Brooks Air Force Base: Air Force Institute for Environment, Safety and Occupational Health Risk Analysis. IERARSBRSR20000012. ADA387077.
- U.S. Congress. 1986. Hazardous air pollutants. Clean Air Act, Title 3.
- \*USGS. 2006. Volatile organic compounds in the Nation's ground water and drinking-water supply wells. Reston, VA: U.S. Department of the Interior, U.S. Geological Survey.
- USITC. 1987. Synthetic organic chemicals: United States production and sales, 1986. USITC Publication 2009. Washington, DC: U.S. International Trade Commission, 26, 39.
- USITC. 1994. Preliminary report on U.S. production of selected synthetic organic chemicals (including synthetic plastics and resin materials): First quarter, second quarter, and cumulative totals, 1994. U.S. International Trade Commission.
- \*Vaalavirta L, Tähti H. 1995a. Astrocyte membrane Na<sup>+</sup>, K<sup>(+)</sup>-ATPase and Mg<sup>(2+)</sup>-ATPase as targets of organic solvent impact. *Life Sci* 57(24):2223-2230.
- \*Vaalavirta L, Tähti H. 1995b. Effects of selected organic solvents on the astrocyte membrane ATPase *in vitro*. *Clin Exper Pharmacol Physiol* 22(4):293-294.
- \*Van der Linden AC, Thijsse GJE. 1965. The mechanisms of microbial oxidations of petroleum hydrocarbons. *Adv Enzymol* 27:469-546.

## 9. REFERENCES

- van Thriel C, Haumann K, Kiesswetter E, et al. 2002. Time courses of sensory irritations due to 2-butanone and ethyl benzene exposure: Influences of self-reported multiple chemical sensitivity (sMCS). *Int J Hyg Environ Health* 204:367-369.
- \*Verhoeff AP, Suk J, Van Wijnen JH. 1988. Residential indoor air contamination by screen printing plants. *Int Arch Occup Environ Health* 60:201-209.
- \*Verschuere K. 1983. *Handbook of environmental data on organic chemicals*. 2nd ed. New York, NY: Van Nostrand Reinhold Co., 628-630.
- Veulemans H, Groeseneken D, Masschelein R, et al. 1987. Survey of ethylene glycol ether exposures in Belgian industries and workshops. *Am Ind Hyg Assoc J* 48:671-677.
- \*Vieira I, Sonnier M, Cresteil T. 1996. Developmental expression of CYP2E1 in the human liver: Hypermethylation control of gene expression during the neonatal period. *Eur J Biochem* 238(2):476-483.
- Vleminckx C, Klemans W, Schriewer L, et al. 1997. Performance of cytogenetic biomarkers on children exposed to environmental pollutants. *Toxicol Ind Health* 13 (2-3):219-230.
- Von Oettingen WF, Neal PA, Donahue DD. 1942. The toxicity and potential danger of toluene. *J Am Med Assoc* 118:579-584.
- \*Vowles PD, Mantoura RFC. 1987. Sediment-water partition coefficients and HPLC retention factors of aromatic hydrocarbons. *Chemosphere* 16:109-116.
- Voznakova Z, Popl M, Berka M. 1978. Recovery of aromatic hydrocarbons from water. *J Chromatogr Sci* 16:123-127.
- Waddell WJ. 2004. Analysis of thresholds for carcinogenicity. *Toxicol Lett* 149(1-3):415-419.
- \*Wadden RA, Scheff PA, Franke JE, et al. 1995. VOC emission rates and emission factors for a sheet fed offset printing shop. *Am Ind Hyg Assoc J* 56:368-376.
- \*Wade OL, Bishop JM, Donald KW. 1962. *Cardiac output and regional blood flow*. Oxford: Blackwell Scientific Publications, 86-107.
- \*Wakeham SG, Davis AC, Karas JL. 1983. Mesocosm experiments to determine the fate and persistence of volatile organic compound in coastal seawater. *Environ Sci Technol* 17:611-617.
- \*Wallace L, Pellizzari E, Hartwell T, et al. 1986. Concentrations of 20 volatile organic compounds in the air and drinking water of 350 residents of New Jersey compared with concentrations in their exhaled breath. *J Occup Med* 28:603-608.
- \*Wallace L, Pellizzari E, Hartwell TD, et al. 1987c. Exposures to benzene and other volatile compounds from active and passive smoking. *Arch Environ Health* 42:272-279.
- \*Wallace L, Zweidinger R, Erickson M, et al. 1982. Monitoring individual exposure measurements of volatile organic compounds in breathing-zone air, drinking water, and exhaled breath. *Environ Int* 8:269-282.

## 9. REFERENCES

- \*Wallace LA. 1986. Personal exposures, indoor and outdoor air concentrations, and exhaled breath concentrations of selected volatile organic compounds measured for 600 residents of New Jersey, North Dakota, North Carolina and California. *Toxicol Environ Chem* 12:215-236.
- Wallace LA, Pellizzari ED, Hartwell TD, et al. 1985. Personal exposures, indoor-outdoor relationships, and breath levels of toxic air pollutants measured for 335 persons in New Jersey. *Atmos Environ* 19:1651-1661.
- \*Wallace LA, Pellizzari ED, Hartwell TD, et al. 1987a. The TEAM study: Personal exposures to toxic substances in air, drinking water, and breath of 400 residents of New Jersey, North Carolina, and North Dakota. *Environ Res* 43:290-307.
- \*Wallace LA, Pellizzari ED, Hartwell TD, et al. 1989. The influence of personal activities on exposure to volatile organic compounds 1.2. *Environ Res* 50(1):37-55.
- \*Wallace LA, Pellizzari E, Leaderer B, et al. 1987b. Emissions of volatile organic compounds from building materials and consumer products. *Atmos Environ* 21:385-393.
- Wasik SP, Miller MM, Tewari YB, et al. 1983. Determination of the vapor pressure, aqueous solubility, and octanol/water partition coefficient of hydrophobic substances by coupled generator column/liquid chromatographic methods. *Residue Rev* 85:29-42.
- Weast RC, ed. 1988. *CRC Handbook of chemistry and physics*. 69th ed. Boca Raton, FL: CRC Press, Inc., C-269.
- Welch VA, Fallon KJ, Gelbke H-P. 2005. Ethylbenzene. *Ullmann's encyclopedia of industrial chemistry*. Weinheim: VCH Verlag GmbH & Co.  
[http://www.mrw.interscience.wiley.com/emrw/9783527306732/ueic/article/a10\\_035/current/pdf](http://www.mrw.interscience.wiley.com/emrw/9783527306732/ueic/article/a10_035/current/pdf). March 29, 2007.
- \*West JR, Smith HW, Chasis H. 1948. Glomerular filtration rate, effective renal blood flow, and maximal tubular excretory capacity in infancy. *J Pediat* 32:10-18.
- \*Whitehead LW, Ball GL, Fine LJ, et al. 1984. Solvent vapor exposures in booth spray painting and spray glueing, and associated operations. *Am Ind Hyg Assoc J* 45:767-772.
- WHO. 1996. *Guidelines for drinking-water quality*. Vol. 2. Health criteria and other supporting information. 2nd ed. Geneva: World Health Organization.
- \*WHO. 2000. *Air quality guidelines*. 2nd ed. Geneva, Switzerland: World Health Organization.  
<http://www.euro.who.int/Document/AIQ/AirQualRepMtg.pdf>. March 08, 2006.
- \*WHO. 2004. *Guidelines for drinking-water quality*. Vol. 1. Recommendations. 3rd ed. Geneva, Switzerland: World Health Organization. [http://www.who.int/water\\_sanitation\\_health/dwq/gdwq3/en/](http://www.who.int/water_sanitation_health/dwq/gdwq3/en/). March 08, 2006.
- \*Widdowson EM, Dickerson JWT. 1964. Chemical composition of the body. In: Comar CL, Bronner F, eds. *Mineral metabolism: An advanced treatise*. Volume II: The elements Part A. New York: Academic Press, 1-247.



## 9. REFERENCES

- Wiesmuller GA, Van Thriel C, Steup A, et al. 2002. Nasal function in self-reported chemically intolerant individuals. *Arch Environ Health* 57(3):247-254.
- \*Wilson BH, Smith GB, Rees JF. 1986. Biotransformations of selected alkylbenzenes and halogenated aliphatic hydrocarbons in methanogenic aquifer material: A microcosm study. *Environ Sci Technol* 20:997-1002.
- Witt KL, Knapton A, Wehr CM, et al. 2000. Micronucleated erythrocyte frequency to peripheral blood of B6C3F1 mice from short-term, prechronic, and chronic studies of the NTP carcinogenesis bioassay program. *Environ Mol Mutagen* 36(3):163-194.
- +\*Wolf MA, Rowe VK, McCollister DD, et al. 1956. Toxicological studies of certain alkylated benzenes and benzene: Experiments on laboratory animals. *AMA Arch Ind Health* 14:387-398.
- +\*Wolff MS. 1976. Evidence for existence in human tissues of monomers for plastics and rubber manufacture. *Environ Health Perspect* 17:183-187.
- +\*Wolff MS, Daum SM, Lorimer WV, et al. 1977. Styrene and related hydrocarbons in subcutaneous fat from polymerization workers. *J Toxicol Environ Health* 2:997-1005.
- +Wrbitzky R, Goen T, Letzel S, et al. 1995. Internal exposure of waste incineration workers to organic and inorganic substances. *Int Arch Occup Environ Health* 68(1):13-21.
- \*Yadav JS, Reddy CA. 1993. Degradation of benzene, toluene, ethylbenzene, and xylenes (BTEX) by the lignin-degrading basidiomycete *Phanerochaete chrysosporium*. *Appl Environ Microbiol* 59(3):756-762.
- \*Yalkowsky SH, Valvani SC. 1976. Partition coefficients and surface areas of some alkylbenzenes. *J Med Chem* 19:727-728.
- Yamamoto RK, Cook W A. 1968. Determination of ethyl benzene and styrene in air by ultraviolet spectrophotometry. *Am Ind Hyg Assoc* 238-241.
- +\*Yamasaki Y. 1984. [The determination of urinary metabolites of ethylbenzene by high-performance liquid chromatography]. *Okayama Igakkai Zasshi* 96:531-535. (Japanese)
- \*Yanagihara S, Shimada I, Shinoyama E, et al. 1977. Photochemical reactivities of hydrocarbons. In: Kasuga S, eds. *Proceedings of the 4th International Clean Air Congress*. Tokyo: Japanese Union of Air Pollution Prevention Associations, 472-477.
- +\*Yant WP, Schrenk HH, Waite CP, et al. 1930. Acute response of guinea pigs to vapors of some new commercial organic compounds. II. Ethylbenzene. *Pub Health Rep* 45:1241-1250.
- Yaws CL. 1975. Toluene, ethylbenzene, and cumene. *Chem Eng* 82:73-81.
- Yerushalmi L, Guiot SR. 1998. Kinetics of biodegradation of gasoline and its hydrocarbon constituents. *Appl Microbiol Biotechnol* 49(4):475-481.
- Young P, Parker A. 1984. Vapors, odors, and toxic gases from landfills. *ASTM Spec Tech Publ* 851:24-41.

## 9. REFERENCES

+Yuan W, Cawley GF, Eyer CS, et al. 1994. Induction of P450 3A by ethylbenzene without altering RNA levels. *Biochem Biophys Res Commun* 202(3):1259-1265.

Yuan W, Sequeira DJ, Cawley GF, et al. 1997a. Time course for the modulation of hepatic cytochrome p450 after administration of ethylbenzene and its correlation with toluene metabolism. *Arch Biochem Biophys* 339(1):55-63.

Yuan W, Serron SC, Haddican MM, et al. 1997b. Ethylbenzene modulates the expression of different cytochrome p-450 isozymes by discrete multistep processes. *Biochim Biophys Acta* 1334(2-3):361-72.

+Yuan W, White T B, White J W, et al. 1995. Relationship between hydrocarbon structure and induction of P450: Effect on RNA levels. *Xenobiotica* 25(1):9-16.

\*Zappi ME, Rogers BA, Teeter CL, et al. 1996. Bioslurry treatment of a soil contaminated with low concentration of total petroleum hydrocarbons. *J Hazard Mater* 46:1-12.

Zarth MOF, Smith RG, Schroeder ED, et al. 1984. Removal of toxic organics by overland flow. *Vom Wasser* 63:281-197.

Zhang S, Cowley GF, Eyer CS, et al. 2002. Altered ethylbenzene-mediated hepatic CYP2E1 expression in growth hormone-deficient dwarf rats. *Toxicol Appl Pharmacol* 179(1):74-82.

Zhao J, Ye M, Ou C, et al. 2003. The combined toxicity of several main pollutant compounds in indoor air. *Toxicology* 191(1):23.

\*Ziegler EE, Edwards BB, Jensen RL et al. 1978. Absorption and retention of lead by infants. *Pediatr Res* 12:29-34.

\*Zielinska B, Sagebiel JC, Harshfield G, et al. 1996. Volatile organic compounds up to C20 emitted from motor vehicles; measurement methods. *Atmos Environ* 30(12):2269-2286.

Zoeteman BCJ, Degreef E, Brinkman FJJ. 1981. Persistency of organic contaminants in groundwater, lessons from soil pollution incidents in the Netherlands. *Sci Total Environ* 21:187-202.

\*Zweidinger RB, Sigsby JE, Tejada SB, et al. 1988. Detailed hydrocarbon and aldehyde mobile source emissions from roadway studies. *Environ Sci Technol* 22:956-962.

## 10. GLOSSARY

**Absorption**—The taking up of liquids by solids, or of gases by solids or liquids.

**Acute Exposure**—Exposure to a chemical for a duration of 14 days or less, as specified in the Toxicological Profiles.

**Adsorption**—The adhesion in an extremely thin layer of molecules (as of gases, solutes, or liquids) to the surfaces of solid bodies or liquids with which they are in contact.

**Adsorption Coefficient ( $K_{oc}$ )**—The ratio of the amount of a chemical adsorbed per unit weight of organic carbon in the soil or sediment to the concentration of the chemical in solution at equilibrium.

**Adsorption Ratio ( $K_d$ )**—The amount of a chemical adsorbed by sediment or soil (i.e., the solid phase) divided by the amount of chemical in the solution phase, which is in equilibrium with the solid phase, at a fixed solid/solution ratio. It is generally expressed in micrograms of chemical sorbed per gram of soil or sediment.

**Benchmark Dose (BMD)**—Usually defined as the lower confidence limit on the dose that produces a specified magnitude of changes in a specified adverse response. For example, a  $BMD_{10}$  would be the dose at the 95% lower confidence limit on a 10% response, and the benchmark response (BMR) would be 10%. The BMD is determined by modeling the dose response curve in the region of the dose response relationship where biologically observable data are feasible.

**Benchmark Dose Model**—A statistical dose-response model applied to either experimental toxicological or epidemiological data to calculate a BMD.

**Bioconcentration Factor (BCF)**—The quotient of the concentration of a chemical in aquatic organisms at a specific time or during a discrete time period of exposure divided by the concentration in the surrounding water at the same time or during the same period.

**Biomarkers**—Broadly defined as indicators signaling events in biologic systems or samples. They have been classified as markers of exposure, markers of effect, and markers of susceptibility.

**Cancer Effect Level (CEL)**—The lowest dose of chemical in a study, or group of studies, that produces significant increases in the incidence of cancer (or tumors) between the exposed population and its appropriate control.

**Carcinogen**—A chemical capable of inducing cancer.

**Case-Control Study**—A type of epidemiological study that examines the relationship between a particular outcome (disease or condition) and a variety of potential causative agents (such as toxic chemicals). In a case-controlled study, a group of people with a specified and well-defined outcome is identified and compared to a similar group of people without outcome.

**Case Report**—Describes a single individual with a particular disease or exposure. These may suggest some potential topics for scientific research, but are not actual research studies.

**Case Series**—Describes the experience of a small number of individuals with the same disease or exposure. These may suggest potential topics for scientific research, but are not actual research studies.

## 10. GLOSSARY

**Ceiling Value**—A concentration of a substance that should not be exceeded, even instantaneously.

**Chronic Exposure**—Exposure to a chemical for 365 days or more, as specified in the Toxicological Profiles.

**Cohort Study**—A type of epidemiological study of a specific group or groups of people who have had a common insult (e.g., exposure to an agent suspected of causing disease or a common disease) and are followed forward from exposure to outcome. At least one exposed group is compared to one unexposed group.

**Cross-sectional Study**—A type of epidemiological study of a group or groups of people that examines the relationship between exposure and outcome to a chemical or to chemicals at one point in time.

**Data Needs**—Substance-specific informational needs that if met would reduce the uncertainties of human health assessment.

**Developmental Toxicity**—The occurrence of adverse effects on the developing organism that may result from exposure to a chemical prior to conception (either parent), during prenatal development, or postnatally to the time of sexual maturation. Adverse developmental effects may be detected at any point in the life span of the organism.

**Dose-Response Relationship**—The quantitative relationship between the amount of exposure to a toxicant and the incidence of the adverse effects.

**Embryotoxicity and Fetotoxicity**—Any toxic effect on the conceptus as a result of prenatal exposure to a chemical; the distinguishing feature between the two terms is the stage of development during which the insult occurs. The terms, as used here, include malformations and variations, altered growth, and *in utero* death.

**Environmental Protection Agency (EPA) Health Advisory**—An estimate of acceptable drinking water levels for a chemical substance based on health effects information. A health advisory is not a legally enforceable federal standard, but serves as technical guidance to assist federal, state, and local officials.

**Epidemiology**—Refers to the investigation of factors that determine the frequency and distribution of disease or other health-related conditions within a defined human population during a specified period.

**Genotoxicity**—A specific adverse effect on the genome of living cells that, upon the duplication of affected cells, can be expressed as a mutagenic, clastogenic, or carcinogenic event because of specific alteration of the molecular structure of the genome.

**Half-life**—A measure of rate for the time required to eliminate one half of a quantity of a chemical from the body or environmental media.

**Immediately Dangerous to Life or Health (IDLH)**—The maximum environmental concentration of a contaminant from which one could escape within 30 minutes without any escape-impairing symptoms or irreversible health effects.

**Immunologic Toxicity**—The occurrence of adverse effects on the immune system that may result from exposure to environmental agents such as chemicals.

## 10. GLOSSARY

**Immunological Effects**—Functional changes in the immune response.

**Incidence**—The ratio of individuals in a population who develop a specified condition to the total number of individuals in that population who could have developed that condition in a specified time period.

**Intermediate Exposure**—Exposure to a chemical for a duration of 15–364 days, as specified in the Toxicological Profiles.

**In Vitro**—Isolated from the living organism and artificially maintained, as in a test tube.

**In Vivo**—Occurring within the living organism.

**Lethal Concentration<sub>(LO)</sub> (LC<sub>LO</sub>)**—The lowest concentration of a chemical in air that has been reported to have caused death in humans or animals.

**Lethal Concentration<sub>(50)</sub> (LC<sub>50</sub>)**—A calculated concentration of a chemical in air to which exposure for a specific length of time is expected to cause death in 50% of a defined experimental animal population.

**Lethal Dose<sub>(LO)</sub> (LD<sub>LO</sub>)**—The lowest dose of a chemical introduced by a route other than inhalation that has been reported to have caused death in humans or animals.

**Lethal Dose<sub>(50)</sub> (LD<sub>50</sub>)**—The dose of a chemical that has been calculated to cause death in 50% of a defined experimental animal population.

**Lethal Time<sub>(50)</sub> (LT<sub>50</sub>)**—A calculated period of time within which a specific concentration of a chemical is expected to cause death in 50% of a defined experimental animal population.

**Lowest-Observed-Adverse-Effect Level (LOAEL)**—The lowest exposure level of chemical in a study, or group of studies, that produces statistically or biologically significant increases in frequency or severity of adverse effects between the exposed population and its appropriate control.

**Lymphoreticular Effects**—Represent morphological effects involving lymphatic tissues such as the lymph nodes, spleen, and thymus.

**Malformations**—Permanent structural changes that may adversely affect survival, development, or function.

**Minimal Risk Level (MRL)**—An estimate of daily human exposure to a hazardous substance that is likely to be without an appreciable risk of adverse noncancer health effects over a specified route and duration of exposure.

**Modifying Factor (MF)**—A value (greater than zero) that is applied to the derivation of a Minimal Risk Level (MRL) to reflect additional concerns about the database that are not covered by the uncertainty factors. The default value for a MF is 1.

**Morbidity**—State of being diseased; morbidity rate is the incidence or prevalence of disease in a specific population.

**Mortality**—Death; mortality rate is a measure of the number of deaths in a population during a specified interval of time.

## 10. GLOSSARY

**Mutagen**—A substance that causes mutations. A mutation is a change in the DNA sequence of a cell's DNA. Mutations can lead to birth defects, miscarriages, or cancer.

**Necropsy**—The gross examination of the organs and tissues of a dead body to determine the cause of death or pathological conditions.

**Neurotoxicity**—The occurrence of adverse effects on the nervous system following exposure to a chemical.

**No-Observed-Adverse-Effect Level (NOAEL)**—The dose of a chemical at which there were no statistically or biologically significant increases in frequency or severity of adverse effects seen between the exposed population and its appropriate control. Effects may be produced at this dose, but they are not considered to be adverse.

**Octanol-Water Partition Coefficient ( $K_{ow}$ )**—The equilibrium ratio of the concentrations of a chemical in *n*-octanol and water, in dilute solution.

**Odds Ratio (OR)**—A means of measuring the association between an exposure (such as toxic substances and a disease or condition) that represents the best estimate of relative risk (risk as a ratio of the incidence among subjects exposed to a particular risk factor divided by the incidence among subjects who were not exposed to the risk factor). An OR of greater than 1 is considered to indicate greater risk of disease in the exposed group compared to the unexposed group.

**Organophosphate or Organophosphorus Compound**—A phosphorus-containing organic compound and especially a pesticide that acts by inhibiting cholinesterase.

**Permissible Exposure Limit (PEL)**—An Occupational Safety and Health Administration (OSHA) allowable exposure level in workplace air averaged over an 8-hour shift of a 40-hour workweek.

**Pesticide**—General classification of chemicals specifically developed and produced for use in the control of agricultural and public health pests.

**Pharmacokinetics**—The dynamic behavior of a material in the body, used to predict the fate (disposition) of an exogenous substance in an organism. Utilizing computational techniques, it provides the means of studying the absorption, distribution, metabolism, and excretion of chemicals by the body.

**Pharmacokinetic Model**—A set of equations that can be used to describe the time course of a parent chemical or metabolite in an animal system. There are two types of pharmacokinetic models: data-based and physiologically-based. A data-based model divides the animal system into a series of compartments, which, in general, do not represent real, identifiable anatomic regions of the body, whereas the physiologically-based model compartments represent real anatomic regions of the body.

**Physiologically Based Pharmacodynamic (PBPD) Model**—A type of physiologically based dose-response model that quantitatively describes the relationship between target tissue dose and toxic end points. These models advance the importance of physiologically based models in that they clearly describe the biological effect (response) produced by the system following exposure to an exogenous substance.

## 10. GLOSSARY

**Physiologically Based Pharmacokinetic (PBPK) Model**—Comprised of a series of compartments representing organs or tissue groups with realistic weights and blood flows. These models require a variety of physiological information: tissue volumes, blood flow rates to tissues, cardiac output, alveolar ventilation rates, and possibly membrane permeabilities. The models also utilize biochemical information, such as air/blood partition coefficients, and metabolic parameters. PBPK models are also called biologically based tissue dosimetry models.

**Prevalence**—The number of cases of a disease or condition in a population at one point in time.

**Prospective Study**—A type of cohort study in which the pertinent observations are made on events occurring after the start of the study. A group is followed over time.

**$q_1^*$** —The upper-bound estimate of the low-dose slope of the dose-response curve as determined by the multistage procedure. The  $q_1^*$  can be used to calculate an estimate of carcinogenic potency, the incremental excess cancer risk per unit of exposure (usually  $\mu\text{g/L}$  for water,  $\text{mg/kg/day}$  for food, and  $\mu\text{g/m}^3$  for air).

**Recommended Exposure Limit (REL)**—A National Institute for Occupational Safety and Health (NIOSH) time-weighted average (TWA) concentration for up to a 10-hour workday during a 40-hour workweek.

**Reference Concentration (RfC)**—An estimate (with uncertainty spanning perhaps an order of magnitude) of a continuous inhalation exposure to the human population (including sensitive subgroups) that is likely to be without an appreciable risk of deleterious noncancer health effects during a lifetime. The inhalation reference concentration is for continuous inhalation exposures and is appropriately expressed in units of  $\text{mg/m}^3$  or ppm.

**Reference Dose (RfD)**—An estimate (with uncertainty spanning perhaps an order of magnitude) of the daily exposure of the human population to a potential hazard that is likely to be without risk of deleterious effects during a lifetime. The RfD is operationally derived from the no-observed-adverse-effect level (NOAEL, from animal and human studies) by a consistent application of uncertainty factors that reflect various types of data used to estimate RfDs and an additional modifying factor, which is based on a professional judgment of the entire database on the chemical. The RfDs are not applicable to nonthreshold effects such as cancer.

**Reportable Quantity (RQ)**—The quantity of a hazardous substance that is considered reportable under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA). Reportable quantities are (1) 1 pound or greater or (2) for selected substances, an amount established by regulation either under CERCLA or under Section 311 of the Clean Water Act. Quantities are measured over a 24-hour period.

**Reproductive Toxicity**—The occurrence of adverse effects on the reproductive system that may result from exposure to a chemical. The toxicity may be directed to the reproductive organs and/or the related endocrine system. The manifestation of such toxicity may be noted as alterations in sexual behavior, fertility, pregnancy outcomes, or modifications in other functions that are dependent on the integrity of this system.

**Retrospective Study**—A type of cohort study based on a group of persons known to have been exposed at some time in the past. Data are collected from routinely recorded events, up to the time the study is undertaken. Retrospective studies are limited to causal factors that can be ascertained from existing records and/or examining survivors of the cohort.

## 10. GLOSSARY

**Risk**—The possibility or chance that some adverse effect will result from a given exposure to a chemical.

**Risk Factor**—An aspect of personal behavior or lifestyle, an environmental exposure, or an inborn or inherited characteristic that is associated with an increased occurrence of disease or other health-related event or condition.

**Risk Ratio**—The ratio of the risk among persons with specific risk factors compared to the risk among persons without risk factors. A risk ratio greater than 1 indicates greater risk of disease in the exposed group compared to the unexposed group.

**Short-Term Exposure Limit (STEL)**—The American Conference of Governmental Industrial Hygienists (ACGIH) maximum concentration to which workers can be exposed for up to 15 minutes continually. No more than four excursions are allowed per day, and there must be at least 60 minutes between exposure periods. The daily Threshold Limit Value-Time Weighted Average (TLV-TWA) may not be exceeded.

**Standardized Mortality Ratio (SMR)**—A ratio of the observed number of deaths and the expected number of deaths in a specific standard population.

**Target Organ Toxicity**—This term covers a broad range of adverse effects on target organs or physiological systems (e.g., renal, cardiovascular) extending from those arising through a single limited exposure to those assumed over a lifetime of exposure to a chemical.

**Teratogen**—A chemical that causes structural defects that affect the development of an organism.

**Threshold Limit Value (TLV)**—An American Conference of Governmental Industrial Hygienists (ACGIH) concentration of a substance to which most workers can be exposed without adverse effect. The TLV may be expressed as a Time Weighted Average (TWA), as a Short-Term Exposure Limit (STEL), or as a ceiling limit (CL).

**Time-Weighted Average (TWA)**—An allowable exposure concentration averaged over a normal 8-hour workday or 40-hour workweek.

**Toxic Dose<sub>(50)</sub> (TD<sub>50</sub>)**—A calculated dose of a chemical, introduced by a route other than inhalation, which is expected to cause a specific toxic effect in 50% of a defined experimental animal population.

**Toxicokinetic**—The absorption, distribution, and elimination of toxic compounds in the living organism.

**Uncertainty Factor (UF)**—A factor used in operationally deriving the Minimal Risk Level (MRL) or Reference Dose (RfD) or Reference Concentration (RfC) from experimental data. UFs are intended to account for (1) the variation in sensitivity among the members of the human population, (2) the uncertainty in extrapolating animal data to the case of human, (3) the uncertainty in extrapolating from data obtained in a study that is of less than lifetime exposure, and (4) the uncertainty in using lowest-observed-adverse-effect level (LOAEL) data rather than no-observed-adverse-effect level (NOAEL) data. A default for each individual UF is 10; if complete certainty in data exists, a value of 1 can be used; however, a reduced UF of 3 may be used on a case-by-case basis, 3 being the approximate logarithmic average of 10 and 1.

**Xenobiotic**—Any chemical that is foreign to the biological system.



## APPENDIX A. ATSDR MINIMAL RISK LEVELS AND WORKSHEETS

The Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) [42 U.S.C. 9601 et seq.], as amended by the Superfund Amendments and Reauthorization Act (SARA) [Pub. L. 99–499], requires that the Agency for Toxic Substances and Disease Registry (ATSDR) develop jointly with the U.S. Environmental Protection Agency (EPA), in order of priority, a list of hazardous substances most commonly found at facilities on the CERCLA National Priorities List (NPL); prepare toxicological profiles for each substance included on the priority list of hazardous substances; and assure the initiation of a research program to fill identified data needs associated with the substances.

The toxicological profiles include an examination, summary, and interpretation of available toxicological information and epidemiologic evaluations of a hazardous substance. During the development of toxicological profiles, Minimal Risk Levels (MRLs) are derived when reliable and sufficient data exist to identify the target organ(s) of effect or the most sensitive health effect(s) for a specific duration for a given route of exposure. An MRL is an estimate of the daily human exposure to a hazardous substance that is likely to be without appreciable risk of adverse noncancer health effects over a specified duration of exposure. MRLs are based on noncancer health effects only and are not based on a consideration of cancer effects. These substance-specific estimates, which are intended to serve as screening levels, are used by ATSDR health assessors to identify contaminants and potential health effects that may be of concern at hazardous waste sites. It is important to note that MRLs are not intended to define clean-up or action levels.

MRLs are derived for hazardous substances using the no-observed-adverse-effect level/uncertainty factor approach. They are below levels that might cause adverse health effects in the people most sensitive to such chemical-induced effects. MRLs are derived for acute (1–14 days), intermediate (15–364 days), and chronic (365 days and longer) durations and for the oral and inhalation routes of exposure. Currently, MRLs for the dermal route of exposure are not derived because ATSDR has not yet identified a method suitable for this route of exposure. MRLs are generally based on the most sensitive chemical-induced end point considered to be of relevance to humans. Serious health effects (such as irreparable damage to the liver or kidneys, or birth defects) are not used as a basis for establishing MRLs. Exposure to a level above the MRL does not mean that adverse health effects will occur.

MRLs are intended only to serve as a screening tool to help public health professionals decide where to look more closely. They may also be viewed as a mechanism to identify those hazardous waste sites that

## APPENDIX A

are not expected to cause adverse health effects. Most MRLs contain a degree of uncertainty because of the lack of precise toxicological information on the people who might be most sensitive (e.g., infants, elderly, nutritionally or immunologically compromised) to the effects of hazardous substances. ATSDR uses a conservative (i.e., protective) approach to address this uncertainty consistent with the public health principle of prevention. Although human data are preferred, MRLs often must be based on animal studies because relevant human studies are lacking. In the absence of evidence to the contrary, ATSDR assumes that humans are more sensitive to the effects of hazardous substance than animals and that certain persons may be particularly sensitive. Thus, the resulting MRL may be as much as 100-fold below levels that have been shown to be nontoxic in laboratory animals.

Proposed MRLs undergo a rigorous review process: Health Effects/MRL Workgroup reviews within the Division of Toxicology and Environmental Medicine, expert panel peer reviews, and agency-wide MRL Workgroup reviews, with participation from other federal agencies and comments from the public. They are subject to change as new information becomes available concomitant with updating the toxicological profiles. Thus, MRLs in the most recent toxicological profiles supersede previously published levels. For additional information regarding MRLs, please contact the Division of Toxicology and Environmental Medicine, Agency for Toxic Substances and Disease Registry, 1600 Clifton Road NE, Mailstop F-32, Atlanta, Georgia 30333.

## APPENDIX A

**MINIMAL RISK LEVEL (MRL) WORKSHEET**

Chemical Name: Ethylbenzene  
CAS Numbers: 100-41-4  
Date: August 2007  
Profile Status: Final Pre-Public Draft  
Route:  Inhalation  Oral  
Duration:  Acute  Intermediate  Chronic  
Graph Key: 13  
Species: Rat

Minimal Risk Level: 10  mg/kg/day  ppm

Reference: Cappaert NLM, Klis SFL, Baretta AB, et al. 2000. Ethyl benzene-induced ototoxicity in rats: A dose-dependent mid-frequency hearing loss. *J Assoc Res Otolaryngol* 1(4):292-299.

Experimental design: Wag/Rij rats (eight rats/group; sex not provided) were exposed to 0, 300, 400, or 550 ppm ethylbenzene (99% pure), 8 hours/day for 5 days. Animal weight was recorded weekly. Measurement of Distortion Product Otoacoustic Emissions (DPOAE), Compound Action Potential (CAP), and hair cell counts were conducted 3–6 weeks after the last ethylbenzene exposure.

*DPOAE:* Stimuli were delivered to the ear canal via a probe system incorporating two speakers and a low-noise microphone. The microphone signal was amplified and the response to the stimulus was measured. DPOAE amplitude growth curves with stimulus levels were obtained from both ears. Growth functions were obtained at 4, 5.6, 8, 11.3, 16, and 22.6 kHz. The DPOAE threshold, defined as the stimulus level required to elicit a response of 0 dB SPL DPOAE was determined for each of the six frequencies.

*CAP:* CAP was conducted immediately after DPOAE measurements. Auditory-evoked responses were recorded via a silverball electrode at the apex of the cochlea after presenting tone bursts of 1, 2, 4, 8, 12, 16, and 24 kHz. An isoresponsive criterion of 1  $\mu$ V level was used to define CAP thresholds. CAP amplitude was defined as the difference between the first negative peak and the summing potential in the electrophysiologic response. Hair cell counts: Immediately after conducting the electrocochleography (CAP) cochleas were removed and bisected longitudinally. Hair cell counts were conducted on five locations of the organ of Corti. Outer hair cell (OHC) loss was determined and expresses as a percentage of the expected number of OHC in different auditory regions.

Effect noted in study and corresponding doses: Rats did not show signs of ill health. There were no significant differences in terminal body weight between exposed and control rats.

*DPOAE:* DPOAE amplitude growth curves showed a significant reduction in rats exposed to 550 ppm, but not 300 or 400 ppm ethylbenzene. Effects were significant at 5.6, 8, and 11.3 kHz, but not at other frequencies. The DPOAE thresholds were significantly shifted (increased stimulus was needed to elicit the threshold response) at 5.6, 8, 11.3, and 16 kHz in rats in the 550-ppm group. DPOAE threshold shifts were not observed in other exposure groups.

*CAP:* Animals exposed to 550 ppm showed a significant shift in the CAP amplitude growth curves at 8, 12, and 16 kHz. In the 400-ppm group, the growth curves were affected only at 12 kHz and there was no effect in animals in the 300-ppm group. CAP thresholds were significantly shifted at 8, 12, and 16 kHz in the 550-ppm group and at 12 and 16 kHz in the 400-ppm group. There was no deterioration of CAP thresholds in the 300-ppm group. Significant OHC losses of approximately 33 and 75% were observed in the 550-ppm group in the auditory regions corresponding to 11 and 21 kHz, respectively. In the 400-ppm group, significant losses (25%) were observed in the 11 kHz region. OHC losses in the 21 kHz region in the 300-ppm group were approximately 12%, but were not statistically significant.

## APPENDIX A

Dose and end point used for MRL derivation: The MRL is based on a NOAEL of 300 ppm and a LOAEL of 400 ppm for significant deterioration in CAP auditory thresholds and significant OHC losses.

[x] NOAEL [ ] LOAEL

Uncertainty Factors used in MRL derivation:

- [ ] 10 for use of a LOAEL
- [x] 3 for extrapolation from animals to humans with dosimetric adjustment
- [x] 10 for human variability

Was a conversion factor used from ppm in food or water to a mg/body weight dose? Not applicable

If an inhalation study in animals, list conversion factors used in determining human equivalent dose: The human equivalent concentration (HEC) for the NOAEL was calculated using Formula 4-48 (page 4-60), from Methods for Derivation of Inhalation Reference Concentrations and Application of Inhalation Dosimetry (EPA 1994o). The recommended equation is that for category 3 gases:

$$\begin{aligned} \text{NOAEL}_{[\text{HEC}]} (\text{ppm}) &= \text{NOAEL}_{[\text{ADJ}]} (\text{ppm}) \times \frac{(H_{b/g})_A}{(H_{b/g})_H} \\ &= 300 \text{ ppm} \times [1] = 300 \text{ ppm} \end{aligned}$$

where:

$(H_{b/g})_A, (H_{b/g})_H$  = Blood/gas partition coefficient in animal and human blood, respectively. Blood/gas partition coefficients of 30.2 and 28.2 for rat and human blood, respectively, were obtained (Abraham et al. 2005). However, when  $(H_{b/g})_A > (H_{b/g})_H$ , a value of 1 is used for the ratio (EPA 1994o). Thus, a default value of 1.0 was used for the animal-to-human blood gas ratio.

Was a conversion used from intermittent to continuous exposure? No adjustment for intermittent exposure was made because the pharmacokinetics of ethylbenzene indicate that ethylbenzene will rapidly be absorbed, attain equilibrium with blood, be metabolized, and be eliminated from the body. Steady-state blood ethylbenzene concentrations achieved within 2 hours of initiating inhalation exposure to ethylbenzene concentration ranging from 75 to 500 ppm (Charest-Tardif et al. 2006). The blood elimination kinetics of inhaled ethylbenzene show that ethylbenzene is rapidly eliminated from the blood, with elimination half-times ranging from 3.3 to 63 minutes (e.g., nonlinearity of clearance with exposure concentration, similar elimination half-times (Charest-Tardif et al. 2006; Tardif et al. 1997).

Other additional studies or pertinent information that lend support to this MRL: Cappaert et al. (1999, 2001, 2002) showed significant adverse effects in the auditory system of rats after acute-duration exposures to  $\geq 400$  ppm ethylbenzene via inhalation. OHC losses, generally the most sensitive end point evaluated in these studies, showed a concentration-related pattern. Functional auditory deficits were observed at exposure concentrations that were greater than or equal to the concentrations that elicited OHC loss. Rats administered ethylbenzene by gavage at 8.47 mmol/kg/day (900 mg/kg/day), 5 days/week for 2 weeks showed almost complete loss of the three rows of OHCs (Gagnaire and Langlais 2005). An intermediate-duration study in rats showed significant irreversible ototoxicity in rats exposed to  $\geq 200$  ppm ethylbenzene via inhalation.

Agency Contacts (Chemical Managers): Jessilyn Taylor, Henry Abadin, Heraline Hicks

## APPENDIX A

**MINIMAL RISK LEVEL (MRL) WORKSHEET**

Chemical Name: Ethylbenzene  
CAS Numbers: 100-41-4  
Date: August 2007  
Profile Status: Final Pre-Public Draft  
Route:  Inhalation  Oral  
Duration:  Acute  Intermediate  Chronic  
Graph Key: 40  
Species: Rat

Minimal Risk Level: 0.7  mg/kg/day  ppm

Reference: Gagnaire F, Langlais C, Grossman S, et al. 2007. Ototoxicity in rats exposed to ethylbenzene and to two xylene vapors for 13 weeks. Arch Toxicol 81:127-143.

Experimental design: Male Sprague-Dawley rats (14 rats/exposure group) were exposed to 0, 200, 400, 600 and 800 ppm ethylbenzene (99% pure), 6 hours/day, 6 days/week, for 13 weeks. Ototoxicity was assessed based on effects on neurophysiological measurements and cochlear total hair cell counts. For the neurophysiologic assessments, rats were surgically fitted with electrodes (active electrode was placed at the lambda point over the inferior colliculus, the reference electrode was placed posterior to the bregma and to the right of the midline, and the ground electrode was placed over the nasal bone). Exposure to ethylbenzene was conducted starting 3–4 weeks after implantation of the electrodes and neurophysiological measurements were conducted at the end of 4<sup>th</sup>, 8<sup>th</sup>, and 13<sup>th</sup> week of exposure and at the end of the 8<sup>th</sup> week of recovery (week 21). Brainstem auditory responses were evoked with 50 microsecond clicks at 10 clicks/second presented in 5 dB steps. The evoked activity was analyzed for 10 ms following each click. Audiometric thresholds were determined at 2, 4, 8, and 16 kHz by inspection of the auditory brainstem responses. Following the 8<sup>th</sup> week of recovery (post-exposure) eight rats/group were sacrificed. The organ of Corti and the basilar membrane were dissected from the cochlea and prepared for total hair cell counts (cytococholeograms). Four left and four right cochleas were prepared in this manner in all groups including controls.

Effect noted in study and corresponding doses: In the 800 ppm group, one rat lost its head plug and could not undergo neurophysiological testing, one rat died for unknown reasons and another rat was sacrificed due to a large neck tumor. There were no significant differences in body weight gain between the surviving treated animals and controls.

Audiometric thresholds at 2, 4, 8, and 16 kHz were significantly higher in animals exposed to 400, 600, and 800 ppm ethylbenzene than in controls ( $p < 0.05$ ). The effect was evident at week 4, did not increase significantly throughout the exposure period, and was not reversed after 8 weeks of recovery. No shift in audiometric thresholds was observed in rats in the 200 ppm group.

The morphological assessment of the organ of Corti (conducted after an 8-week recovery period) showed significant losses (up to 30% of the OHC in the mid frequency region) in the third row of the OHC in 4/8 rats exposed to 200 ppm. A dose related loss in third row OHC (OHC3) was evident with almost complete loss observed in the 600- and 800-ppm groups. The data suggest that the extent of the damage at each dose was greatest in the OHC3 followed, in decreasing order, by damage in OHC2, OHC1, and inner hair cells (IHC). There was no significant hair loss in the control animals. The LOAEL for OHC3 loss was 200 ppm. A NOAEL was not established.

## APPENDIX A

Dose and end point used for MRL derivation: The MRL is based on a LOAEL of 200 ppm for significant loss of cochlear OHCs after 13 weeks of exposure.

[ ] NOAEL [x] LOAEL

Uncertainty Factors used in MRL derivation:

- [x] 10 for use of a LOAEL
- [x] 3 for extrapolation from animals to humans with dosimetric adjustment
- [x] 10 for human variability

Was a conversion factor used from ppm in food or water to a mg/body weight dose? Not applicable

If an inhalation study in animals, list conversion factors used in determining human equivalent concentration: The human equivalent concentration (HEC) for the LOAEL was calculated using Formula 4-48 (page 4-60), from Methods for Derivation of Inhalation Reference Concentrations and Application of Inhalation Dosimetry (EPA 1994o). The recommended equation is that for category 3 gases:

$$\begin{aligned} \text{LOAEL}_{[\text{HEC}]} (\text{ppm}) &= \text{LOAEL}_{[\text{ADJ}]} (\text{ppm}) \times \frac{(H_{b/g})_A}{(H_{b/g})_H} \\ &= 200 \text{ ppm} \times [1] = 200 \text{ ppm} \end{aligned}$$

where:

$(H_{b/g})_A$ ,  $(H_{b/g})_H$  = Blood/gas partition coefficient in animal and human blood, respectively. Blood/gas partition coefficients of 30.2 and 28.2 for rat and human blood, respectively, were obtained (Abraham et al. 2005). However, when  $(H_{b/g})_A > (H_{b/g})_H$ , a value of 1 is used for the ratio (EPA 1994o). Thus, a default value of 1.0 was used for the animal-to-human blood gas ratio.

Was a conversion used from intermittent to continuous exposure? No adjustment for intermittent exposure was made because the pharmacokinetics of ethylbenzene indicate that ethylbenzene will rapidly be absorbed, attain equilibrium with blood, be metabolized, and be eliminated from the body. Steady-state blood ethylbenzene concentrations achieved within 2 hours of initiating inhalation exposure to ethylbenzene concentration ranging from 75 to 500 ppm (Charest-Tardif et al. 2006). The blood elimination kinetics of inhaled ethylbenzene show that ethylbenzene is rapidly eliminated from the blood, with elimination half-times ranging from 3.3 to 63 minutes (e.g., nonlinearity of clearance with exposure concentration, similar elimination half-times (Charest-Tardif et al. 2006; Tardif et al. 1997).

Other additional studies or pertinent information that lend support to this MRL: Significant adverse effects on the auditory system was observed in rats after acute-duration exposures to  $\geq 400$  ppm ethylbenzene via inhalation (Cappaert et al. 1999, 2000, 2001, 2002). OHC losses, usually the most sensitive end point evaluated in these acute-duration studies, showed a concentration-related pattern. Functional auditory deficits were observed at exposure concentrations that were greater than or equal to the concentrations that elicited OHC loss. Rats administered ethylbenzene by gavage at 8.47 mmol/kg/day (900 mg/kg/day), 5 days/week for 2 weeks showed almost complete loss of the three rows of OHCs (Gagnaire and Langlais 2005).

Agency Contacts (Chemical Managers): Jessilynn Taylor, Henry Abadin, Heraline Hicks

## APPENDIX A

**MINIMAL RISK LEVEL (MRL) WORKSHEET**

Chemical Name: Ethylbenzene  
CAS Numbers: 100-41-4  
Date: August 2007  
Profile Status: Final Pre-Public Draft  
Route:  Inhalation  Oral  
Duration:  Acute  Intermediate  Chronic  
Graph Key: 60  
Species: Rat

Minimal Risk Level: 0.3  mg/kg/day  ppm

Reference: NTP. 1999. NTP technical report on the toxicology and carcinogenesis studies of ethylbenzene in F344/N rats and B6C3F1 mice (inhalation studies). Research Triangle Park, NC: National Toxicology Program, U.S. Department of Health and Human Services. NTP TR 466.

Experimental design: Groups of F344/N rats and B6C3F1 mice (50 animals/sex/dose group) were exposed to 0, 75, 250, or 750 ppm ethylbenzene by inhalation for 5 days/week, 6 hours/day, for 104 (rats) or 103 (mice) weeks. Animals were observed twice daily and clinical findings were recorded monthly. Body weights were recorded at the initiation of the study, weekly for the first 13 weeks, at week 16, monthly through the end of exposure, and prior to terminal necropsy. Animals that survived to study termination were killed by asphyxiation with CO<sub>2</sub>. A complete necropsy and microscopic examination were performed on all rats and mice that survived to study termination or died early. The tissues examined included the adrenal gland, blood vessel (aorta), bone and marrow, brain, clitoral gland, esophagus, gall bladder, harderian gland, heart, large intestine (cecum, colon, and rectum), small intestine (duodenum, jejunum, ileum), kidney, liver, lung, lymph nodes (mandibular and mesenteric), mammary gland, nose, ovary, pancreas, parathyroid gland, preputial gland, prostate gland, salivary gland, spleen, stomach (forestomach and glandular stomach), testis with epididymis and seminal vesicle, thymus, thyroid gland, trachea, urinary bladder, and uterus.

Effect noted in study and corresponding doses: Survival of male rats in the 750-ppm group was significantly less than that of control animals. Survival was not affected in rats in other exposure groups or in mice at any ethylbenzene concentration. No clinical findings were attributed to ethylbenzene exposure in rats or mice. The severity of nephropathy observed in exposed rats was significantly increased in females at  $\geq 75$  ppm and in males at 750 ppm. Nephropathy was characterized by dilation of renal tubules with hyaline or cellular casts, interstitial fibrosis, infiltration of inflammatory cells, tubular regeneration, and transitional hyperplasia of the renal papilla. In male rats exposed to 750 ppm, the incidences of renal tubule proliferative lesions were significantly increased relative to control animals. The incidences of renal tubule adenoma and adenoma or carcinoma (combined) in the 750-ppm group were significantly greater than the incidence in control animals. The incidence of renal tubule hyperplasia in 750-ppm males was significantly greater than that in the control group. Significant increases were observed in the incidence of interstitial cell adenoma and bilateral testicular adenoma in males in the 750-ppm group. An increase was observed in the incidence of cystic degeneration of the liver in male rats at 750 ppm. Significant increases in the incidence of hyperplasia of the pituitary gland pars distalis were observed in female mice at  $\geq 250$  ppm. A significant increase in the incidence of alveolar epithelial metaplasia was observed in male mice in the 750-ppm group. In 750-ppm males, the incidences of alveolar/bronchiolar adenoma and alveolar/bronchiolar adenoma or carcinoma (combined) were significantly greater than those in control animals but remained within the historical control ranges. The incidence of hepatocellular adenoma and adenoma or carcinoma (combined) in female mice was

## APPENDIX A

significantly increased in the 750-ppm group. Eosinophilic foci of the liver were observed in females in the 750-ppm group at a higher incidence than in control animals. Syncytial alterations of hepatocytes were observed in male mice in all ethylbenzene exposure groups, but not in controls, with a significant increase in incidence observed at  $\geq 250$  ppm. Other nonneoplastic changes in male mice exposed to 750 ppm included mild-to-minimal hepatocellular hypertrophy and hepatocyte necrosis. A significant increase in incidences of follicular cell hyperplasia was observed in male and female mice in the 750-ppm groups.

A NOAEL was not established.

Dose and end point used for MRL derivation: The MRL is based on a LOAEL of 75 ppm for significant increases in the severity of nephropathy in female rats after 2 years of exposure.

[ ] NOAEL [x] LOAEL

Uncertainty Factors used in MRL derivation:

[x] 10 for use of a LOAEL

[x] 3 for extrapolation from animals to humans with dosimetric adjustment

[x] 10 for human variability

Was a conversion factor used from ppm in food or water to a mg/body weight dose? Not applicable

If an inhalation study in animals, list conversion factors used in determining human equivalent concentration: The human equivalent concentration (HEC) for the LOAEL was calculated using Formula 4-48 (page 4-60), from Methods for Derivation of Inhalation Reference Concentrations and Application of Inhalation Dosimetry (EPA 1994o). The recommended equation is that for category 3 gases:

$$\begin{aligned} \text{LOAEL}_{[\text{HEC}]} (\text{ppm}) &= \text{LOAEL}_{[\text{ADJ}]} (\text{ppm}) \times \frac{(H_{b/g})_A}{(H_{b/g})_H} \\ &= 75 \text{ ppm} \times [1] = 75 \text{ ppm} \end{aligned}$$

where:

$(H_{b/g})_A$ ,  $(H_{b/g})_H$  = Blood/gas partition coefficient in animal and human blood, respectively. Blood/gas partition coefficients of 30.2 and 28.2 for rat and human blood, respectively, were obtained (Abraham et al. 2005). However, when  $(H_{b/g})_A > (H_{b/g})_H$ , a value of 1 is used for the ratio (EPA 1994o). Thus, a default value of 1.0 was used for the animal-to-human blood gas ratio.

Was a conversion used from intermittent to continuous exposure? No adjustment for intermittent exposure was made because the pharmacokinetics of ethylbenzene indicate that ethylbenzene will rapidly be absorbed, attain equilibrium with blood, be metabolized, and eliminated from the body. Steady-state blood ethylbenzene concentrations achieved within 2 hours of initiating inhalation exposure to ethylbenzene concentration ranging from 75 to 500 ppm (Charest-Tardif et al. 2006). The blood elimination kinetics of inhaled ethylbenzene show that ethylbenzene is rapidly eliminated from the blood, with elimination half-times ranging from 3.3 to 63 minutes (e.g., nonlinearity of clearance with exposure concentration, similar elimination half-times (Charest-Tardif et al. 2006; Tardif et al. 1997).

Other additional studies or pertinent information that lend support to this MRL: A limited number of studies have examined the chronic toxicity of ethylbenzene. Two studies have looked at possible effects in workers chronically exposed to ethylbenzene and NTP (1999) examined chronic toxicity in rats and



## APPENDIX A

mice. Hematological effects (increased average number of lymphocytes and decreased hemoglobin) were observed in workers exposed to solvents containing ethylbenzene (Angerer and Wulf 1985). No hematological effects, liver lesions or effects on liver function were reported in a study of workers exposed chronically (>20 years) to ethylbenzene (Bardodej and Cirek 1988). Exposure levels were not indicated in the latter study, but the risk of ethylbenzene exposure in this production plant was reported as negligible. An increased incidence of hyperplasia of the pituitary gland pars distalis was observed in female mice exposed to 250 ppm (NTP 1999). At 750 ppm, increased incidence of follicular cell hyperplasia in the thyroid gland and syncytial alterations of the hepatocytes, hypertrophy, and hepatic necrosis were observed in mice (NTP 1999).

Agency Contacts (Chemical Managers): Jessilynn Taylor, Henry Abadin, Heraline Hicks

## APPENDIX A

**MINIMAL RISK LEVEL (MRL) WORKSHEET**

Chemical Name: Ethylbenzene  
CAS Numbers: 100-41-4  
Date: August 2007  
Profile Status: Final Pre-Public Draft  
Route:  Inhalation  Oral  
Duration:  Acute  Intermediate  Chronic  
Graph Key: 4  
Species: Rat

Minimal Risk Level: 0.5  mg/kg/day  ppm

Reference: Mellert W, Deckardt K, Kauffmann W, et al. 2007. Ethylbenzene: 4- and 13-week rat oral toxicity. Arch Toxicol 81:361-370.

Experimental design: Groups of 10 male and 10 female Wistar rats were administered ethylbenzene (no vehicle) by oral gavage at doses of 0, 75, 250, or 750 mg/kg/day for 13 weeks. The total daily dose of ethylbenzene was administered as split morning/evening half doses. Animals were examined daily for mortality and clinical signs. Food and water consumption and body weights were recorded weekly. A detailed clinical examination [ophthalmology and a functional observational battery (FOB)] and assessment of motor activity were conducted during the last week of treatment. After 13 weeks, urinalysis was conducted and blood samples were obtained and analyzed for hematology and clinical chemistry; organ weights were recorded and gross histopathologic examinations of the liver, kidney, and pancreas were conducted on animals in all groups. A comprehensive histopathological examination of tissues was performed in the control and 750 mg/kg/day groups.

Effect noted in study and corresponding doses: Clinical signs (post-dosing salivation) in treated animals were observed in all animals administered  $\geq 250$  mg/kg/day and in one animal administered 75 mg/kg/day. Terminal body weight in males was significantly decreased by 14% compared to controls in the 750 mg/kg/day group. Mean corpuscular volume was increased in males and females and platelet count was reduced in females treated with 750 mg/kg/day. Effects indicative of liver toxicity included increased activity of serum liver enzymes (ALT and GGT) in males ( $\geq 250$  mg/kg/day) and females (750 mg/kg/day), increased absolute and relative liver weights ( $\geq 250$  mg/kg/day in males and females), and a dose-related increase in the incidence of centrilobular hepatocyte hypertrophy ( $\geq 250$  mg/kg/day in males and females). Increased bilirubin ( $\leq 250$  mg/kg/day in males and 750 mg/kg/day in females), total protein (750 mg/kg/day in females), albumin (750 mg/kg/day in males and females), globulins (750 mg/kg/day in females), and cholesterol ( $\leq 250$  mg/kg/day in males and females), and decreased prothrombin time (750 mg/kg/day in males and  $\geq 250$  mg/kg/day in females) were considered by study investigators as adaptive effects in the liver. In males in the 75 mg/kg/day group, relative liver weight was significantly increased by (4% compared to controls); however, no histopathological changes or increases in absolute liver or serum liver enzyme activities were observed at this dosage. Given that ethylbenzene is a microsomal enzyme inducer and the absence of histopathology and other evidence of liver injury at the 75 mg/kg/day dosage, the small increase in relative liver weight in male rats at this dosage was not considered indicative of an adverse effect on the liver.

Renal effects in males included increased serum creatinine (750 mg/kg/day), increased incidences of transitional epithelial cells and granular and epithelial cell casts in the urine ( $\geq 250$  mg/kg/day), increased absolute and relative kidney weights ( $\geq 250$  mg/kg/day), and a dose-related increase in severity of hyaline droplet nephropathy ( $\geq 250$  mg/kg/day). Adverse renal effects in males were most likely related to accumulation of  $\alpha_2\mu$ -globulin, and, therefore, considered not relevant to humans. Absolute kidney

## APPENDIX A

weight was significantly increased by 7 and 13% in females administered 250 and 750 mg/kg/day, respectively, compared to controls; however, since no histopathological findings or alterations in urinalysis parameters were observed, the increased kidney weight in females was not considered indicative of an adverse kidney effect in female rats. Absolute and relative thymus weights were decreased in females treated with  $\geq 250$  mg/kg/day, but no histopathological findings were observed. Results of the FOB did not reveal consistent treatment-related effects.

Dose and end point used for MRL derivation: Based on evidence of hepatotoxicity (increased serum liver enzyme activity, absolute and relative liver weights, and dose-related increased incidence of centrilobular hepatocyte hypertrophy), and the lack of evidence for adverse effects in other tissues or organ systems at lower oral intermediate-duration dosages, liver effects were selected as the basis for deriving the intermediate oral MRL, with NOAEL and LOAEL values of 75 and 250 mg/kg/day, respectively. Since serum liver enzyme activities were increased in the mid- and high-dose groups in males, but only in the high-dose group in females, males appeared more sensitive than females to the adverse hepatic effects of oral ethylbenzene. To determine the point of departure for derivation of the intermediate-duration MRL, data sets for serum liver enzymes (ALT and GGT), relative liver weight, and centrilobular hepatocyte hypertrophy in male rats were evaluated for suitability for benchmark dose (BMD) modeling. Using all available continuous variable models in the EPA Benchmark Dose Software (BMDS) version 1.3.2 (EPA 2000), no models provided adequate fit to the data for serum liver enzymes and relative liver weights; therefore, these data sets were considered unsuitable for BMD analysis. Data for the incidence of centrilobular hepatocyte hypertrophy (Table A-1) were analyzed using all available dichotomous models in the EPA Benchmark Dose Software (version 1.3.2). Predicted doses associated with a 10% extra risk were calculated. As assessed by the chi-square goodness-of-fit statistic, all available dichotomous models provided adequate fit ( $X^2 p > 0.1$ ) (Table A-2). Comparing across models, a better fit is generally indicated by a lower Akaike's Information Criteria (AIC). As assessed by AIC, the log-probit model (Figure A-1) provided the best fit to the data. The  $BMD_{10}$  and  $BMDL_{10}$  predicted by the log-probit model for the data on centrilobular hepatocyte hypertrophy in male rats were 78.9 and 48.2 mg/kg/day, respectively. The  $BMDL_{10}$  of 48.2 mg/kg/day for male rats was selected as the point of departure for deriving the intermediate-duration oral MRL.

NOAEL  LOAEL  BMDL

**Table A-1. Incidence Data for Centrilobular Hepatocyte Hypertrophy in Male Rats Exposed to Ethylbenzene for 13 Weeks**

Dose group (mg/kg/day)	Incidence
0	1/10
75	1/10
250	6/10
750	8/10

Source: Mellert et al. 2007

## APPENDIX A

**Table A-2. Modeling Predictions for the Incidence of Centrilobular Hepatocyte Hypertrophy in Male Rats Exposed to Oral Ethylbenzene by Gavage for 13 Weeks**

Model	BMD <sub>10</sub> (mg/kg/day)	BMDL <sub>10</sub> (mg /kg/day)	$\chi^2$ p-value	AIC
Gamma <sup>a</sup>	61.5899	29.1257	1.60	44.152
Logistic	114.336	73.5251	3.46	43.9535
Log-logistic <sup>b</sup>	73.0775	18.2396	1.04	43.5549
Multi-stage <sup>c</sup>	46.8785	28.9177	1.62	42.2384
Probit	112.022	76.3196	3.44	43.9119
<b>Log-probit<sup>b</sup></b>	<b>78.9472</b>	<b>48.2564</b>	<b>0.98</b>	<b>41.482</b>
Quantal linear	46.8785	28.9177	1.62	42.2384
Quantal quadratic	173.773	126.831	4.80	44.9624
Weibull <sup>a</sup>	54.5432	28.9959	1.62	44.2057


<sup>a</sup>Restrict power  $\geq 1$ .

<sup>b</sup>Slope restricted to  $>1$ .

<sup>c</sup>Restrict betas  $\geq 0$ ; lowest degree polynomial with an adequate fit is reported; degree of polynomial=3.

Source: Mellert et al. 2007

**Figure A-1. Predicted (Log-Probit Model) and Observed Incidence of Centrilobular Hepatocyte Hypertrophy in Male Rats Exposed to Oral Ethylbenzene by Gavage for 13 Weeks\***



\*BMDs and BMDLs indicated are associated with a 10% extra risk change from the control, and are in units of mg/kg/day.

## APPENDIX A

Uncertainty Factors used in MRL derivation:

- 10 for use of a less serious LOAEL
- 10 for extrapolation from animals to humans
- 10 for human variability

Was a conversion factor used from ppm in food or water to a mg/body weight dose? Not applicable.

If an inhalation study in animals, list conversion factors used in determining human equivalent dose: Not applicable.

Was a conversion used from intermittent to continuous exposure? Not applicable.

Other additional studies or pertinent information that lend support to this MRL: The selection of BMDL<sub>10</sub> of 48.2 mg/kg/day, derived for male rats exposed to ethylbenzene for 13 weeks (Mellert et al. 2007), as a point of departure for deriving an intermediate-duration oral MRL for ethylbenzene is supported by results a 4-week oral gavage study in rats (Mellert et al. 2007) and a 6-month oral study in rats (Wolf et al. 1956). Results of the 4-week gavage study in rats were similar to those of the 13-week study, identifying NOAEL and LOAEL values of 250 and 750 mg/kg/day, respectively, for liver effects. Observed effects consistent with hepatotoxicity included increased absolute and relative liver weights ( $\geq 250$  mg/kg/day in males and 750 mg/kg/day in females), increased incidence of hepatocyte centrilobular ( $\geq 250$  mg/kg/day in males and 750 mg/kg/day in females), and increased serum liver enzyme activity (ALT) (750 mg/kg/day in males and females). Histopathological changes characterized by cloudy swelling of parenchymal cells of the liver and an increase in liver weight were observed in female rats administered 408 mg/kg/day by gavage for 6 months (Wolf et al. 1956). No other hepatic changes were reported. No liver effects were observed in female rats administered 136 mg/kg/day (Wolf et al. 1956). However, this study was poorly reported and did not provide adequate descriptions of study methods or results.

Agency Contacts (Chemical Managers): Jessilyn Taylor, Henry Abadin, Heraline Hicks

APPENDIX A

This page is intentionally blank.

## APPENDIX B. USER'S GUIDE

### Chapter 1

#### Public Health Statement

This chapter of the profile is a health effects summary written in non-technical language. Its intended audience is the general public, especially people living in the vicinity of a hazardous waste site or chemical release. If the Public Health Statement were removed from the rest of the document, it would still communicate to the lay public essential information about the chemical.

The major headings in the Public Health Statement are useful to find specific topics of concern. The topics are written in a question and answer format. The answer to each question includes a sentence that will direct the reader to chapters in the profile that will provide more information on the given topic.

### Chapter 2

#### Relevance to Public Health

This chapter provides a health effects summary based on evaluations of existing toxicologic, epidemiologic, and toxicokinetic information. This summary is designed to present interpretive, weight-of-evidence discussions for human health end points by addressing the following questions:

1. What effects are known to occur in humans?
2. What effects observed in animals are likely to be of concern to humans?
3. What exposure conditions are likely to be of concern to humans, especially around hazardous waste sites?

The chapter covers end points in the same order that they appear within the Discussion of Health Effects by Route of Exposure section, by route (inhalation, oral, and dermal) and within route by effect. Human data are presented first, then animal data. Both are organized by duration (acute, intermediate, chronic). *In vitro* data and data from parenteral routes (intramuscular, intravenous, subcutaneous, etc.) are also considered in this chapter.

The carcinogenic potential of the profiled substance is qualitatively evaluated, when appropriate, using existing toxicokinetic, genotoxic, and carcinogenic data. ATSDR does not currently assess cancer potency or perform cancer risk assessments. Minimal Risk Levels (MRLs) for noncancer end points (if derived) and the end points from which they were derived are indicated and discussed.

Limitations to existing scientific literature that prevent a satisfactory evaluation of the relevance to public health are identified in the Chapter 3 Data Needs section.

#### Interpretation of Minimal Risk Levels

Where sufficient toxicologic information is available, ATSDR has derived MRLs for inhalation and oral routes of entry at each duration of exposure (acute, intermediate, and chronic). These MRLs are not meant to support regulatory action, but to acquaint health professionals with exposure levels at which adverse health effects are not expected to occur in humans.

## APPENDIX B

MRLs should help physicians and public health officials determine the safety of a community living near a chemical emission, given the concentration of a contaminant in air or the estimated daily dose in water. MRLs are based largely on toxicological studies in animals and on reports of human occupational exposure.

MRL users should be familiar with the toxicologic information on which the number is based. Chapter 2, "Relevance to Public Health," contains basic information known about the substance. Other sections such as Chapter 3 Section 3.9, "Interactions with Other Substances," and Section 3.10, "Populations that are Unusually Susceptible" provide important supplemental information.

MRL users should also understand the MRL derivation methodology. MRLs are derived using a modified version of the risk assessment methodology that the Environmental Protection Agency (EPA) provides (Barnes and Dourson 1988) to determine reference doses (RfDs) for lifetime exposure.

To derive an MRL, ATSDR generally selects the most sensitive end point which, in its best judgement, represents the most sensitive human health effect for a given exposure route and duration. ATSDR cannot make this judgement or derive an MRL unless information (quantitative or qualitative) is available for all potential systemic, neurological, and developmental effects. If this information and reliable quantitative data on the chosen end point are available, ATSDR derives an MRL using the most sensitive species (when information from multiple species is available) with the highest no-observed-adverse-effect level (NOAEL) that does not exceed any adverse effect levels. When a NOAEL is not available, a lowest-observed-adverse-effect level (LOAEL) can be used to derive an MRL, and an uncertainty factor (UF) of 10 must be employed. Additional uncertainty factors of 10 must be used both for human variability to protect sensitive subpopulations (people who are most susceptible to the health effects caused by the substance) and for interspecies variability (extrapolation from animals to humans). In deriving an MRL, these individual uncertainty factors are multiplied together. The product is then divided into the inhalation concentration or oral dosage selected from the study. Uncertainty factors used in developing a substance-specific MRL are provided in the footnotes of the levels of significant exposure (LSE) tables.

## **Chapter 3**

### **Health Effects**

#### **Tables and Figures for Levels of Significant Exposure (LSE)**

Tables and figures are used to summarize health effects and illustrate graphically levels of exposure associated with those effects. These levels cover health effects observed at increasing dose concentrations and durations, differences in response by species, MRLs to humans for noncancer end points, and EPA's estimated range associated with an upper-bound individual lifetime cancer risk of 1 in 10,000 to 1 in 10,000,000. Use the LSE tables and figures for a quick review of the health effects and to locate data for a specific exposure scenario. The LSE tables and figures should always be used in conjunction with the text. All entries in these tables and figures represent studies that provide reliable, quantitative estimates of NOAELs, LOAELs, or Cancer Effect Levels (CELs).

The legends presented below demonstrate the application of these tables and figures. Representative examples of LSE Table 3-1 and Figure 3-1 are shown. The numbers in the left column of the legends correspond to the numbers in the example table and figure.



## APPENDIX B

**LEGEND****See Sample LSE Table 3-1 (page B-6)**

- (1) **Route of Exposure.** One of the first considerations when reviewing the toxicity of a substance using these tables and figures should be the relevant and appropriate route of exposure. Typically when sufficient data exist, three LSE tables and two LSE figures are presented in the document. The three LSE tables present data on the three principal routes of exposure, i.e., inhalation, oral, and dermal (LSE Tables 3-1, 3-2, and 3-3, respectively). LSE figures are limited to the inhalation (LSE Figure 3-1) and oral (LSE Figure 3-2) routes. Not all substances will have data on each route of exposure and will not, therefore, have all five of the tables and figures.
- (2) **Exposure Period.** Three exposure periods—acute (less than 15 days), intermediate (15–364 days), and chronic (365 days or more)—are presented within each relevant route of exposure. In this example, an inhalation study of intermediate exposure duration is reported. For quick reference to health effects occurring from a known length of exposure, locate the applicable exposure period within the LSE table and figure.
- (3) **Health Effect.** The major categories of health effects included in LSE tables and figures are death, systemic, immunological, neurological, developmental, reproductive, and cancer. NOAELs and LOAELs can be reported in the tables and figures for all effects but cancer. Systemic effects are further defined in the "System" column of the LSE table (see key number 18).
- (4) **Key to Figure.** Each key number in the LSE table links study information to one or more data points using the same key number in the corresponding LSE figure. In this example, the study represented by key number 18 has been used to derive a NOAEL and a Less Serious LOAEL (also see the two "18r" data points in sample Figure 3-1).
- (5) **Species.** The test species, whether animal or human, are identified in this column. Chapter 2, "Relevance to Public Health," covers the relevance of animal data to human toxicity and Section 3.4, "Toxicokinetics," contains any available information on comparative toxicokinetics. Although NOAELs and LOAELs are species specific, the levels are extrapolated to equivalent human doses to derive an MRL.
- (6) **Exposure Frequency/Duration.** The duration of the study and the weekly and daily exposure regimens are provided in this column. This permits comparison of NOAELs and LOAELs from different studies. In this case (key number 18), rats were exposed to "Chemical x" via inhalation for 6 hours/day, 5 days/week, for 13 weeks. For a more complete review of the dosing regimen, refer to the appropriate sections of the text or the original reference paper (i.e., Nitschke et al. 1981).
- (7) **System.** This column further defines the systemic effects. These systems include respiratory, cardiovascular, gastrointestinal, hematological, musculoskeletal, hepatic, renal, and dermal/ocular. "Other" refers to any systemic effect (e.g., a decrease in body weight) not covered in these systems. In the example of key number 18, one systemic effect (respiratory) was investigated.
- (8) **NOAEL.** A NOAEL is the highest exposure level at which no harmful effects were seen in the organ system studied. Key number 18 reports a NOAEL of 3 ppm for the respiratory system, which was used to derive an intermediate exposure, inhalation MRL of 0.005 ppm (see footnote "b").

## APPENDIX B

- (9) LOAEL. A LOAEL is the lowest dose used in the study that caused a harmful health effect. LOAELs have been classified into "Less Serious" and "Serious" effects. These distinctions help readers identify the levels of exposure at which adverse health effects first appear and the gradation of effects with increasing dose. A brief description of the specific end point used to quantify the adverse effect accompanies the LOAEL. The respiratory effect reported in key number 18 (hyperplasia) is a Less Serious LOAEL of 10 ppm. MRLs are not derived from Serious LOAELs.
- (10) Reference. The complete reference citation is given in Chapter 9 of the profile.
- (11) CEL. A CEL is the lowest exposure level associated with the onset of carcinogenesis in experimental or epidemiologic studies. CELs are always considered serious effects. The LSE tables and figures do not contain NOAELs for cancer, but the text may report doses not causing measurable cancer increases.
- (12) Footnotes. Explanations of abbreviations or reference notes for data in the LSE tables are found in the footnotes. Footnote "b" indicates that the NOAEL of 3 ppm in key number 18 was used to derive an MRL of 0.005 ppm.

**LEGEND****See Sample Figure 3-1 (page B-7)**

LSE figures graphically illustrate the data presented in the corresponding LSE tables. Figures help the reader quickly compare health effects according to exposure concentrations for particular exposure periods.

- (13) Exposure Period. The same exposure periods appear as in the LSE table. In this example, health effects observed within the acute and intermediate exposure periods are illustrated.
- (14) Health Effect. These are the categories of health effects for which reliable quantitative data exists. The same health effects appear in the LSE table.
- (15) Levels of Exposure. Concentrations or doses for each health effect in the LSE tables are graphically displayed in the LSE figures. Exposure concentration or dose is measured on the log scale "y" axis. Inhalation exposure is reported in mg/m<sup>3</sup> or ppm and oral exposure is reported in mg/kg/day.
- (16) NOAEL. In this example, the open circle designated 18r identifies a NOAEL critical end point in the rat upon which an intermediate inhalation exposure MRL is based. The key number 18 corresponds to the entry in the LSE table. The dashed descending arrow indicates the extrapolation from the exposure level of 3 ppm (see entry 18 in the table) to the MRL of 0.005 ppm (see footnote "b" in the LSE table).
- (17) CEL. Key number 38m is one of three studies for which CELs were derived. The diamond symbol refers to a CEL for the test species-mouse. The number 38 corresponds to the entry in the LSE table.

## APPENDIX B

- (18) Estimated Upper-Bound Human Cancer Risk Levels. This is the range associated with the upper-bound for lifetime cancer risk of 1 in 10,000 to 1 in 10,000,000. These risk levels are derived from the EPA's Human Health Assessment Group's upper-bound estimates of the slope of the cancer dose response curve at low dose levels ( $q_1^*$ ).
- (19) Key to LSE Figure. The Key explains the abbreviations and symbols used in the figure.

## SAMPLE


1 → **Table 3-1. Levels of Significant Exposure to [Chemical x] – Inhalation**

Key to figure <sup>a</sup>	Species	Exposure frequency/ duration	System	NOAEL (ppm)	LOAEL (effect)		Reference
					Less serious (ppm)	Serious (ppm)	
2 → INTERMEDIATE EXPOSURE							
	5	6	7	8	9		10
3 → Systemic	↓	↓	↓	↓	↓		↓
4 → 18	Rat	13 wk 5 d/wk 6 hr/d	Resp	3 <sup>b</sup>	10 (hyperplasia)		Nitschke et al. 1981
CHRONIC EXPOSURE							
Cancer						11	
					↓		
38	Rat	18 mo 5 d/wk 7 hr/d			20	(CEL, multiple organs)	Wong et al. 1982
39	Rat	89–104 wk 5 d/wk 6 hr/d			10	(CEL, lung tumors, nasal tumors)	NTP 1982
40	Mouse	79–103 wk 5 d/wk 6 hr/d			10	(CEL, lung tumors, hemangiosarcomas)	NTP 1982

12 → <sup>a</sup> The number corresponds to entries in Figure 3-1.<sup>b</sup> Used to derive an intermediate inhalation Minimal Risk Level (MRL) of  $5 \times 10^{-3}$  ppm; dose adjusted for intermittent exposure and divided by an uncertainty factor of 100 (10 for extrapolation from animal to humans, 10 for human variability).

**SAMPLE**

**Figure 3-1. Levels of Significant Exposure to [Chemical X] - Inhalation**



\*\*\*DRAFT FOR PUBLIC COMMENT\*\*\*

APPENDIX B

This page is intentionally blank.

## APPENDIX C. ACRONYMS, ABBREVIATIONS, AND SYMBOLS

ACGIH	American Conference of Governmental Industrial Hygienists
ACOEM	American College of Occupational and Environmental Medicine
ADI	acceptable daily intake
ADME	absorption, distribution, metabolism, and excretion
AED	atomic emission detection
AFID	alkali flame ionization detector
AFOSH	Air Force Office of Safety and Health
ALT	alanine aminotransferase
AML	acute myeloid leukemia
AOAC	Association of Official Analytical Chemists
AOEC	Association of Occupational and Environmental Clinics
AP	alkaline phosphatase
APHA	American Public Health Association
AST	aspartate aminotransferase
atm	atmosphere
ATSDR	Agency for Toxic Substances and Disease Registry
AWQC	Ambient Water Quality Criteria
BAT	best available technology
BCF	bioconcentration factor
BEI	Biological Exposure Index
BMD	benchmark dose
BMR	benchmark response
BSC	Board of Scientific Counselors
C	centigrade
CAA	Clean Air Act
CAG	Cancer Assessment Group of the U.S. Environmental Protection Agency
CAS	Chemical Abstract Services
CDC	Centers for Disease Control and Prevention
CEL	cancer effect level
CELDS	Computer-Environmental Legislative Data System
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFR	Code of Federal Regulations
Ci	curie
CI	confidence interval
CL	ceiling limit value
CLP	Contract Laboratory Program
cm	centimeter
CML	chronic myeloid leukemia
CPSC	Consumer Products Safety Commission
CWA	Clean Water Act
DHEW	Department of Health, Education, and Welfare
DHHS	Department of Health and Human Services
DNA	deoxyribonucleic acid
DOD	Department of Defense
DOE	Department of Energy
DOL	Department of Labor
DOT	Department of Transportation
DOT/UN/ NA/IMDG	Department of Transportation/United Nations/ North America/Intergovernmental Maritime Dangerous Goods Code

## APPENDIX C

DWEL	drinking water exposure level
ECD	electron capture detection
ECG/EKG	electrocardiogram
EEG	electroencephalogram
EEGL	Emergency Exposure Guidance Level
EPA	Environmental Protection Agency
F	Fahrenheit
F <sub>1</sub>	first-filial generation
FAO	Food and Agricultural Organization of the United Nations
FDA	Food and Drug Administration
FEMA	Federal Emergency Management Agency
FIFRA	Federal Insecticide, Fungicide, and Rodenticide Act
FPD	flame photometric detection
fpm	feet per minute
FR	Federal Register
FSH	follicle stimulating hormone
g	gram
GC	gas chromatography
gd	gestational day
GLC	gas liquid chromatography
GPC	gel permeation chromatography
HPLC	high-performance liquid chromatography
HRGC	high resolution gas chromatography
HSDB	Hazardous Substance Data Bank
IARC	International Agency for Research on Cancer
IDLH	immediately dangerous to life and health
ILO	International Labor Organization
IRIS	Integrated Risk Information System
K <sub>d</sub>	adsorption ratio
kg	kilogram
kgg	metric ton
K <sub>oc</sub>	organic carbon partition coefficient
K <sub>ow</sub>	octanol-water partition coefficient
L	liter
LC	liquid chromatography
LC <sub>50</sub>	lethal concentration, 50% kill
LC <sub>Lo</sub>	lethal concentration, low
LD <sub>50</sub>	lethal dose, 50% kill
LD <sub>Lo</sub>	lethal dose, low
LDH	lactic dehydrogenase
LH	lutinizing hormone
LOAEL	lowest-observed-adverse-effect level
LSE	Levels of Significant Exposure
LT <sub>50</sub>	lethal time, 50% kill
m	meter
MA	<i>trans,trans</i> -muconic acid
MAL	maximum allowable level
mCi	millicurie
MCL	maximum contaminant level
MCLG	maximum contaminant level goal
MF	modifying factor



## APPENDIX C

MFO	mixed function oxidase
mg	milligram
mL	milliliter
mm	millimeter
mmHg	millimeters of mercury
mmol	millimole
mppcf	millions of particles per cubic foot
MRL	Minimal Risk Level
MS	mass spectrometry
NAAQS	National Ambient Air Quality Standard
NAS	National Academy of Science
NATICH	National Air Toxics Information Clearinghouse
NATO	North Atlantic Treaty Organization
NCE	normochromatic erythrocytes
NCEH	National Center for Environmental Health
NCI	National Cancer Institute
ND	not detected
NFPA	National Fire Protection Association
ng	nanogram
NHANES	National Health and Nutrition Examination Survey
NIEHS	National Institute of Environmental Health Sciences
NIOSH	National Institute for Occupational Safety and Health
NIOSHTIC	NIOSH's Computerized Information Retrieval System
NLM	National Library of Medicine
nm	nanometer
nmol	nanomole
NOAEL	no-observed-adverse-effect level
NOES	National Occupational Exposure Survey
NOHS	National Occupational Hazard Survey
NPD	nitrogen phosphorus detection
NPDES	National Pollutant Discharge Elimination System
NPL	National Priorities List
NR	not reported
NRC	National Research Council
NS	not specified
NSPS	New Source Performance Standards
NTIS	National Technical Information Service
NTP	National Toxicology Program
ODW	Office of Drinking Water, EPA
OERR	Office of Emergency and Remedial Response, EPA
OHM/TADS	Oil and Hazardous Materials/Technical Assistance Data System
OPP	Office of Pesticide Programs, EPA
OPPT	Office of Pollution Prevention and Toxics, EPA
OPPTS	Office of Prevention, Pesticides and Toxic Substances, EPA
OR	odds ratio
OSHA	Occupational Safety and Health Administration
OSW	Office of Solid Waste, EPA
OTS	Office of Toxic Substances
OW	Office of Water
OWRS	Office of Water Regulations and Standards, EPA
PAH	polycyclic aromatic hydrocarbon

## APPENDIX C

PBPD	physiologically based pharmacodynamic
PBPK	physiologically based pharmacokinetic
PCE	polychromatic erythrocytes
PEL	permissible exposure limit
pg	picogram
PHS	Public Health Service
PID	photo ionization detector
pmol	picomole
PMR	proportionate mortality ratio
ppb	parts per billion
ppm	parts per million
ppt	parts per trillion
PSNS	pretreatment standards for new sources
RBC	red blood cell
REL	recommended exposure level/limit
RfC	reference concentration
RfD	reference dose
RNA	ribonucleic acid
RQ	reportable quantity
RTECS	Registry of Toxic Effects of Chemical Substances
SARA	Superfund Amendments and Reauthorization Act
SCE	sister chromatid exchange
SGOT	serum glutamic oxaloacetic transaminase
SGPT	serum glutamic pyruvic transaminase
SIC	standard industrial classification
SIM	selected ion monitoring
SMCL	secondary maximum contaminant level
SMR	standardized mortality ratio
SNARL	suggested no adverse response level
SPEGL	Short-Term Public Emergency Guidance Level
STEL	short term exposure limit
STORET	Storage and Retrieval
TD <sub>50</sub>	toxic dose, 50% specific toxic effect
TLV	threshold limit value
TOC	total organic carbon
TPQ	threshold planning quantity
TRI	Toxics Release Inventory
TSCA	Toxic Substances Control Act
TWA	time-weighted average
UF	uncertainty factor
U.S.	United States
USDA	United States Department of Agriculture
USGS	United States Geological Survey
VOC	volatile organic compound
WBC	white blood cell
WHO	World Health Organization

## APPENDIX C

>	greater than
≥	greater than or equal to
=	equal to
<	less than
≤	less than or equal to
%	percent
α	alpha
β	beta
γ	gamma
δ	delta
μm	micrometer
μg	microgram
q <sub>1</sub> *	cancer slope factor
-	negative
+	positive
(+)	weakly positive result
(-)	weakly negative result

APPENDIX C

This page is intentionally blank.

## APPENDIX D. INDEX

absorbed dose.....	94, 96, 99, 101, 111, 114, 116, 121
acetylcholinesterase .....	116
adipose tissue .....	93, 133, 161, 187, 193
adsorbed .....	160, 183, 198
adsorption.....	9, 153, 193
aerobic.....	9, 151, 162, 165, 166
alanine aminotransferase (see ALT) .....	11
ALT (see alanine aminotransferase) .....	11, 26, 27, 80, 129
ambient air .....	9, 10, 122, 169, 170, 176
anaerobic .....	151, 153, 165, 166
bioaccumulation .....	161, 179, 186
bioavailability .....	160, 161, 183, 186, 189
bioconcentration factor .....	161
biodegradation.....	136, 151, 162, 165, 167
biomarker .....	120, 121, 133
biomarkers .....	120, 121, 122, 123, 133, 135, 191, 200
body weight effects .....	64
breast milk.....	4, 120, 135, 161, 179, 181, 183, 187
cancer .....	4, 14, 72, 106, 107, 110, 119
carcinogen .....	14, 206, 209
carcinogenic .....	14, 16, 29, 31, 72, 83, 130, 206, 209
carcinogenicity .....	14, 72, 83, 115, 130, 206, 209
carcinoma .....	23, 72, 73
carcinomas .....	62, 73
cardiovascular .....	33, 59, 73, 84
Cardiovascular Effects .....	59, 80
chromosomal aberrations .....	88
clearance .....	18, 20, 23, 90, 103, 108, 115
death.....	4, 31, 32, 33, 73, 84
dermal effects.....	33, 84
DNA.....	86, 87, 88, 115, 121
dopamine.....	115
elimination half-time.....	18, 20, 23, 115
elimination rate .....	100
endocrine.....	21, 33, 63, 73, 84, 117, 118
endocrine effects .....	63
estrogenic .....	118
fetus.....	118
Gastrointestinal Effects .....	59
general population.....	10, 120, 153, 178, 183, 187, 188, 200
genotoxic.....	31, 86, 88, 115, 130
genotoxicity.....	88, 131
germinal epithelium .....	68
groundwater .....	2, 134, 136, 151, 153, 158, 159, 160, 165, 167, 174, 175, 178, 183, 186
growth retardation.....	71
half-life.....	9, 90, 121, 151, 159, 162
hematological effects .....	10, 59, 60, 65, 72, 80, 129, 130
hepatic effects .....	26, 60, 61, 80, 81, 122
hydrolysis.....	162

## APPENDIX D

hydroxyl radical .....	9, 151, 159, 161
immune system .....	131
immunological .....	31, 65, 81, 131
immunological effects.....	81, 131
K <sub>ow</sub> .....	113, 141, 160, 161
LD <sub>50</sub> .....	73, 84
lymphoreticular .....	65
metabolic effects .....	33, 73, 84
micronuclei .....	86, 87
milk .....	92, 120, 122, 136, 187, 192, 193
musculoskeletal effects .....	60
neonatal .....	116, 183
neoplasm .....	14, 72
neoplastic .....	73
neurobehavioral.....	118
neurodevelopmental.....	131
neurophysiological.....	20
nuclear.....	63
ocular effects.....	14, 86
partition coefficients .....	18, 20, 24, 90, 105, 109, 114, 115
pharmacodynamic .....	102
pharmacokinetic.....	101, 102, 104, 117, 120, 134, 183
pharmacokinetics .....	18, 20, 23, 118, 135
photolysis .....	9, 151, 162
placenta .....	120, 135
rate constant .....	111, 113, 161
renal effects.....	26, 62, 81
retention .....	90, 91, 93
salivation.....	11, 22, 25, 66
solubility .....	160
thyroid.....	23, 33, 63, 130
toxicokinetic.....	31
tumors .....	4, 14, 62, 72, 83, 130
vapor phase .....	151, 159, 161
vapor pressure .....	9, 159, 183, 186
volatilization .....	9, 153, 159, 162, 167
weanlings .....	92

